

HIBBARD

PLUMBING SUPPLIES

The Finest Quality
Your Money
Can Buy

♦ For Your Home ♦



HIBBARD SPENCER BARTLETT & CO.
CHICAGO

Digitized by:

The Association for Preservation Technology




From the collection of:

Floyd Mansberger
Fever River Research
www.IllinoisArchaeology.com

"CLOSE-UP" of Mr. Smith's opinion of Hibbard's Plumbing Catalog


*and every day, more and more Plumbers
are echoing the opinion of Mr. Smith*



and...

NOW IT'S BETTER THAN EVER! *with
many illustrations in beautiful NATURAL COLORS!*

WHICH of these men



THANKS FOR
SHOWING ME
WHAT YOU HAVE
-I'LL LET YOU
KNOW LATER!

This man

has a prospective customer who is in the market for a complete new bathroom outfit.

He buys his plumbing materials from a number of sources and must consult a variety of catalogs and price lists. This method requires much time, confuses the customer who cannot visualize the completed room — and many times results in the remark:

—“Well, I’ll let you know later”—

THE OLD FASHIONED WAY

You have lost, and are losing, sales because the old method is no longer satisfactory and the customer who promised to, never came back.

Would you buy a suit of clothes if it was not priced and the dealer who showed it to you said that he had to figure the price of the coat, the price of the vest, the price of the trousers, and he needed time to do this? Would you feel like buying from him after waiting twenty minutes? You would probably say, “I will come back later,” but you would never come back, because you decided, while you were waiting, that because his merchandise was not priced and he had to spend so much time before he could quote, that the price he gave you might not be correct.

Because Plumbers Who Do Not Buy From **Hibbard**’s Have to Figure Their Prices This Way They Lose Many Sales, and in Many Cases, if They Make a Sale, They Have Lost Their Profit Because of Some Error They Made When Quoting.

Be Successful—Use The NEW *Hibbard*

would YOU rather Be?..


This man

has a prospect who wants to completely modernize her bathroom.

He shows her a copy of the Hibbard Retail Priced Catalog, with its New Actual Color Illustrations of complete bathrooms.

She sees and compares styles and prices. A selection is made—and he adds F.O.B. and installation charges to the price shown—and the deal is closed.

—That's the Modern Way to SELL!



THIS IS THE Hibbard WAY

NO WAITING, NO PRICE GUESSING, NO DISSATISFIED CUSTOMERS—because the HIBBARD CATALOG is so simple and complete that anyone can sell from it.

It shows more than thirty different styles of Bath Room Sets in all price classes and styles, all beautifully illustrated, many in actual colors, and all priced completely in plain figures.

This means EASY SALES, SATISFIED AND PLEASED CUSTOMERS AND A GUARANTEED PROFIT, because you cannot lose on sales you make when you sell HIBBARD PLUMBING FROM HIBBARD'S COMPLETELY PRICED PLUMBING CATALOG.

Retail Plumbing Catalog To Help You Sell

PROFIT-

as others are doing
with the **HIBBARD Merchandising Plan**



NO OTHER COMPANY OFFERS ALL OF THESE:

COMPLETE DEALER AND RETAIL CATALOG

Enables You and Your customer to SEE ALL—KNOW ALL—No guesswork! Bathrooms shown in beautiful colors, plainly priced. You add Installation Costs and your freight costs, from our warehouse to your store. Customer gets the complete story at a glance. **YOU GET THE BUSINESS!**

**BUY ALL YOUR
PLUMBING NEEDS
FROM ONE SOURCE
OF SUPPLY.**

**THIS ENABLES YOU
TO DEVOTE MORE
OF YOUR TIME TO
SELLING.**

STORE DISPLAYS AND ADVERTISING HELPS

Beautiful Window and Counter Displays To Help You Sell. They have irresistible appeal. Get them up in your windows and see the customers—STOP—LOOK—READ! Then they will come in your store to BUY from this SELLING CATALOG.

Aggressive Dealers Advertise—We furnish you with the Mats.


SATISFACTION GUARANTEED

We guarantee the Hibbard line of Plumbing to be equal in quality, finish and beauty to any other make. You make no exceptions, our returns of defective ware are below the average for the industry.


This guarantee is backed, not only by the manufacturer who makes our ware, but also by our own company, with a continuous business record of over eighty years and assets of over one million dollars. If we have stayed in business for over eighty years and continue to grow, it means that we must have satisfied not only our customers but also the consumer who has been using Hibbard PRODUCTS.



HIBBARD, SPENCER, BARTLETT & Co.
CHICAGO.




THE *Hibbard Elite* BATHROOM SET




LARGE, ROOMY SHELF BACK, PROTECTS WALL, IDEAL FOR TUMBLER, COSMETICS, ETC.

BETTER QUALITY, GREATER CONVENIENCE AND MODERN DESIGN . . . ACID-RESISTING


NO INCREASE IN PRICE over regular cast iron plumbing ware. Made in the modern manner, utilizing the new manufacturing methods and sound metallurgical developments that have come to light within the past decade.




ACID-RESISTING, NOT AFFECTED BY MEDICINE, LOTIONS, DYES OR FRUIT JUICES.



RAISED EDGE ON ENTIRE RIM OF LAVATORY PREVENTS OVERFLOW, PROTECTS THE PERSON AND FLOOR.




CHROMIUM PLATED, TUBULAR BRASS LEGS, ADJUSTABLE TO HEIGHT OF LAVATORY. PERMANENT SUPPORT, MORE KNEE ROOM.



CHROMIUM PLATED, ART DESIGN HEAVY BRASS FITTINGS ON TUB, LAVATORY AND CLOSET.




THREE COATS OF ACID-RESISTING PORCELAIN ENAMEL, MILK WHITE FINISH, UNIFORM TEXTURE. ABSOLUTELY GUARANTEED.



AUTOMATIC BATH TUB WASTE WITH FINGER-TIP CONTROL. INSTANT ACTING. NO COMPLICATED PARTS TO GET OUT OF ORDER.

Hibbard *Elite* BATHROOM SETS



ACID-RESISTING ENAMEL AT NO EXTRA COST

GREATER STRENGTH WITH HALF THE WEIGHT — EASIER TO HANDLE — CHEAPER TO INSTALL

DELIVERED FREE


FULL FREIGHT ALLOWED TO ANY DESTINATION

- Modern Streamline Design Tub—
Beautiful clear white finish. To match other fixtures.
- Large Shelf Type Lavatory—20 in. wide, 24 in. long.
Ideal for holding tumbler, cosmetics, etc.
Heavy chromium legs.
- New Era Washdown Closet of latest design.
- White Enameled Seat, guaranteed for 5 years.
- Chromium plated heavy brass plated fittings, pop-up waste on lavatory, trip-lever waste on tub.


No. W37LD0—5 ft. right hand.....each \$89.95
No. W037LD0—5 ft. left hand.....each 89.95
W't per set 385 lbs.

SET CONSISTS OF—
W216ALD0—BATH TUB
W350ULD0—LAVATORY
W17LD0—CLOSET

With Fittings to Floor.....add \$1.50



THE *Hibbard Commander* BATHROOM SET




ACID-RESISTING, NOT AFFECTED BY MEDICINES, LOTIONS, DYES OR FRUIT JUICES.


BEAUTIFUL AND MODERN IN DESIGN, LIGHTER, MORE WEAR-RESISTING PLUMBING FIXTURES. MEETS THE MOST EXACTING REQUIREMENTS.




LARGE ROOMY SHELF BACK, PROTECTS WALL AND IS IDEAL FOR TUMBLER, COSMETICS, ETC.



Built with the strength of an automobile chassis, 12-gauge steel drawn to uniform thickness throughout. One-piece, braced at ends for extra strength, raised flange for plastering prevents unsightly cracks and makes a water-tight joint between tub and wall. Easier to install due to being only one-third the weight of ordinary tub.



SHELF TYPE TANK COVER WITH RAISED EDGE PRESENTS A VARIETY OF USES.




SIMPLICITY OF DESIGN TO MATCH MODERN TRENDS IN DECORATION. MATCHES CLOSET AND LAVATORY IN EVERY DETAIL.



THREE COATS OF ACID RESISTING PORCELAIN ENAMEL, MILK WHITE FINISH, UNIFORM TEXTURE. ABSOLUTELY GUARANTEED.

Hibbard Commander BATHROOM SETS



ACID-RESISTING ENAMEL AT NO EXTRA COST
 GREATER STRENGTH WITH HALF THE WEIGHT — EASIER TO HANDLE — CHEAPER TO INSTALL

DELIVERED FREE

FULL FREIGHT ALLOWED TO ANY DESTINATION

- Modern Streamline Design Tub—
Beautiful clear white finish. To match other fixtures.
- Large Shelf Type Lavatory—20 in. wide, 24 in. long.
Ideal for holding tumbler, cosmetics, etc.
- New Era Washdown Close of newest design.
- White Enameled Seat, guaranteed for 5 years.
- Chromium plated heavy brass plated fittings, pop-up waste on lavatory, trip-lever waste on tub.

No. W38LD0 — 5 ft. right hand.....each \$87.75
 No. W038LD0 — 5 ft. left hand.....each 87.75

W't set 375 lbs.



SET CONSISTS OF—
 W216ALD0—BATH TUB
 W345ULD0—LAVATORY
 W17LD0—CLOSET




Prices Net F.O.B. Chicago, Add Freight to _____

THE *Hibbard Beauty* BATHROOM SET


Note the charming, colorful design of the bathroom as a whole, and the modern beauty and simplicity of each individual fixture. Has much the same atmosphere as a lady's boudoir yet it is a practical arrangement and with its straight line fixtures is equally suitable as the Master's Bathroom.



Chromium Plated, Heavy Cast Brass Adjustable Legs of Hexagon Design. Complete with Large Hexagon Design Towel Racks and Wall Flange.



Chromium Plated Brass, Self-Cleaning Shower Head with Adjustable Spray. A finer, more concentrated stream, less Splash.




Quiet Action Genuine Vitreous China Closet. Close Coupled, No Exposed Connections. Shelf Top Tank. Mother-of-Pearl Celluloid Seat and Cover Guaranteed for Five Years.



Vanity dressing table of gleaming genuine vitreous china. Smooth hard lustrous surface, easily kept clean. Large roomy top with raised edge to prevent toilet articles from slipping off. Chromium plated brass legs, hexagon design, adjustable in height. Especially designed to conform with today's modern trends.

Hibbard Beauty BATHROOM SETS



COMPLETE WITH RECESS TUB, SHOWER AND DRESSING TABLE

BENCH NOT INCLUDED. FOR PRICES SEE PAGE 810B

- Modern Colonial Design Tub—Beautiful lasting finish.
- Vitreous China Lavatory—Size 20 in. wide, 24 in. long.
Not affected by acids.
Adjustable chromium legs and large chromium towel racks.
- Vitreous China Dressing Table—size 30 in. long, 18 in. wide.
Large, roomy, with plenty of space for cosmetics, etc. Adjustable chromium legs.
- Beautiful new-unit type closet—Mother of Pearl finished seat. Quiet—no exposed connections.
- Shower has adjustable self-cleaning head.

SET CONSISTS OF: W26RLD0—BATH TUB, W1097CLD0—LAVATORY, W4475LD0—DRESSING TABLE, W25LD0—CLOSET.

ART DESIGN FITTINGS

HEAVILY CHROMIUM PLATED—LUSTROUS—BEAUTIFUL—REQUIRE NO POLISHING. COMPRESSION TYPE WITH RENEWABLE SEAT. SOLID BRASS THROUGHOUT.

★Items Marked Thus ★ Are Shipped from Factory Only

White


W96LD0—Right Hand Fittings	
W096LD0—Left Hand Fittings	
4½ ft. Tub, w't 700 lbs.....set	\$199.35
5 ft. Tub, w't 730 lbs.....set	202.75
5½ ft. Tub, w't 760 lbs.....set	208.25

Acid Resisting White

W960LD0—Right Hand Fittings	
W0960LD0—Left Hand Fittings	
4½ ft. Tub, w't 700 lbs.....set	\$202.55
5 ft. Tub, w't 730 lbs.....set	206.35
5½ ft. Tub, w't 760 lbs.....set	210.75

Acid Resisting Colors


F960½LD0—Right Hand Fittings	
F0960½LD0—Left Hand Fittings	
4½ ft. Tub, w't 700 lbs.....set	\$253.25★
5 ft. Tub, w't 730 lbs.....set	257.95★
5½ ft. Tub, w't 760 lbs.....set	263.45★
With Fittings to Flooradd \$1.50



Prices Net, Stock Items F.O.B. Chicago. ★F.O.B. Ohio Factory, Add Freight to _____

THE *Hibbard Embassy* BATHROOM SET

Built-in Seat at end. Safety is the keynote of this Tub.




Large Side Seat makes foot baths no longer a task.




THE EMBASSY TUB HAS TWO CONVENIENT SEATS

Practical—is the word that describes this attractive tub. The straight, modern lines . . . the easily matched fixtures . . . the Lavatory with convenient steel cabinet . . . all add to its desirability.


IDEAL FOR THE ELDERLY AND VERY YOUNG.
EXTRA BATHING SPACE — EXTRA SAFETY.



ACID-RESISTING, NOT EFFECTED BY MEDICINE, LOTIONS, DYES OR FRUIT STAIN.




QUIET ACTION, GENUINE VITREOUS CHINA CLOSET. CLOSE COUPLED, NO EXPOSED CONNECTIONS. SHELF TOP TANK. MOTHER-OF-PEARL CELLULOID SEAT AND COVER. GUARANTEED FOR FIVE YEARS.




RECESSED BASE GIVES PLENTY OF TOE ROOM.

STEEL ENAMELED CABINET HAS TWO LARGE SPACIOUS SHELVES, FOR STORING SOAP, TOWEL, AND OTHER SUPPLIES. UTILIZES SPACE FORMERLY WASTED.

Heavy steel cabinet finished in white durable enamel with contrasting black steel base. Door is attractively decorated with chromium lines and black and chrome pull.



Hibbard *Embassy* BATHROOM SETS



COMPLETE WITH RECESS TUB AND SHOWER

- Latest Design Embassy Seat Type Tub—Roomy—convenient seats at end and side. Flat bottom prevents slipping. Built-in soap dishes.
- Vitreous China Lavatory, 24 in. long, 20 in. wide. Not affected by acids—will always retain its beautiful glossy finish. Handy Cabinet for storing towels, cosmetics, etc.
- Beautiful unit type closet—Mother of Pearl finished seat. Quiet—no exposed connections.
- Shower has self-cleaning adjustable head.
- Shower curtain of genuine Rayon Silk.

ART DESIGN FITTINGS

Heavily chromium plated—lustrous—beautiful—require no polishing.



Tub measures 65 in. long, 32 in. wide, 18½ in. high, lavatory measures 24 in. long, 20 in. wide, w't per set 675 lbs.

White

W89LD0—Right Hand Fittings.....set \$155.40

W089LD0—Left Hand Fittings.....set 155.40

Acid Resisting White

W89OLD0—Right Hand Fittings.....set \$165.45

W089OLD0—Left Hand Fittings.....set 165.45

With Fittings to Floor.....add \$1.50

SET CONSISTS OF


W146RLD0—BATH TUB
W1095CLD0—LAVATORY
W25LD0—CLOSET

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Prices Net F.O.B. Chicago, Add Freight to _____



OUR VERY BEST BATHROOM SETS



COMPLETE WITH RECESSED TUB AND SHOWER

Tub measures 65 in. long, 32 in. wide, 18½ in. high.
Lavatory measures 24 in. long, 20 in. wide, w't 650 lbs.

- Latest Design Embassy Seat Type Tub—
- Roomy—convenient seats at end and side. Flat bottom prevents slipping. Built-in soap dishes.
- Vitreous China Lavatory, 24 in. long, 20 in. wide—not affected by acids—Will always retain its beautiful glossy finish. Plenty of space for cosmetics, etc.
- Beautiful unit type closet—Mother of Pearl finished seat. Quiet—no exposed connections.
- Shower has self-cleaning adjustable head.
- Shower curtain of genuine Rayon Silk.

White

W95LD0—Right Hand Fittings.....set \$152
W095LD0—Left Hand Fittings.....set 152

Acid Resisting White

W950LD0—Right Hand Fittings.....set \$162
W0950LD0—Left Hand Fittings.....set 162

With Fittings to Floor.....add \$1

ART DESIGN FITTINGS

Heavily chromium plated—lustrous—beautiful—require no polishing.




SET CONSISTS OF

W146RLD0—BATH TUB
W1098CLD0—LAVATORY
W25LD0—CLOSET

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard Mode BATHROOM SETS



COMPLETE WITH RECESS TUB AND SHOWER

Tub measures 65 in. long, 32 in. wide, 18½ in. high, lavatory measures 24 in. long, 20 in. wide, w't per set 725 lbs.

- Latest Design Embassy Seat Type Tub—
- Roomy—convenient seats at end and side. Flat bottom prevents slipping. Built-in soap dishes.
- Colonial Design Pedestal Lavatory with deep apron, 24 in. long, 20 in. wide. Matches tub perfectly in finish and design.
- Beautiful unit type closet—Mother of Pearl finished seat. Quiet—no exposed connections.
- Shower has self-cleaning adjustable head.
- Shower curtain of genuine Rayon Silk.

White

W91LD0—Right Hand Fittings.....set \$148.40

W091LD0—Left Hand Fittings.....set 148.40

Acid Resisting White

W910LD0—Right Hand Fittings.....set \$161.45

W0910LD0—Left Hand Fittings.....set 161.45

With Fittings to Floor.....add \$1.50

ART DESIGN FITTINGS

Heavily chromium plated—lustrous—beautiful—require no polishing.



SET CONSISTS OF

W146RLD0—BATH TUB
W40CLD0—LAVATORY
W25LD0—CLOSET


ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Prices Net F.O.B. Chicago, Add Freight to _____

THE *Hibbard Vanity* POWDER ROOM SET

The Powder Room



AN IMPORTANT ACCESSORY TO THE MODERN HOME




PLAN ABOVE SHOWS
TYPICAL LOCATION OF
THE POWDER ROOM

Most homes have a closet which can easily be converted into a "Powder Room" without a great deal of inconvenience or expense. Requires very little room, meets the need for extra toilet facilities when entertaining guests.


Chromium Plated,
Heavy Cast Brass Ad-
justable Legs of Hexa-
gon Design. Complete
with Large Hexagon
Design Towel Racks
and Wall Flange.



Shelf back on lavatory pro-
tects wall and is ideal for
tumbler, cosmetics, etc.
Raised edge prevents articles
from slipping off.



Chromium Plated Brass,
Compact Lavatory Fixture
with Finger-Tip Control
Pop-Up Drain. Recessed
Back Allows More Bowl
Space.



Quiet Action, Genuine Vitreous
China Closet. Close Coupled.
No Exposed Connections. She-
Top Tank. Mother-of-Pearl Cel-
luloid Seat and Cover. Guarant-
teed for Five Years.

Hibbard *Vanity* POWDER ROOM SETS



COMPLETE WITH SHELF TYPE LAVATORY AND DRESSING TABLE

BENCH NOT INCLUDED. FOR PRICES SEE PAGE 810B

- Large Shelf Type Lavatory—21 in. long, 18 in. wide.
Ideal for holding tumbler, cosmetics, etc.
Heavy chromium legs—Large chromium towel racks.
- Beautiful new-unit type closet—
Mother of Pearl finished seat. Quiet—no exposed connections.
- Vitreous China Dressing Table, 30 in. long, 18 in. wide.
Large, roomy, with plenty of space for cosmetics, etc. Adjustable chromium legs.

ART DESIGN FITTINGS

Heavily chromium plated—lustrous—beautiful—require no polishing.



Acid Resisting White

W97LD0—POWDER ROOM SET,
set\$125.95

Acid Resisting in Colors

F97½LD0—POWDER ROOM SET,
set\$157.45★

With Fittings to Floor.....add \$1.50


SET CONSISTS OF

W1552½MLD0—LAVATORY
W4475LD0—DRESSING TABLE
W25LD0—CLOSET

THE *Hibbard Charm* BATHROOM SET

LATEST DESIGN SEAT TYPE TUB

Built-in seat at end.
Safety is the keynote
of this tub.




Large side seat makes
footbaths no longer a
task, but a pleasure.




LOWERED RIM AT SIDE FOR EASIER
ACCESS. FOR THE ELDERLY, THE
VERY YOUNG. ESPECIALLY SUITED
FOR BATHING CHILDREN.


WIDER, FLATTER BOTTOM FOR
GREATER SAFETY AND EXTRA
BATHING SPACE. ELIMINATES
DANGEROUS ACCIDENTS



Large shelf back on lavatory
protects wall and is ideal for
holding tumbler, cosmetics,
etc.



Quiet action genuine vitre-
ous china closet. Close coup-
led, no exposed connections.
Shelf top tank. Mother-of-
pearl celluloid seat and
cover, guaranteed for five
years.



Chromium plated heavy cast
brass adjustable legs of hex-
agon design. Complete with
large hexagon design towel
racks and wall flanges.



- Latest Design Embassy Seat Type Tub—
- Roomy—convenient seats at end and side. Flat bottom prevents slipping. Built-in soap dishes.
- Large Shelf Type Lavatory—21 in. long, 12 in. wide. Ideal for holding tumbler, cosmetics, etc. Heavy adjustable chromium legs with chromium towel racks.
- Beautiful unit type closet—Mother of Pearl finished seat. Quiet—no exposed connections.
- Shower has self-cleaning adjustable head.
- Shower curtain of genuine Rayon Silk.

COMPLETE WITH RECESS TUB AND SHOWER

Tub measures 65 in. long, 32 in. wide, 18½ in. high, lavatory measures 21 in. long, 18 in. wide, w't per set 675 lbs.

White

W92LD0—Right Hand Fittings.....set \$151.25
W092LD0—Left Hand Fittings.....set 151.25

Acid Resisting White

W920LD0—Right Hand Fittings.....set \$164.25
W0920LD0—Left Hand Fittings.....set 164.25

Acid Resisting Colors

F920½LD0—Right Hand Fittings.....set \$205.35★
F0920½LD0—Left Hand Fittings.....set 205.35★

In Ordering Specify Color

With Fittings to Floor.....add \$1.50




SET CONSISTS OF
W146RLD0 — BATH TUB. W1552MLD0 — LAVATORY.
W25LD0—CLOSET.

ART DESIGN FITTINGS

HEAVILY CHROMIUM PLATED—LUSTROUS—BEAUTIFUL—REQUIRE NO POLISHING. COMPRESSION TYPE WITH RENEWABLE SEAT. SOLID BRASS THROUGHOUT.

Hibbard *Vogue* BATHROOM SETS



COMPLETE WITH RECESS TUB AND SHOWER

White

- Modern Colonial Design Tub—Beautiful clear white finish.
- Vitreous China Pedestal Type Lavatory—27 in. long, 22 in. wide. Extra large, roomy, with plenty of space for tumblers, cosmetics, etc. Not affected by acids.
- Beautiful new-unit type closet—Mother of Pearl finished seat. Quiet—no exposed connections.
- Shower has adjustable self-cleaning head.
- Shower curtain of genuine Rayon Silk.

W14LD0—Right Hand Fittings	
W014LD0—Left Hand Fittings	
4½ ft. Tub, w't 700 lbs.....set	\$148.55
5 ft. Tub, w't 730 lbs.....set	151.85
5½ ft. Tub, w't 760 lbs.....set	157.35

Acid Resisting White

W140LD0—Right Hand Fittings	
W0140LD0—Left Hand Fittings	
4½ ft. Tub, w't 700 lbs.....set	\$154.75
5 ft. Tub, w't 730 lbs.....set	158.55
5½ ft. Tub, w't 760 lbs.....set	164.95

With Fittings to Floor.....add \$1.50

ART DESIGN FITTINGS

Heavily chromium plated—lustrous—beautiful—require no polishing.



SET CONSISTS OF

W26RLD0—BATH TUB
W3300CLD0—LAVATORY
W25LD0—CLOSET

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard Vogue BATHROOM SETS



COMPLETE WITH CORNER TUB AND SHOWER

- Modern Colonial Design Tub—Beautiful clear white finish.
- Vitreous China Pedestal Type Lavatory—27 in. long, 22 in. wide. Extra large, roomy, with plenty of space for tumblers, cosmetics, etc. Not affected by acids.
- Beautiful new-unit type closet—Mother of Pearl finished seat. Quiet—no exposed connections.
- Shower has adjustable self-cleaning head.
- Shower curtain of genuine Rayon Silk.

White

W15LD0—Right Hand Fittings

W015LD0—Left Hand Fittings

5 ft. Tub, w't 760 lbs.....set \$160.00

5½ ft. Tub, w't 810 lbs.....set 166.45

Acid Resisting White

W150LD0—Right Hand Fittings

W0150LD0—Left Hand Fittings

5 ft. Tub, w't 760 lbs.....set \$167.45

5½ ft. Tub, w't 810 lbs.....set 174.95

With Fittings to Floor.....add \$1.50

ART DESIGN FITTINGS

Heavily chromium plated—lustrous—beautiful—require no polishing.



SET CONSISTS OF

W20RLD0—BATH TUB


W3300CLD0—LAVATORY

W25LD0—CLOSET

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard Royale BATHROOM SETS



COMPLETE . . . WITH RECESS TUB AND SHOWER

- Modern Colonial Design Tub—Beautiful clear white finish.
- Large Shelf Type Lavatory—21 in. long, 18 in. wide.
Ideal for holding tumbler, cosmetics, etc.
Heavy chromium legs.
- Beautiful new-unit type closet—Mother of Pearl finished seat. Quiet—no exposed connections.
- Shower has adjustable self-cleaning head.
- Shower curtain of genuine Rayon Silk.

SET CONSISTS OF W26RLD0—BATH TUB. W1550MLD0—LAVATORY. W25LD0—CLOSET.



ART DESIGN FITTING

Heavily chromium plated—
— beautiful — require no paint

White


W93LD0—Right Hand Fittings
W093LD0—Left Hand Fittings
4½ ft. Tub, w't 700 lbs. set
5 ft. Tub, w't 730 lbs. set
5½ ft. Tub, w't 760 lbs. set

Acid Resisting White

W930LD0—Right Hand Fittings
W0930LD0—Left Hand Fittings
4½ ft. Tub, w't 700 lbs. set
5 ft. Tub, w't 730 lbs. set
5½ ft. Tub, w't 760 lbs. set
With Fittings to Floor ad

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Hibbard Royale BATHROOM SETS



COMPLETE . . . WITH CORNER TUB AND SHOWER

- Modern Colonial Design Tub—Beautiful clear white finish.
- Large Shelf Type Lavatory—21 in. long, 18 in. wide.
Ideal for holding tumbler, cosmetics, etc.
Heavy chromium legs.
- Beautiful new-unit type closet—Mother of Pearl finished seat. Quiet—no exposed connections.
- Shower has adjustable self-cleaning head.
- Shower curtain of genuine Rayon Silk.

SET CONSISTS OF W20RLD0—BATH TUB. W1550MLD0—LAVATORY. W25LD0—CLOSET.



ART DESIGN FITTINGS

Heavily chromium plated—lustrous—beautiful—require no polishing.

White

W94LD0—Right Hand Fittings

W094LD0—Left Hand Fittings

5 ft. Tub, w't 760 lbs. set \$139.45

5½ ft. Tub, w't 810 lbs. set 145.90

Acid Resisting White

W940LD0—Right Hand Fittings

W0940LD0—Left Hand Fittings

5 ft. Tub, w't 760 lbs. set \$145.90


5½ ft. Tub, w't 810 lbs. set 153.40

With Fittings to Floor add \$1.50


ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Prices Net F.O.B. Chicago, Add Freight to _____

THE *Hibbard Classic* BATHROOM SET




CHROMIUM PLATED BRASS, SELF CLEANING SHOWER HEAD WITH ADJUSTABLE SPRAY. A FINER MORE CONCENTRATED STREAM, LESS SPLASH.



RAISED EDGE ON ENTIRE RIM OF LAVATORY PREVENTS OVERFLOW, PROTECTS THE PERSON AND FLOOR.


BEAUTIFUL COLONIAL DESIGN TUB




Hibbard CLASSIC TUBS ARE IN THE MODERN MODE AND REPRESENT THE LATEST IN NEW STRAIGHT LINE DESIGNS. THEY HAVE PROVEN EXTREMELY POPULAR AND THE CLEAN CUT ANGULAR LINES HARMONIZE WITH OTHER FIXTURES IN THE BATHROOM, MAKING A COMPLETE AND PLEASING ENSEMBLE.



VANITY DRESSING TABLE OF GLEAMING GENUINE VITREOUS CHINA. SMOOTH HARD, LUSTROUS SURFACE, EASILY KEPT CLEAN. LARGE ROOMY TOP WITH RAISED EDGE TO PREVENT TOILET ARTICLES FROM SLIPPING OFF. CHROMIUM PLATED BRASS LEGS, HEXAGON DESIGN. ADJUSTABLE IN HEIGHT, ESPECIALLY DESIGNED TO CONFORM WITH TODAY'S MODERN TRENDS.



CHROMIUM PLATED HEAVY CAST BRASS ADJUSTABLE LEGS OF HEXAGON DESIGN. COMPLETE WITH LARGE HEXAGON DESIGN TOWEL RACKS AND WALL FLANGES.



ACID-RESISTING, NOT EFFECTED BY MEDICINES, LOTIONS, DYES OR FRUIT JUICES.

Hibbard Classic BATHROOM SETS



COMPLETE WITH RECESS TUB AND SHOWER

SHOWER DOORS AND BENCH NOT INCLUDED
IN PRICES

White

W1LD0 —Right Hand Fittings	
W01LD0 —Left Hand Fittings	
4½ ft. Tub, w't 700 lbs.....set	\$199.35
5 ft. Tub, w't 730 lbs.....set	202.75
5½ ft. Tub, w't 760 lbs.....set	208.25

Acid Resisting White

W10LD0 —Right Hand Fittings	
W010LD0 —Left Hand Fittings	
4½ ft. Tub, w't 700 lbs.....set	\$202.55
5 ft. Tub, w't 730 lbs.....set	206.35
5½ ft. Tub, w't 760 lbs.....set	210.75

Acid Resisting Colors

F10½LD0 —Right Hand Fittings	
F010½LD0 —Left Hand Fittings	
4½ ft. Tub, w't 700 lbs.....set	\$253.25★
5 ft. Tub, w't 730 lbs.....set	257.95★
5½ ft. Tub, w't 760 lbs.....set	263.45★

With Fittings to Floor.....add \$1.50

- Modern Colonial Design Tub—Beautiful lasting finish.
- Vitreous China Lavatory—24 in. long, 20 in. wide. Not affected by acids.
Adjustable chromium legs and large chromium towel racks.
- Vitreous China Dressing Table—30 in. long, 18 in. wide—
Large, roomy, with plenty of space for cosmetics, etc. Adjustable chromium legs.
- Beautiful new-unit type closet—
Mother of Pearl finished seat. Quiet—no exposed connections.
- Shower has adjustable self-cleaning head.

SET CONSISTS OF W16RLD0—BATH TUB. W1097CLD0—LAVATORY. W4475LD0—DRESSING TABLE. W25LD0—CLOSET.

ART DESIGN FITTINGS


HEAVILY CHROMIUM PLATED — LUSTROUS — BEAUTIFUL — REQUIRE NO POLISHING. COMPRESSION TYPE WITH RENEWABLE SEAT. SOLID BRASS THROUGHOUT.



★Items Marked Thus ★ Are Shipped from Factory Only.

Prices Net F.O.B. Chicago, Add Freight to _____

Bath Rooms in Color!



No. 20
CORAL BLUSH

No. 16
ROYAL ORCHID

No. 13
OLD ROSE

No. 10
PAGAN RED

No. 31
COLONIAL IVORY

No. 28
JONQUIL YELLOW

No. 34
TUSCAN TAN

No. 40
PASTEL GREEN

ACTUAL COLORS OF Hibbard PLUMBING FIXTURES

With the increased popularity of colored plumbing fixtures, color has become one of the most important factors in planning a bathroom.

Color in plumbing fixtures is not costly—in fact it is but a small part of the total cost of any bathroom and the added charm and individuality given the bathroom easily offsets the small additional cost.

• • •

ALL COLORED FIXTURES ARE
SHIPPED FROM FACTORY

• • •

NO MORE GUESS WORK
THESE ARE THE ACTUAL COLORS

BLACK, MIDNIGHT BLUE AND LIGHT BLUE COLORS CAN ALSO BE FURNISHED

IMPORTANT:

COLORLED FIXTURES ARE MADE ONLY IN ACID-RESISTING FINISH
ADD 25% TO PRICE OF ACID RESISTING WHITE, USING THE SAME NUMBERS

Hibbard Classic BATHROOM SETS



- Modern Colonial Design Tub—Beautiful clear white finish.
- Vitreous China Lavatory 24 in. long, 20 in. wide—large, roomy, with plenty of space for tumblers, cosmetics, etc. Not affected by acids.
- Beautiful new-unit type closet—Mother of Pearl finished seat. Quiet—no exposed connections.
- Shower has adjustable self-cleaning head.
- Shower curtain of genuine Rayon Silk.

COMPLETE WITH CORNER TUB AND SHOWER

White

W2LD0 —Right hand Fittings	
W02LD0 —Left Hand Fittings	
5 ft. Tub, w't 760 lbs.....	set \$146.10
5½ ft. Tub, w't 810 lbs.....	set 152.55


Acid Resisting White

W20LD0 —Right Hand Fittings	
W020LD0 —Left Hand Fittings	
5 ft. Tub, w't 760 lbs.....	set \$149.40
5½ ft. Tub, w't 810 lbs.....	set 156.90

With Fittings to Floor.....add \$1.50

ART DESIGN FITTINGS

Heavily chromium plated—lustrous—beautiful—require no polishing.




SET CONSISTS OF

W20RLD0—BATH TUB
W1098CLD0—LAVATORY
W25LD0—CLOSET

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard President BATHROOM SETS



COMPLETE WITH RECESS TUB AND SHOWER

- Modern Colonial Design Tub—Beautiful clear white finish.
- Colonial Design Pedestal Lavatory, 24 in. long, 20 in. wide—with deep apron. Matches tub perfectly in finished design.
- Beautiful new-unit type closet—Mother of Pearl finished seat. Quiet—no exposed connections.
- Shower has adjustable self-cleaning head.
- Shower curtain of genuine Rayon Silk.

White

W3LD0 —Right Hand Fittings	
W03LD0 —Left Hand Fittings	
4½ ft. Tub, w't 810 lbs.....set	\$130.85
5 ft. Tub, w't 840 lbs.....set	134.15
5½ ft. Tub, w't 870 lbs.....set	139.65

Acid Resisting White

W77LD0 —Right Hand Fittings	
W077LD0 —Left Hand Fittings	
4½ ft. Tub, w't 810 lbs.....set	\$140.00
5 ft. Tub, w't 840 lbs.....set	143.80
5½ ft. Tub, w't 870 lbs.....set	150.20

With Fittings to Floor.....add \$1.50

ART DESIGN FITTINGS

heavily chromium plated—lustrous—beautiful—require no polishing.




SET CONSISTS OF

W26RLD0—BATH TUB
W40CLD0—LAVATORY
W25LD0—CLOSET

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard President BATHROOM SETS



COMPLETE WITH CORNER TUB AND SHOWER

- Modern Colonial Design Tub—
Beautiful clear white finish.
- Colonial Design Pedestal Lavatory, 24 in. long,
20 in. wide—with deep apron. Matches tub
perfectly in finished design.
- Beautiful new-unit type closet—
Mother of Pearl finished seat. Quiet—no ex-
posed connections.
- Shower has adjustable self-cleaning head.
- Shower curtain of genuine Rayon Silk.

White

W4LD0—Right Hand Fittings

W04LD0—Left Hand Fittings

5 ft. Tub, w't 880 lbs.....set \$142.30

5½ ft. Tub, w't 930 lbs.....set 148.75

Acid Resisting White

W88LD0—Right Hand Fittings

W088LD0—Left Hand Fittings

5 ft. Tub, w't 880 lbs.....set \$152.70

5½ ft. Tub, w't 930 lbs.....set 160.20

With Fittings to Floor.....add \$1.50

ART DESIGN FITTINGS

Heavily chromium plated—lustrous—
beautiful—require no polishing.



SET CONSISTS OF

W20RLD0—BATH TUB


W40CLD0—LAVATORY

W25LD0—CLOSET

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard Ambassador BATHROOM SETS



COMPLETE WITH RECESS TUB AND SHOWER

White

W5LDO—Right Hand Fittings	
W05LDO—Left Hand Fittings	
4½ ft. Tub, w't 810 lbs.....set	\$122.65
5 ft. Tub, w't 840 lbs.....set	125.95
5½ ft. Tub, w't 870 lbs.....set	131.45

Acid Resisting White

W50LDO—Right Hand Fittings	
W050LDO—Left Hand Fittings	
4½ ft. Tub, w't 810 lbs.....set	\$131.85
5 ft. Tub, w't 840 lbs.....set	135.65
5½ ft. Tub, w't 870 lbs.....set	142.00

With Fittings to Floor.....add \$1.50

- Modern Colonial Design Tub—Beautiful clear white finish.
- Colonial Design Pedestal Lavatory, 24 in. long, 20 in. wide—with deep apron. Matches tub perfectly in finish and design.
- New Era Washdown Closet of newest design. Sheet celluloid covered seat, guaranteed for five years.
- Shower has adjustable self-cleaning head.
- Shower curtain of genuine Rayon Silk.

ART DESIGN FITTINGS

Heavily chromium plated—lustrous—beautiful—require no polishing.




SET CONSISTS OF

W26RLDO—BATH TUB
W40CLDO—LAVATORY
W17LDO—CLOSET

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard Ambassador BATHROOM SETS



COMPLETE WITH CORNER TUB AND SHOWER

- Modern Colonial Design Tub—Beautiful clear white finish.
- Colonial Design Pedestal Lavatory, 24 in. long, 20 in. wide—with deep apron. Matches tub perfectly in finish and design.
- New Era Washdown Closet of newest design. Sheet celluloid covered seat, guaranteed for five years.
- Shower has adjustable self-cleaning head.
- Shower curtain of genuine Rayon Silk.

White

W6LD0—Right Hand Fittings	
W06LD0—Left Hand Fittings	
5 ft. Tub, w't 880 lbs.....set	\$130.80
5½ ft. Tub, w't 930 lbs.....set	137.25


Acid Resisting White

W60LD0—Right Hand Fittings	
W060LD0—Left Hand Fittings	
5 ft. Tub, w't 880 lbs.....set	\$144.55
5½ ft. Tub, w't 930 lbs.....set	152.00

With Fittings to Floor.....add \$1.50

ART DESIGN FITTINGS

Heavily chromium plated—lustrous—beautiful—require no polishing.



SET CONSISTS OF

W20RLD0—BATH TUB
W40CLD0—LAVATORY
W17LD0—CLOSET

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard General BATHROOM SETS



COMPLETE . . . WITH RECESS TUB AND SHOWER

- Modern Colonial Design Tub—Beautiful clear white finish.
- Colonial Design Pedestal Lavatory, 24 in. long, 20 in. wide—with deep apron. Matches tub perfectly in finish and design.
- New Era Washdown Closet of newest design. Sheet celluloid covered seat, guaranteed for five years.
- Diverter type shower with adjustable self-cleaning head. Trip lever waste.
- Shower curtain of genuine Rayon Silk.

ART DESIGN FITTINGS

Heavily chromium plated—lustrous—beautiful—require no polishing.

SET CONSISTS OF:

W26MLD0—BATH TUB
W40CLD0—LAVATORY
W17LD0—CLOSET



White

W9LD0—Right Hand Fittings

W09LD0—Left Hand Fittings

4½ ft. Tub, w't 810 lbs. set \$116.10

5 ft. Tub, w't 840 lbs. set 119.45

5½ ft. Tub, w't 870 lbs. set 125.10

Acid Resisting White

W90LD0—Right Hand Fittings

W090LD0—Left Hand Fittings

4½ ft. Tub, w't 810 lbs. set \$125.30


5 ft. Tub, w't 840 lbs. set 129.00

5½ ft. Tub, w't 870 lbs. set 135.50

With Fittings to Floor add \$1.50

ACID RESISTING IN COLORS ADD
25 % TO PRICE OF ACID WHITE—
USING SAME NUMBERS AND SPECIFY
COLOR

Hibbard General BATHROOM SETS



COMPLETE . . . WITH RECESS TUB AND SHOWER

- Modern Colonial Design Tub—Beautiful clear white finish.
- Colonial Design Pedestal Lavatory, 24 in. long, 20 in. wide—with deep apron. Matches tub perfectly in finish and design.
- New Era Washdown Closet of newest design Sheet celluloid covered seat, guaranteed for five years.
- Diverter type shower with adjustable self-cleaning head. Trip lever waste.
- Shower curtain of genuine Rayon Silk.

White

W19LDO—Right Hand Fittings

W019LDO—Left Hand Fittings

5 ft. Tub, w't 880 lbs.....set \$124.20

5½ ft. Tub, w't 930 lbs.....set 130.65

Acid Resisting White

W19OLD0—Right Hand Fittings

W019OLD0—Left Hand Fittings

5 ft. Tub, w't 880 lbs.....set \$138.00

5½ ft. Tub, w't 930 lbs.....set 145.45

With Fittings to Floor.....add \$1.50

ART DESIGN FITTINGS

Heavily chromium plated—lustrous—beautiful—require no polishing.



SET CONSISTS OF

W20MLD0—BATH TUB


W40CLD0—LAVATORY

W17LD0—CLOSET

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard Colonial BATHROOM SETS



COMPLETE . . . WITH RECESS TUB AND SHOWER

- Modern Colonial Design Tub—Beautiful clear white finish.
- Colonial Design Wall Lavaratory with back and deep apron, size 21 in. long, 18 in. wide. Large roomy bowl.
- New Era Washdown Closet of newest design. Sheet celluloid covered seat, guaranteed for five years.
- Shower has adjustable self-cleaning head.
- Shower curtain of genuine Rayon Silk.

SET CONSISTS OF
W26MLD0—BATH TUB
W45GLD0—LAVATORY
W17LD0—CLOSET

ACID RESISTING IN COLORS ADD 25% TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR



ART DESIGN FITTINGS

Heavily chromium plated—lustrous—beautiful—require no polishing.

White

W29LD0—Right Hand Fittings	
W029LD0—Left Hand Fittings	
4½ ft. Tub, w't 685 lbs.....set	\$103.25
5 ft. Tub, w't 715 lbs.....set	106.60
5½ ft. Tub, w't 745 lbs.....set	112.35

Acid Resisting White

W290LD0—Right Hand Fittings	
W0290LD0—Left Hand Fittings	
4½ ft. Tub, w't 685 lbs.....set	\$110.00
5 ft. Tub, w't 715 lbs.....set	113.75
5½ ft. Tub, w't 745 lbs.....set	120.25

With Fittings to Floor.....add \$1.50

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard Colonial BATHROOM SETS



COMPLETE . . . WITH CORNER TUB AND SHOWER

- Modern Colonial Design Tub—Beautiful clear white finish.
- Colonial Design Wall Lavaratory with back and deep apron, size 21 in. long, 18 in. wide. Large roomy bowl.
- New Era Washdown Closet of newest design. Sheet celluloid covered seat, guaranteed for five years.
- Shower has adjustable self-cleaning head.
- Shower curtain of genuine Rayon Silk.

White

W30LDO—Right Hand Fittings	
W030LDO—Left Hand Fittings	
5 ft. Tub, w't 745 lbs.....set	\$111.30
5½ ft. Tub, w't 805 lbs.....set	117.75

Acid Resisting White

W300LDO—Right Hand Fittings	
W0300LDO—Left Hand Fittings	
5 ft. Tub, w't 745 lbs.....set	\$122.75
5½ ft. Tub, w't 805 lbs.....set	130.20

With Fittings to Floor.....add \$1.50

ART DESIGN FITTINGS

Heavily chromium plated—lustrous—beautiful—require no polishing.




SET CONSISTS OF

W20MLDO—BATH TUB
W45GLDO—LAVATORY
W17LDO—CLOSET

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard President BATHROOM SETS



COMPLETE SET . . . WITH RECESS TUB

White

W33LD0 —Right Hand Fittings	
W033LD0 —Left Hand Fittings	
4½ ft. Tub, w't 785 lbs.	set \$116.85
5 ft. Tub, w't 815 lbs.	set 120.25
5½ ft. Tub, w't 845 lbs.	set 125.85

Acid Resisting White

W330LD0 —Right Hand Fittings	
W0330LD0 —Left Hand Fittings	
4½ ft. Tub, w't 785 lbs.	set \$125.90
5 ft. Tub, w't 815 lbs.	set 129.85
5½ ft. Tub, w't 845 lbs.	set 136.25

With Fittings to Floor. add \$1.50

- Modern Colonial Design Tub—Beautiful clear white finish.
- Colonial Design Pedestal Lavatory, 24 in. long, 20 in. wide—with deep apron. Matches tub perfectly in finish and design.
- Beautiful new-unit type closet—Mother of Pearl finished seat. Quiet—no exposed connections.

ART DESIGN FITTINGS

heavily chromium plated—lustrous—beautiful—require no polishing.



SET CONSISTS OF

W26TLD0—BATH TUB
W40CLD0—LAVATORY
W25LD0—CLOSET

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard President BATHROOM SETS



COMPLETE SET . . . WITH CORNER TUB

White

- Modern Colonial Design Tub—Beautiful clear white finish.
- Colonial Design Pedestal Lavatory, 24 in. long, 20 in. wide—with deep apron. Matches tub perfectly in finish and design.
- Beautiful new-unit type closet—Mother of Pearl finished seat. Quiet—no exposed connections.

W34LD0—Right Hand Fittings

W034LD0—Left Hand Fittings

5 ft. Tub, w't 845 lbs. set \$125.00

5½ ft. Tub, w't 905 lbs. set 131.45

Acid Resisting White

W340LD0—Right Hand Fittings

W0340LD0—Left Hand Fittings

5 ft. Tub, w't 845 lbs. set \$135.60

5½ ft. Tub, w't 905 lbs. set 142.95

With Fittings to Floor. add \$1.50

ART DESIGN FITTINGS

Heavily chromium plated—lustrous—beautiful—require no polishing.



SET CONSISTS OF


W20TLD0—BATH TUB

W40CLD0—LAVATORY

W25LD0—CLOSET

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Hibbard Ambassador BATHROOM SETS



COMPLETE SET . . . WITH RECESS TUB

White

W35LDO—Right Hand Fittings	
W035LDO—Left Hand Fittings	
4½ ft. Tub, w't 785 lbs.	set \$109.75
5 ft. Tub, w't 815 lbs.	set \$113.20
5½ ft. Tub, w't 845 lbs.	set 118.80

Acid Resisting White

W35OLD0—Right Hand Fittings	
W035OLD0—Left Hand Fittings	
4½ ft. Tub, w't 785 lbs.	set \$118.80
5 ft. Tub, w't 815 lbs.	set 122.75
5½ ft. Tub, w't 845 lbs.	set 129.15

With Fittings to Floor.....add \$1.50

- Modern Colonial Design Tub—Beautiful clear white finish.
- Colonial Design Pedestal Lavatory, 24 in. long, 20 in. wide—with deep apron. Matches tub perfectly in finish and design.
- New Era Washdown Closet of newest design. Sheet celluloid covered seat, guaranteed for five years.

ART DESIGN FITTINGS

vily chromium plated—lustrous—
utiful—require no polishing.



SET CONSISTS OF

W26TLD0—BATH TUB
W40CLD0—LAVATORY
W17LD0—CLOSET

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Prices Net F.O.B. Chicago. Add Freight to _____

Hibbard Ambassador BATHROOM SETS



COMPLETE SET . . . WITH CORNER TUB

- Modern Colonial Design Tub—Beautiful clear white finish.
- Colonial Design Pedestal Lavatory, 24 in. long, 20 in. wide—with deep apron. Matches tub perfectly in finish and design.
- New Era Washdown Closet of newest design. Sheet celluloid covered seat, guaranteed for five years.

White

W36LDO—Right Hand Fittings

W036LDO—Left Hand Fittings

5 ft. Tub, w't 845 lbs. set \$117.90

5½ ft. Tub, w't 905 lbs. set 124.35

Acid Resisting White

W360LDO—Right Hand Fittings

W0360LDO—Left Hand Fittings

5 ft. Tub, w't 845 lbs. set \$128.50

5½ ft. Tub, w't 905 lbs. set 135.85

With Fittings to Floor add \$1.50

ART DESIGN FITTINGS

Heavily chromium plated—lustrous—beautiful—require no polishing.



SET CONSISTS OF

W20TLDO—BATH TUB


W40CLDO—LAVATORY

W17LDO—CLOSET

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard Composition Tileboard and Panelboard For Attractive Kitchens and Bathrooms



No. W825LD $\frac{1}{4}$

GET YOUR SHARE OF THIS GROWING BUSINESS

THIS DISPLAY PANEL IN SIX ATTRACTIVE COLORS MAKES IT EASY TO SELL AND WILL INCREASE YOUR VOLUME. 12x24 IN. WITH CHROME BORDER. CAN BE HUNG ON THE WALL OR COUNTER. TAKE IT WITH YOU WHEN CALLING ON PROSPECTIVE CUSTOMERS. FURNISHED AT OUR ACTUAL COST OF \$1.00 AND MAY BE RETURNED FOR FULL CREDIT WITHIN ONE YEAR IF YOU ARE NOT SATISFIED WITH THE RESULTS.

Make the Home More Inviting—Modernize the Kitchen, Bath, Laundry, Nursery, Attic

... Most Homeowners, must have a room or two that they really want to "fix-up" or remodel—but—faced with expensive alternation costs—they've just been putting it off! NOW—you can do it—and at half the cost!

Hibbard Tileboard and Panelboard is a new composition wallboard, made in large sheets that can be applied right over old walls and ceilings by any carpenter, without costly preparations—no bother, fuss or dirt!

And here's why this new material is so wonderful. The special baked enamel finish provides a hard, moisture-resistant surface which is glistening clean and sanitary, and is easily kept so by occasional washing with a soft cloth or water—plain soap when necessary.

★ ★ ★

Amazing what a few sheets of **Hibbard** Tileboard and Panelboard will do to make old rooms cheerful, new and livable. Makes you feel like a new person, too, when you find how easy it is to keep them clean and bright.

Hibbard "tile" and panelboard does away with the costly periodic repainting and repairing of bothersome cracked walls and ceilings! Plenty of exciting color combinations to choose from. Just what is needed to make the home more inviting! No excuse now for drab cheerless rooms.

Made of a Masonite base composition produced under enormous pressure and has a glazed finish that is impervious to moisture and will not chip, crack, peel, warp or crumble. Very easily kept clean with a damp cloth or with soap and water.

It is not easily damaged by scratches or blows. If ever damaged, a block can be removed and replaced at small cost. Very light in weight, it is easily and quickly installed and can be sawed, planed, milled and glued like lumber.


ATTRACTIVE COLORS AND COMBINATIONS TO CHOOSE FROM

HIBBARD MASONITE BASE WATERPROOF

FOR BATHROOMS AND KITCHENS



TRULY ECONOMICAL IN
PRICE AND EASY
TO INSTALL



No. W711LD0—GREEN
WITH WHITE SCOR-
ING TILEBOARD



No. W704LD0—WHITE
WITH BLACK SCORING
TILEBOARD



No. W703LD0—LIGHT
BLUE WITH WHITE
SCORING TILEBOARD



Base Mould-
ing



No. W802LD0—IVORY
PANELBOARD

Hibbard Scored Tileboard

Sheets 48x48 In., in 4 In. Squares, W't per Sq. Ft. $\frac{3}{4}$ Lb.

W701LD0—Green with ivory scoring . . . sq. ft.	\$0.35
W703LD0—Light blue with white scoringsq. ft.	.35
W704LD0—White with black scoring . . . sq. ft.	.35
W705LD0—White with gray scoring . . . sq. ft.	.35
W706LD0—Black with white scoring . . . sq. ft.	.35
W707LD0—Ivory with white scoring . . . sq. ft.	.35
W708LD0—Ivory with green scoring . . . sq. ft.	.35
W709LD0—Orchid with white scoring . . . sq. ft.	.35
W710LD0—Ivory with black scoring . . . sq. ft.	.35
W711LD0—Green with white scoring . . . sq. ft.	.35



No. W706LD0—BLACK
WITH WHITE SCORING
TILEBOARD

Hibbard Panelboard

Sheets 48x48 In., Plain Without Scoring, W't per Sq. Ft. $\frac{3}{4}$ Lb.

W801LD0—Green . . . sq. ft.	\$0.35
W802LD0—Ivory . . . sq. ft.	.35
W803LD0—Light blue . . . sq. ft.	.35
W804LD0—Orchid . . . sq. ft.	.35
W805LD0—White . . . sq. ft.	.35
W806LD0—Black . . . sq. ft.	.35



No. W804LD0—ORCHID
PANELBOARD

Cap or Top Moulding

$1\frac{3}{4}$ In. Wide, 48 In. Lengths, W't per Lineal Ft. $\frac{1}{4}$ Lb.

W901LD0—Black, plain . . . lin. ft.	\$0.30
W902LD0—Black with white scoring . . . lin. ft.	.30
W903LD0—Black with gray scoring . . . lin. ft.	.30
W904LD0—Chrome with wood back . . . lin. ft.	.35

Base Moulding

4 In. Wide, 48 In. Lengths, W't per Lineal Ft. $\frac{1}{2}$ Lb.

W905LD0—Black, plain . . . lin. ft.	\$0.35
W906LD0—Black with white scoring . . . lin. ft.	.35
W907LD0—Black with gray scoring . . . lin. ft.	.35

Chrome Moulding

48 In. Lengths, W't per Lineal Ft. $\frac{1}{2}$ Lb.

W908LD0—For inside corners . . . lin. ft.	\$0.30
W909LD0—For outside corners . . . lin. ft.	.25
W910LD0—Dividing strip . . . lin. ft.	.20
W911LD0—Edging . . . lin. ft.	.15

Sold Only in Full Sheets and Lengths

Cement

W912LD0—1 gallon cans . . . gallon	\$2.00
------------------------------------	--------



No. W710LD0—IVORY
WITH BLACK SCORING
TILEBOARD

Hibbard General BATHROOM SET



COMPLETE SET . . . WITH RECESS TUB

- Modern Colonial Design Tub—Beautiful clear white finish.
- Colonial Design Pedestal Lavatory, 24 in. long, 20 in. wide—with deep apron. Matches tub perfectly in finish and design.
- New Era Washdown Closet of newest design. Sheet celluloid covered seat, guaranteed for five years. Trip lever waste on tub.

ART DESIGN FITTINGS

Heavily chromium plated—lustrous—beautiful—require no polishing.



ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

White

W39LDO—Right Hand Fittings

W039LDO—Left Hand Fittings

4½ ft. Tub, w't 785 lbs. set \$106.60

5 ft. Tub, w't 815 lbs. set 110.10

5½ ft. Tub, w't 845 lbs. set 115.65

Acid Resisting White

W39LDO—Right Hand Fittings

W039LDO—Left Hand Fittings

4½ ft. Tub, w't 785 lbs. set \$115.75

5 ft. Tub, w't 815 lbs. set 119.60

5½ ft. Tub, w't 845 lbs. set 126.10

With Fittings to Floor add \$1.50

SET CONSISTS OF:


W26ALDO—BATH TUB

W40CLDO—LAVATORY

W17LDO—CLOSET

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard General BATHROOM SETS



COMPLETE SET . . . WITH CORNER TUB

- Modern Colonial Design Tub—Beautiful clear white finish.
- Colonial Design Pedestal Lavatory, 24 in. long, 20 in. wide—with deep apron. Matches tub perfectly in finish and design.
- New Era Washdown Closet of newest design. Sheet celluloid covered seat, guaranteed for five years.
- Trip lever waste on tub.

White

W40LD0—Right Hand Fittings	
W040LD0—Left Hand Fittings	
5 ft. Tub, w't 845 lbs.	set \$114.80
5½ ft. Tub, w't 905 lbs.	set 121.25

Acid Resisting White

W400LD0—Right Hand Fittings	
W0400LD0—Left Hand Fittings	
5 ft. Tub, w't 845 lbs.	set \$125.35
5½ ft. Tub, w't 905 lbs.	set 132.80
With Fittings to Floor.	add \$1.50

ART DESIGN FITTINGS

heavily chromium plated—lustrous—beautiful—require no polishing.



SET CONSISTS OF


W20ALD0—BATH TUB
W40CLD0—LAVATORY
W17LD0—CLOSET

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Prices Net F.O.B. Chicago, Add Freight to _____


THE *Hibbard* Colonial BATHROOM SET

BEAUTIFUL COLONIAL DESIGN TUB




Hibbard Classic Tubs are in the Modern Mode and represent the latest in the new straight line designs.

They have proven extremely popular and the clean cut angular lines harmonize with the other fixtures in the bathroom, making a complete and pleasing ensemble.




Plenty of bowl space. Fixtures recessed in back. Raised edge on rim prevents overflow.



Large roomy shelf back, protects wall and is ideal for tumbler, cosmetics, etc.



Handy shelf makes shaving a pleasure.



Quiet action genuine vitreous china closet. Close coupled, no exposed connections. Shelf top tank. Mother-of-pearl celluloid seat and cover, guaranteed for five years.

Hibbard Colonial BATHROOM SETS



COMPLETE SET . . . WITH RECESS TUB

- Modern Colonial Design Tub—Beautiful clear white finish.
- Large Shelf Type Lavatory—size 21 in. long, 18 in. wide. Ideal for holding tumbler, cosmetics, etc.
- New Era Washdown Closet of newest design. Sheet celluloid covered seat, guaranteed for five years.

ART DESIGN FITTINGS

Heavily chromium plated—lustrous—beautiful—require no polishing.



White	
W41LDO—Right Hand Fittings	
W041LDO—Left Hand Fittings	
4½ ft. Tub, w't 685 lbs.....set	\$ 96.10
5 ft. Tub, w't 715 lbs.....set	99.55
5½ ft. Tub, w't 745 lbs.....set	105.10

Acid Resisting White	
W410LDO—Right Hand Fittings	
W0410LDO—Left Hand Fittings	
4½ ft. Tub, w't 685 lbs.....set	\$104.80
5 ft. Tub, w't 715 lbs.....set	108.60
5½ ft. Tub, w't 745 lbs.....set	115.10
With Fittings to Floor.....add	\$1.50

SET CONSISTS OF

W26ALDO—BATH TUB
W1563MLDO—LAVATORY
W17LDO—CLOSET

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Hibbard Challenger BATHROOM SETS



OUR GREATEST VALUE COMPLETE BATHROOM SET ... WITH RECESS TUB

White

W45LD0—Right Hand Fittings

W045LD0—Left Hand Fittings

4½ ft. Tub, w't 760 lbs.....set \$ 82.25

5 ft. Tub, w't 790 lbs.....set 85.30

5½ ft. Tub, w't 820 lbs.....set 90.75

Acid Resisting White

W450LD0—Right Hand Fittings

W0450LD0—Left Hand Fittings

4½ ft. Tub, w't 760 lbs.....set \$ 90.00

5 ft. Tub, w't 790 lbs.....set 93.60


5½ ft. Tub, w't 820 lbs.....set 99.80

With Fittings to Floor.....add \$1.50

- Modern Colonial Design Tub—Beautiful clear white finish.
- Colonial Design Wall Lavatory with back and deep apron, size 19 in. long, 17 in. wide. Large roomy bowl.
- New Era Washdown Closet of newest design. White enameled finish guaranteed seat.

CLASSIC DESIGN FITTINGS

Heavily chromium plated—lustrous—beautiful—require no polishing. Chain and plug waste on tub and lavatory.



SET CONSISTS OF

W26HLD0—BATH TUB

W50JLD0—LAVATORY

W17LD0—CLOSET

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard Challenger BATHROOM SETS



OUR GREATEST VALUE COMPLETE BATHROOM SET ... WITH CORNER TUB

White

- Modern Colonial Design Tub—Beautiful clear white finish.
- Colonial Design Wall Lavatory with back and deep apron, size 19 in. long, 17 in. wide. Large roomy bowl.
- New Era Washdown Closet of newest design. White enameled finish seat.

W46LDO—Right Hand Fittings

W046LDO—Left Hand Fittings

5 ft. Tub, w't 820 lbs.....set \$ 90.10

5½ ft. Tub, w't 880 lbs.....set 96.25

Acid Resisting White

W46OLD0—Right Hand Fittings

W046OLD0—Left Hand Fittings

5 ft. Tub, w't 820 lbs.....set \$ 99.00

5½ ft. Tub, w't 880 lbs.....set 106.00

With Fittings to Floor.....add \$1.50

CLASSIC DESIGN FITTINGS

Heavily chromium plated—lustrous—beautiful—require no polishing. Chain and Plug Waste on Tub and Lavatory.



SET CONSISTS OF

W20HLD0—BATH TUB


W50JLDO—LAVATORY

W17LDO—CLOSET

ACID RESISTING IN COLORS ADD 25% TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard True Value BATHROOM SETS



COMPLETE SET . . . WITH RECESS TUB

White

W43LD0—Right Hand Fittings

W043LD0—Left Hand Fittings

4½ ft. Tub, w't 760 lbs. set \$ 88.00

5 ft. Tub, w't 790 lbs. set 91.65

5½ ft. Tub, w't 820 lbs. set 97.00

Acid Resisting White

W430LD0—Right Hand Fittings

W0430LD0—Left Hand Fittings

4½ ft. Tub, w't 760 lbs. set \$ 95.15

5 ft. Tub, w't 790 lbs. set 98.80

5½ ft. Tub, w't 820 lbs. set 104.95

With Fittings to Floor. add \$1.50

- Modern Colonial Design Tub—Beautiful clear white finish.
- Colonial Design Wall Lavatory with back and deep apron, size 21 in. long, 18 in. wide. Large roomy bowl.
- New Era Washdown Closet of newest design. Sheet celluloid covered seat, guaranteed for five years.
- Trip lever waste on tub.

CLASSIC DESIGN FITTINGS

Heavily chromium plated—lustrous—beautiful—require no polishing.



SET CONSISTS OF

W26KLD0—BATH TUB


W45ELD0—LAVATORY

W17LD0—CLOSET

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard True Value BATHROOM SETS



COMPLETE SET . . . WITH CORNER TUB

- Modern Colonial Design Tub—Beautiful clear white finish.
- Colonial Design Wall Lavatory with back and deep apron, size 21 in. long, 18 in. wide. Large roomy bowl.
- New Era Washdown Closet of newest design. sheet celluloid covered seat, guaranteed for five years.
- Trip lever waste on tub.

White

W44LD0—Right Hand Fittings

W044LD0—Left Hand Fittings

5 ft. Tub, w't 820 lbs. set \$ 92.65

5½ ft. Tub, w't 880 lbs. set 98.75

Acid Resisting White

W440LD0—Right Hand Fittings

W0440LD0—Left Hand Fittings

5 ft. Tub, w't 820 lbs. set \$104.20

5½ ft. Tub, w't 880 lbs. set 111.30

With Fittings to Floor. add \$1.50

CLASSIC DESIGN FITTINGS

heavily chromium plated—lustrous—
beautiful—require no polishing.



SET CONSISTS OF:

W20KLD0—BATH TUB


W45ELD0—LAVATORY

W17LD0—CLOSET

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard De Luxe Economist BATHROOM SETS



FURNISHED WITH 5 FT. TUB ONLY

COMPLETE SET WITH NEW MODERN LEG TUB

Modernistic DeLuxe Tub combines these special features and advantages:

- New Low Height—only 19 inches to top of rim.
- Wide Flat Bottom—reduces chances of slipping.
- Beveled Rim—harmonizes with lavatory and closet.
- Indented Soap Dishes—a great convenience.
- Modernistic Feet—add distinctiveness.
- Top Rim Faucet—provides an attractive faucet which meets all plumbing code requirements

Colonial Design Wall Lavatory with back and unit type faucet, size 19 in. long, 17 in. wide—more shelf space

New Era Washdown Closet—newest design, guaranteed white enameled seat.

ART DESIGN FITTINGS

Heavily chromium plated throughout.

W13LD0—SET CONSISTS OF W201BLD0 BATH TUB, W850PLD0 LAVATORY, W17LD0 CLOSET, w't per set 400 lbs. set **\$72.95**

With Fittings to Floor add **\$1.50**

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard Economist BATHROOM SETS



COMPLETE SET WITH
ROLLED RIM LEG TUB

For the Home Where Economy and Comfort Mean So Much

- The finest in quality at an unusually low price.
- Leg Type Tub with rolled rim—no sharp corners.
- Sheer white enameled finish.
- Colonial Design Wall Lavatory with back—size 19 in. long, 17 in. wide—large bowl—plenty of shelf space—deep apron.
- New Era Washdown Closet—newest design—guaranteed white enameled seat.
- All Brass Fittings—heavily plated throughout in chromium or nickel finish.

White Only

Nickel Plated Fittings

W11LD0—	
½ ft. Tub, w't 360 lbs.....set	\$55.75
ft. Tub, w't 395 lbs.....set	58.65
½ ft. Tub, w't 425 lbs.....set	63.45

Chromium Plated Fittings

W11CLD0—	
4½ ft. Tub, w't 360 lbs.....set	\$56.95
5 ft. Tub, w't 395 lbs.....set	59.85
5½ ft. Tub, w't 425 lbs.....set	64.75

SET CONSISTS OF W204LD0 BATH TUB, W50LD0 LAVATORY, W17LD0 CLOSET

With Fittings to Floor.....add \$1.50

Hibbard Economy BATHROOM SETS



COMPLETE BATHROOM SET
WITH ROLL RIM TUB

For the Home Where Economy Is the Main Object

- The finest in quality at the lowest price.
- Leg Type Tub with rolled rim—no sharp corners.
- Sheer white enameled finish.
- Wall Lavatory with back—deep apron—round front to match tub—size 19 in. long, 17 in. wide—large bowl.
- Washdown Closet—fast flushing—guaranteed—heavy mahogany finished seat.
- All Brass Fittings—heavily plated throughout in chromium or nickel finish.

White Only

Nickel Plated Fittings

W12LD0—	
4½ ft. Tub, w't 360 lbs.....set	\$52.90
5 ft. Tub, w't 395 lbs.....set	55.80
5½ ft. Tub, w't 425 lbs.....set	60.60

Chromium Plated Fittings

W12CLD0—	
4½ ft. Tub, w't 360 lbs.....set	\$54.00
5 ft. Tub, w't 395 lbs.....set	57.00
5½ ft. Tub, w't 425 lbs.....set	61.80

SET CONSISTS OF W204LD0 BATH TUB, W53LD0 LAVATORY, W117LD0 CLOSET

With Fittings to Floor.....add \$1.50

MODERNIZE


YOUR COUNTRY HOME AND FARM


Easy and Simple to Install

RUNNING WATER PLUMBING HEATING

ENJOY ALL THE
COMFORTS OF THE
CITY HOME

SEE SUGGESTED
LAYOUT ON
NEXT
PAGE





**BUY ON EASY
PAYMENT PLAN**

SEE PAGE 898J

FREE ESTIMATING AND
PLANNING SERVICE

AS LOW AS

\$595⁰⁰

ALL NECESSARY
MATERIALS TO
FULLY EQUIP AN
AVERAGE FARM
HOME WITH
RUNNING WA-
TER, PLUMBING
AND HEATING

COMPARE THESE VALUES:

BATH ROOM SET—Five Foot Tub, Closet, Lavatory (Page 774)	\$ 83.95
CABINET SINK—60 inch, Double Drainboard (Page 802)	69.95
WATER SYSTEM—250 Gallon Capacity (Page 887)	61.30
RANGE BOILER—30 Gallon Capacity, Complete with Stand and Fitting (Page 848)	8.95
LAUNDRY TUB—Complete with Stand and Faucet (Page 847)	12.45
WATER SOFTENER—300 Gallons per Hour (Page 895)	89.50
SEPTIC TANK—220 Gallon, for Six Persons (Page 813)	20.75
HEATING PLANT—Warm Air Furnace, Complete for Two Story House	235.00
Steam Boiler, Complete, 400 Sq. Ft. Radiation	295.00
Hot Water Boiler, Complete, 650 Sq. Ft. Radiation	395.00
SOIL PIPE AND FITTINGS—including Stack	60.00
WATER SUPPLY PIPE AND FITTINGS—Galvanized	25.00
SEWERAGE—To and From Septic Tank	125.00

PRICES DO NOT INCLUDE COST OF INSTALLATION

MORE COMFORT . . .

MORE CONVENIENCES

. . . BETTER HEALTH

Hibbard De Luxe BATH TUB



New modern design leg type with built in soap dishes on shelf type rim.

Flat bottom and semi-sloping end prevents slipping.

White enameled inside, painted outside. Sturdy new design legs.

30 in. wide, 60 in. long, height to top of rim 19 in. Chromium combination bath faucet mounted on top rim. Chromium 1½ in. .20 gauge connected waste and overflow. Chromium ¾ in. bath supplies with floor flanges.

Furnished in 5 ft. Size Only

201BLD0—W't each 295 lbs.....each **\$37.75**

Hibbard BATH TUBS ON LEGS



Hibbard—White enameled inside. Compression bath faucet with hose nozzle, metal lever top handle. Exposed 1½ in. 20 gauge connected drain overflow. Plated ½ in. l. P. size brass offset bath supplies.

Width overall 30 in., inside width 24 in., height 26 in., depth 17½ in.
Size, ft. 4½ 5 5½
Approx. shipping w't, lbs. 260 295 325

In Ordering Specify Size Wanted

With Nickel Fixtures

204NLD0—Size, ft. 4½ 5 5½
Each **\$23.25 26.15 30.95**

With Chromium Fixtures

204CLD0—Size, ft. 4½ 5 5½
Each **\$23.85 26.75 31.50**

Without Fixtures

204LD0—Size, ft. 4½ 5 5½
Each **\$17.25 19.95 24.75**

Width overall 26 in., inside width 21½ in., height 23 in., depth 17½ in.
Size, ft. 4 4½ 5 5½
Approx. shipping w't, lbs. 220 250 285 315

In Ordering Specify Size Wanted

With Nickel Fixtures

W203NLD0—Size, ft. 4 4½ 5 5½
Each **\$23.25 23.25 26.15 30.95**

With Chromium Fixtures

W203CLD0—Size, ft. 4 4½ 5 5½
Each **\$23.85 23.85 26.75 31.50**


Without Fixtures

W203LD0—Size, ft. 4 4½ 5 5½
Each **\$17.25 17.25 19.95 24.75**

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard Modern RECESSED BATH TUB

THIS TUB MAY BE HAD IN PLACE OF ANY REGULAR 5-FOOT RECESS TUB IN SETS SHOWN ON PAGES 756A TO B770 AT NO EXTRA COST



WIDER, FLATTER BOTTOM FOR SHOWERING SAFETY AND EXTRA BATHING SPACE



FLAT RIM CAN BE USED AS SEAT. FOR THE ELDERLY, THE VERY YOUNG. FOOT-BATHS ARE SIMPLER FOR ALL. LOWER RIM FOR EASIER ACCESS. PANELED FOR BEAUTY.

NEW BATHING AND SHOWERING SAFETY

This is the tub that has caused such a wave of commendation, and deservedly so, because it has so many outstanding features.

It has a wide rim seat, a utility and safety feature, has more bathing area than larger tubs. Dangerous slopes have been eliminated, giving greater length and width inside the tub for comfort and safety and reduces the possibility of slipping. Its paneled and graceful lines combine attractiveness that makes it easy to match fixtures. You may safely select this new design tub for your new home or to modernize the old one. Requires no more space than the ordinary 5-foot tub.

SPECIFY THESE NUMBERS WHEN ORDERING

5 FT. SIZE ONLY

White

W426LD0—Right Hand Outlet.

W416LD0—Left Hand Outlet.

Each \$42.00

W't Each 450 Lbs.

Acid-Resisting

W427½LD0—Right Hand Outlet.

W417½LD0—Left Hand Outlet.

Each \$48.35

W't Each 450 Lbs.

PRICES DO NOT INCLUDE FIXTURES

The man or woman who buys a bath tub often puts safety first. A close second is beauty. Right up close is practicability. On all counts, the

Hibbard modern bath tub is the answer.


WHEN INCLUDING THIS TUB IN SETS, BE SURE TO SPECIFY NUMBERS

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard Embassy BATH TUBS WITH FIXTURES

All Art Metal Chromium Bath and Shower Equipment. Non-rising stem compression valves—4 in. brass shower head, ball joint and flow control. Outlet of drain tapped in 1½ in. for iron pipe with 1 in. chrome plated heavy brass curtain rod and flanges, highest grade shrunk rayon silk curtain with holdback hook and chain.

Latest Design Seat Type Tub. Roomy convenient seats at end and side. Flat bottom prevents slipping. Built-in soap dishes.



5½ FT. SIZE
ONLY



Width overall 32 in., inside width 22½ in., height 18½ in., length overall 65 in., inside length 50 in., w't 475 lbs.

Recess Tub, with Five Valve Shower Fixture

White

W146RLD0—Right Hand Fittings.....each **\$89.50**
W136RLD0—Left Hand Fittings.....each **89.50**

Acid Resisting White

W147½RLD0—Right Hand Fittings.....each **\$99.50**
W137½RLD0—Left Hand Fittings.....each **99.50**



5½ FT. SIZE
ONLY



Width overall 32 in., inside width 22½ in., height 18½ in., length overall 65 in., inside length 50 in., w't 465 lbs.

Recess Tub, without Shower

White

W146TLD0—Right Hand Fittings.....each **\$77.95**
W136TLD0—Left Hand Fittings.....each **77.95**

Acid Resisting White

W147½TLD0—Right Hand Fittings.....each **\$87.25**
W137½TLD0—Left Hand Fittings.....each **87.25**


White
W146LD0—Right Hand Outlet.....each **\$61.95**
W136LD0—Left Hand Outlet.....each **61.95**

Without Fixtures

Acid Resisting White

W147½LD0—Right Hand Outlet.....each **\$71.25**
W137½LD0—Left Hand Outlet.....each **71.25**

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR



Width overall 32 in., inside width 22½ in., height 18½ in., length overall 65 in., inside length 50 in., w't 475 lbs.


Recess Tub, with Diverter Shower Fixture

White

W146MLD0—Right Hand Fittings.....each **\$85.45**
W136MLD0—Left Hand Fittings.....each **85.45**

Acid Resisting White

W147½MLD0—Right Hand Fittings.....each **\$94.75**
W137½MLD0—Left Hand Fittings.....each **94.75**



Width overall 32 in., inside width 22½ in., height 18½ in., length overall 65 in., inside length 50 in., w't 465 lbs.

Recess Tub, without Shower

White


W146ALD0—Right Hand Fittings.....each **\$74.75**
W136ALD0—Left Hand Fittings.....each **74.75**

Acid Resisting White

W147½ALD0—Right Hand Fittings.....each **\$83.95**
W137½ALD0—Left Hand Fittings.....each **83.95**

Hibbard Classic BATH TUBS WITH FIXTURES

All Art Metal Chromium Bath and Shower Equipment. Non-rising stem compression valves—4 in. brass shower head, ball joint and flow control. With 1 in. chrome plated heavy brass curtain rod and flanges, highest grade shrunk rayon silk curtain, with holdback hook and chain.



Recess Tub, with Five-Valve Shower Fixture
White

W26RLD0 —Right Hand Fittings	
W16RLD0 —Left Hand Fittings	
4½ ft. tub, w't 460 lbs.....set	\$71.95
5 ft. tub, w't 490 lbs.....set	75.25
5½ ft. tub, w't 520 lbs.....set	80.75

	Acid Resisting White
W27½RLD0 —Right Hand Fittings	
W17½RLD0 —Left Hand Fittings	
4½ ft. tub, w't 460 lbs.....set	\$78.15
5 ft. tub, w't 490 lbs.....set	81.95
5½ ft. tub, w't 520 lbs.....set	88.35



Recess Tub, Without Shower
White

W26TLD0 —Right Hand Fittings	
W16TLD0 —Left Hand Fittings	
4½ ft. tub, w't 435 lbs.....set	\$57.95
5 ft. tub, w't 465 lbs.....set	61.35
5½ ft. tub, w't 495 lbs.....set	66.95

	Acid Resisting White
W27½TLD0 —Right Hand Fittings	
W17½TLD0 —Left Hand Fittings	
4½ ft. tub, w't 435 lbs.....set	\$64.00
5 ft. tub, w't 465 lbs.....set	67.95
5½ ft. tub, w't 495 lbs.....set	74.35

ACID RESISTING IN COLORS ADD 25% TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR



Corner Tub, with Five-Valve Shower Fixture
White

W20RLD0 —Right Hand Fittings	
W10RLD0 —Left Hand Fittings	
5 ft. tub, w't 470 lbs.....set	\$83.40
5½ ft. tub, w't 500 lbs.....set	89.85

	Acid Resisting White
W21½RLD0 —Right Hand Fittings	
W11½RLD0 —Left Hand Fittings	
5 ft. tub, w't 470 lbs.....set	\$90.85
5½ ft. tub, w't 500 lbs.....set	98.35



Corner Tub, Without Shower
White

W20TLD0 —Right Hand Fittings	
W10TLD0 —Left Hand Fittings	
5 ft. tub, w't 460 lbs.....set	\$66.15
5½ ft. tub, w't 485 lbs.....set	72.55

	Acid Resisting White
W21½TLD0 —Right Hand Fittings	
W11½TLD0 —Left Hand Fittings	
5 ft. tub, w't 460 lbs.....set	\$73.65
5½ ft. tub, w't 485 lbs.....set	81.00

Hibbard General BATH TUBS WITH FIXTURES

All metal chromium Bath and Shower Equipment with trip waste transfer valve and over rim nozzle, 4-in. brass shower head, ball joint and flow control, 1½-in. concealed connected drain and overflow, 1-in. chrome plated heavy brass curtain rod and flanges with highest grade shrunk rayon silk curtain wth hold-back hook and chain.



Recess Tub, with Diverter Shower Fixture
White

W26MLD0 —Right Hand Fittings.	
W16MLD0 —Left Hand Fittings.	
4½ ft. tub, w't 460 lbs.....set	\$65.40
5 ft. tub, w't 490 lbs.....set	68.75
5½ ft. tub, w't 520 lbs.....set	74.40

Acid Resisting White	
W27½MLD0 —Right Hand Fittings.	
W17½MLD0 —Left Hand Fittings.	
4½ ft. tub, w't 460 lbs.....set	\$71.60
5 ft. tub, w't 490 lbs.....set	75.35
5½ ft. tub, w't 520 lbs.....set	81.85



Corner Tub with Diverter Shower Fixture
White

W20MLD0 —Right Hand Fittings.	
W10MLD0 —Left Hand Fittings.	
5 ft. tub, w't 470 lbs.....set	\$76.80
5½ ft. tub, w't 500 lbs.....set	83.25


Acid Resisting White	
W21½MLD0 —Right Hand Fittings.	
W11½MLD0 —Left Hand Fittings.	
5 ft. tub, w't 470 lbs.....set	\$84.35
5½ ft. tub, w't 500 lbs.....set	91.80



Recess Tub without Shower
White

W26ALD0 —Right Hand Fittings.	
W16ALD0 —Left Hand Fittings.	
4½ ft. tub, w't 435 lbs.....set	\$54.80
5 ft. tub, w't 465 lbs.....set	58.25
5½ ft. tub, w't 495 lbs.....set	63.80

Acid Resisting White	
W27½ALD0 —Right Hand Fittings.	
W17½ALD0 —Left Hand Fittings.	
4½ ft. tub, w't 435 lbs.....set	\$60.95
5 ft. tub, w't 465 lbs.....set	64.75
5½ ft. tub, w't 495 lbs.....set	71.25



Corner Tub without Shower
White



W20ALD0 —Right Hand Fittings.	
W10ALD0 —Left Hand Fittings.	
5 ft. tub, w't 460 lbs.....set	\$62.95
5½ ft. tub, w't 485 lbs.....set	69.40

Acid Resisting White	
W21½ALD0 —Right Hand Fittings.	
W11½ALD0 —Left Hand Fittings.	
5 ft. tub, w't 460 lbs.....set	\$70.50
5½ ft. tub, w't 485 lbs.....set	77.95

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Hibbard BATH TUBS WITH FIXTURES

All metal chromium fittings. Bath supply with trip waste and over rim nozzle.



Recess Tub Without Shower
White

- W26KLD0**—Right Hand Fittings
- W16KLD0**—Left Hand Fittings
- 4½ ft. tub, w't 436 lbs.....set **\$49.95**
- 5 ft. tub, w't 465 lbs.....set **53.60**
- 5½ ft. tub, w't 495 lbs.....set **58.95**

Acid Resisting White

- W27½KLD0**—Right Hand Fittings
- W17½KLD0**—Left Hand Fittings
- 4½ ft. tub, w't 436 lbs.....set **\$56.35**
- 5 ft. tub, w't 465 lbs.....set **60.00**
- 5½ ft. tub, w't 495 lbs.....set **66.15**




Corner Tub Without Shower
White

- W20KLD0**—Right Hand Fittings
- W10KLD0**—Left Hand Fittings
- 5 ft. tub, w't 460 lbs.....set **\$58.25**
- 5½ ft. tub, w't 485 lbs.....set **64.35**

Acid Resisting White

- W21½KLD0**—Right Hand Fittings
- W11½KLD0**—Left Hand Fittings
- 5 ft. tub, w't 460 lbs.....set **\$65.40**
- 5½ ft. tub, w't 485 lbs.....set **72.50**



Recess Tub, without Shower
White

- W26NLD0**—Right Hand Fittings
- W16NLD0**—Left Hand Fittings
- 4½ ft. tub, w't 435 lbs.....set **\$48.60**
- 5 ft. tub, w't 565 lbs.....set **51.95**
- 5½ ft. tub, w't 495 lbs.....set **57.25**

Acid Resisting White

- W27½NLD0**—Right Hand Fittings
- W17½NLD0**—Left Hand Fittings
- 4½ ft. tub, w't 435 lbs.....set **\$54.75**
- 5 ft. tub, w't 465 lbs.....set **58.35**
- 5½ ft. tub, w't 495 lbs.....set **64.50**

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR





Corner Tub, without Shower
White

- W20NLD0**—Right Hand Fittings
- W10NLD0**—Left Hand Fittings
- 5 ft. tub, w't 460 lbs.....set **\$56.65**
- 5½ ft. tub, w't 485 lbs.....set **62.75**

Acid Resisting White

- W21½NLD0**—Right Hand Fittings
- W11½NLD0**—Left Hand Fittings
- 5 ft. tub, w't 460 lbs.....set **\$63.75**
- 5½ ft. tub, w't 485 lbs.....set **70.95**

Hibbard BATH TUBS WITH FIXTURES



Recess Tub, without Shower

White

26HLD0—Right Hand Fittings	
16HLD0—Left Hand Fittings	
ft. tub, w't 435 lbs.....set	\$49.15
ft. tub, w't 465 lbs.....set	52.20
ft. tub, w't 495 lbs.....set	57.65

Acid Resisting White

27½HLD0—Right Hand Fittings	
17½HLD0—Left Hand Fittings	
ft. tub, w't 435 lbs.....set	\$55.15
ft. tub, w't 465 lbs.....set	58.75
ft. tub, w't 495 lbs.....set	64.95

Corner Tub, without Shower

White

W20HLD0—Right Hand Fittings	
W10HLD0—Left Hand Fittings	
5 ft. tub, w't 460 lbs.....set	\$57.00
5½ ft. tub, w't 485 lbs.....set	63.15

Acid Resisting White

W21½HLD0—Right Hand Fittings	
W11½HLD0—Left Hand Fittings	
5 ft. tub, w't 460 lbs.....set	\$64.20
5½ ft. tub, w't 485 lbs.....set	71.25

Hibbard CORNER APRON BATH TUBS



Enameled One-Piece Built-in Apron Bath Tub with drilling for standing type supply and waste fixture in exposed end. Combination bath supply and waste fixture, with nozzle through tub and supplies to floor.

Dimensions—Width overall 30½ in., width of rim 3½ in., width to wall 29½ in., height from bottom to rim 18½ in., height from floor to rim 17½ in., depth inside 17 in. Size 5 ft. length from finished wall 59½ in., approx. shipping w't 595 lbs.

With Chromium Fixtures

Color	White	Acid Resisting White
Right Hand, Corner, Left Hand Fittings	W03RLD0	F05RGLD0
Left Hand, Corner, Right Hand Fittings	W02RLD0	F04RGLD0
Each	\$71.50	79.00★

Without Fixtures


White

W03LD0—Right Hand, Corner, Left Hand Fittings.	
W02LD0—Left Hand, Corner, Right Hand Fittings.	
Each	\$47.95

Illustration shows tub with right hand installation and left hand outlet.

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

THE *Hibbard* Classic STEEL TUB




MODERN AS TO-MORROW


Modern technique of deep drawing metals and improved manufacture have produced a Tub of greater strength, smoother, more uniform quality with only one-third the weight of regular tubs.




So light in weight that two men may easily do the job which formerly required five. Easier handling means less damage to walls, staircases, etc.




Lip Flange permits easy and perfect installation, prevents seepage into walls and eliminates unsightly cracks, making a perfect, water-tight joint between tub and wall.



Three coats of acid-resisting porcelain enamel, milk white finish, uniform texture. Absolutely guaranteed.



Acid-resisting, not effected by caustic cleaning fluids and alkalis. Smooth, hard and non-porous.




Firmly braced at each end of tub, insuring a perfectly level installation. Integral clip on back of tub drops over a two-by-four support which fastens tub so securely to the studding that it simply cannot move.

Hibbard Classic BATH TUBS

ACID RESISTING PORCELAIN ENAMELED STEEL

Art design chromium plated brass bath and shower fixture with transfer valve to shower. Trip lever waste, over-rim spout, self-cleaning shower head. Highest quality silk shower curtain, 1 in. chromium plated curtain rod, complete with pins and curtain hold back.



5 Foot Recess Tub with Shower

Width overall 30½ in., width of rim 3½ in., width to wall 29½ in., height from bottom to rim 18¼ in., depth inside 17 in., w't each 205 lbs.

Acid Resisting White

W226MLD0—Right Handeach **\$62.35**
W216MLD0—Left Handeach **62.35**

5 Foot Corner Tub with Shower

Width overall 30½ in., width of rim 3½ in., width to wall 29½ in., height from bottom to rim 18¼ in., depth inside 17 in., w't each 235 lbs.

Acid Resisting White

W220MLD0—Right Handeach **\$74.35**
W210MLD0—Left Handeach **74.35**



5 Foot Recess Tub with Over-Rim Fixture, Less Shower

Width overall 30½ in., width of rim 3½ in., width to wall 29½ in., height from bottom to rim 18¼ in., depth inside 17 in., w't each 195 lbs.

Acid Resisting White

W226ALD0—Right Handeach **\$51.95**
W216ALD0—Left Handeach **51.95**

5 Foot Corner Tub with Over-Rim Fixture, Less Shower


Width overall 30½ in., width of rim 3½ in., width to wall 29½ in., height from bottom to rim 18¼ in., depth inside 17 in., w't each 225 lbs.

Acid Resisting White

W220ALD0—Right Handeach **\$59.95**
W210ALD0—Left Handeach **59.95**

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Hibbard BATH TUBS ON BASE



Hibbard—White enameled inside. Compression bath faucet with hose nozzle, metal lever top handles. Exposed $1\frac{3}{8}$ in. 20 ga. connected waste and overflow. Plated brass offset bath supplies. Width 30 in., height 23 in., depth $17\frac{1}{2}$ in.

Size, ft.	4 $\frac{1}{2}$	5
Approximate shipping w't, lbs.	300	340

In Ordering Specify Size Wanted

With Nickel Fixtures

W200NLD0 —Size, ft.	4 $\frac{1}{2}$	5
Each	\$34.95	38.00


With Chromium Fixtures

W200CLD0 —Size, ft.	4 $\frac{1}{2}$	5
Each	\$35.50	38.75

Without Fixtures

W200LD0 —Size, ft.	4 $\frac{1}{2}$	5
Each	\$29.40	32.60

Hibbard BATH TUBS WITHOUT FIXTURES



Recess

Dimensions—Width overall $30\frac{1}{2}$ in., width of rim $3\frac{3}{4}$ in., width to wall $29\frac{1}{2}$ in., height from bottom to rim $18\frac{1}{2}$ in., height from floor to rim $17\frac{1}{2}$ in., depth inside 17 in.

White

W26LD0 —Right Hand Outlet	
W16LD0 —Left Hand Outlet	
4 $\frac{1}{2}$ ft., w't 415 lbs.	each \$39.00
5 ft., w't 445 lbs.	each 42.00
5 $\frac{1}{2}$ ft., w't 500 lbs.	each 47.35

Acid Resisting White

W27$\frac{1}{2}$LD0 —Right Hand Outlet	
W17$\frac{1}{2}$LD0 —Left Hand Outlet	
4 $\frac{1}{2}$ ft., w't 415 lbs.	each \$44.85
5 ft., w't 445 lbs.	each 48.35
5 $\frac{1}{2}$ ft., w't 500 lbs.	each 54.40



Corner

Dimensions—Width overall $30\frac{1}{2}$ in., width of rim $3\frac{3}{4}$ in., width to wall $29\frac{1}{2}$ in., height from bottom to rim $18\frac{1}{2}$ in., height from floor to rim $17\frac{1}{2}$ in., depth inside 17 in.

White

W20LD0 —Right Hand Outlet	
W10LD0 —Left Hand Outlet	
5 ft., w't 500 lbs.	each \$46.70
5 $\frac{1}{2}$ ft., w't 550 lbs.	each 52.70

Acid Resisting White

W21$\frac{1}{2}$LD0 —Right Hand Outlet	
W11$\frac{1}{2}$LD0 —Left Hand Outlet	
5 ft., w't 500 lbs.	each \$53.70
5 $\frac{1}{2}$ ft., w't 550 lbs.	each 60.60

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard Classic CABINET LAVATORY

Vitreous China "Acid Resisting" Lavatory, Steel Enameled Cabinet



Medicine Cabinet and Shelf Not Included

Modern . . . Attractive . . . Convenient

Two large spacious shelves, for storing soap, towel and other supplies. Utilizes space formerly wasted.

Heavy steel cabinet finished in white durable enamel with contrasting black steel base. Door is attractively decorated with chromium lines and black and chrome pull.

Large, 24x20 in. size. Finest white vitreous china lavatory

top. Acid-resisting, gleaming finish is easy to clean and affords the maximum in appearance and sanitation.

Chromium plated hexagon design combination supply and pop-up waste fixture. 1½ in. brass chromium plated lavatory trap and ¾ in. brass chromium plated supply pipe.

Height to top 31½ in., width 24 in., depth 20 in., w't each 80 lbs.

W1095BLD0 —With fittings to wall.....	each \$38.95
W1096BLD0 —With fittings to floor.....	each 40.25

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard Classic LAVATORIES



- PORCELAIN ENAMELED STEEL, ACID RESISTING LAVATORY
- LARGE STORAGE CABINET
- UTILIZES ALL OF VALUABLE SPACE USUALLY WASTED

Large shelf for storing soap, towels and other supplies. Heavy steel cabinet finished in white durable enamel with contrasting black steel base. Door is fitted with chrome pulls. Large 24x20 size, finest white acid resisting lavatory top, gleaming finish is easy to clean and affords the maximum in appearance and sanitation. Chromium plated hexagon design combination supply and pop-up waste fixture, 1½ in. brass chromium plated lavatory trap and ¾ in. brass chromium plated supply pipe. Height of top of shelf back 32½ in., width 24 in., depth 20 in., w't each 110 lbs.

W395ULD0each **\$32.25**

If Wanted with Fittings to Floor Instead of Wall add **\$1.50**



LARGE ROOMY BOWL

- LOW SHELF BACK
- POP-UP WASTE
- ACID RESISTING

Enameled octagonal shelf type lavatory with enameled pedestal, chromium plated combination supply with pop-up waste. ¾ in. I. P. size chromium plated brass supplies to wall. 1½ in. chromium plated brass trap with escutcheon. Size overall 20x24 in., w't 85 lbs.

With Chromium Fixtures

W340ULD0each **\$27.85**

If Wanted with Fittings to Floor Instead of Wall add **\$1.50**

Without Fixtures

W340LD0each **\$17.95**

Hibbard Classic LAVATORIES

PORCELAIN ENAMELED STEEL—ACID RESISTING

32 25
24 50
65
121 20

DEEP ROOMY BOWL

- LARGE HANDY SHELF
- CHROMIUM TRIM

New shelf pattern enameled apron lavatory with integral back, and patent overflow, concealed hangers. Chromium plated combination supply fixture with pop-up drain fixture. $\frac{3}{8}$ in. I. P. size chromium brass supplies to wall, $1\frac{1}{4}$ in. chromium plated brass "P" trap with escutcheon. Size 20x24 in., w't each 55 lbs.



With Chromium Fixtures

W345ULD0each **\$18.95**

For Fittings to Floor.....add **\$1.50**

Without Fixtures

W345LD0each **\$9.25**



- ART DESIGN FITTINGS
- ADJUSTABLE CHROME LEGS
- PATENT OVERFLOW

Enameled octagonal shelf lavatory with chromium plated legs and chromium plated combination supply with pop-up waste. $\frac{3}{8}$ in. I. P. size chromium plated brass supplies to wall. $1\frac{1}{4}$ in. chromium plated brass "P" trap with escutcheon. Size overall 20x24 in., w't 55 lbs.

With Chromium Fixtures

W350ULD0—With Chrome Legs.....each **\$23.25**

For Fittings to Floor.....add **\$1.50**

Without Fixtures

W350LD0—With Chrome Legs.....each **\$13.50**

Hibbard MODERN LAVATORIES

HANDY SHELF MODEL



- LARGE ROOMY BOWL
- FOUR INCH SHELF BACK
- TRIP ACTION WASTE

Enameled octagonal shelf lavatory with chromium plated hexagonal legs and chromium plated combination supply with pop-up waste through back. $\frac{3}{8}$ in. I. P. size chromium plated brass supplies to wall. $1\frac{1}{4}$ in. chromium plated brass "P" trap with escutcheon. Size overall 18x21 in. Size of bowl $13\frac{1}{2}$ x11 in., 4 in. shelf, w't 115 lbs.

Without Towel Racks

W1550MLD0 —White	each	\$29.10
W1550$\frac{1}{2}$MLD0 —Acid Resisting White.....	each	32.25

With Towel Racks

W1552MLD0 —White	each	\$34.75
W1552$\frac{1}{2}$MLD0 —Acid Resisting White.....	each	37.75

For Fittings to Floor.....add **\$1.50**

**ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—
USING SAME NUMBERS AND SPECIFY COLORS**

VITREOUS CHINA—ACID RESISTING

- ART DESIGN FITTINGS
- HEAVY CHROME LEGS
- CONCEALED OVERFLOW

Colonial design, vitreous china lavatory with integral overflow and splash rim, chromium plated adjustable hexagon legs and compression. Combination lavatory supply and pop-up drain fixture. $\frac{3}{8}$ in. I. P. size brass supplies to wall. $1\frac{1}{4}$ in. chrome plated brass "P" trap with escutcheon. Size 20x24 in. overall, approx. shipping w't 85 lbs.

W1097CLD0 —With Chrome Towel Racks.....	each	\$39.25
W1098CLD0 —Without Towel Racks.....	each	35.75

For Fittings to Floor.....add **\$1.50**




ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard

LAVATORIES

**Vitreous China—Acid Resisting**

- DRESSING TABLE SHELF
- ATTRACTIVE PANELED BACK
- EXTRA LARGE BOWL

Martha Washington Vitreous China Dressing Table Lavatory with 6½ in. wide raised shelf back. Octagonal basin, integral hooded overflow and anti-splash rim, supported on two chromium plated hexagonal stepped pattern legs and chromium plated wall brackets. Chromium plated combination fitting with metal nozzle and snap action pop-up waste. ¾ in. supplies and 1¼ in. "P" trap. Size overall 21x24 in., size of basin 12x17 in., w't each 110 lbs.

W3140LD0—Without Towel Rackseach \$56.25

W3141LD0—With Towel Rackseach 61.75

**Enameled Iron—Acid Resisting**

- CHROME UNIT FAUCET
- INTEGRAL SOAP DISH
- CONCEALED OVERFLOW

Enameled octagonal shelf lavatory with adjustable chromium plated hexagonal legs and chromium plated combination supply and pop-up waste. ¾ in. chromium plated brass supplies to wall. 1¼ in. chromium plated brass "P" trap with escutcheon. Size overall 22x20 in., 3 in. shelf, w't 115 lbs.

W711ULD0—With Chrome Towel Racks.....each \$37.50

W712ULD0—Without Towel Rackseach 34.35



For Fittings to Floor.....add **\$1.50**

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard COLONIAL PEDESTAL LAVATORIES



No. W40CLD0

Enameled iron apron lavatory with enameled pedestal. Compression lavatory faucets. Indexed handles. Pop-up drain fixture. $\frac{3}{8}$ in. I. P. size brass supplies to wall, less stop cocks on supply pipes. Chrome plated brass "P" trap with escutcheon.

Size of lavatory 20x24 in., size of bowl 12x16 in. approximate shipping w't 165 lbs.

With Chromium Fixtures

W40ELD0—Whiteeach **\$25.80**
 W41 $\frac{1}{2}$ ELD0—Acid Resisting White.....each **28.75**
 For Fittings to Floor.....add **\$1.50**

Without Fixtures

W40LD0—Whiteeach **\$19.75**
 W41 $\frac{1}{2}$ LD0—Acid Resisting White.....each **22.65**

Enameled iron apron lavatory with enameled pedestal. Compression combination supply and pop-up drain fixture. Chromium plated $\frac{3}{8}$ in. I. P. size brass supplies to wall. $1\frac{1}{4}$ in. chromium plated brass "P" trap with escutcheon. Size of lavatory 20x24 in., size of bowl 12x16 in., approximate shipping w't 165 lbs.

With Hexagon Design Chromium Fixtures

W40CLD0—Whiteeach **\$31.95**
 W41 $\frac{1}{2}$ CLD0—Acid Resisting White.....each **34.95**
 For Fittings to Floor.....add **\$1.50**

Without Fixtures

W40LD0—Whiteeach **\$19.75**
 W41 $\frac{1}{2}$ LD0—Acid Resisting White.....each **22.65**



No. W40ELD0

ACID RESISTING IN COLORS ADD 25% TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard COLONIAL PEDESTAL LAVATORIES



Enameled iron apron lavatory with enameled pedestal, compression supply fixture, chain and plug waste. Chromium plated $\frac{3}{8}$ in. I. P. size brass supplies to wall. Chromium plated brass "P" trap with escutcheon. Size of lavatory 20x24 in., size of bowl 12x16 in., approx. shipping w't 165 lbs.

With Chromium Fixtures

W840PLD0—Whiteeach **\$28.15**
W841 $\frac{1}{2}$ PLD0—Acid Resisting White.....each **31.00**

For Fittings to Floor.....add **\$1.50**

Without Fixtures

W840LD0—Whiteeach **\$19.75**
W841 $\frac{1}{2}$ LD0—Acid Resisting White.....each **22.65**

Enameled iron apron lavatory with enameled pedestal. Compression combination supply and pop-up drain fixture. Chromium plated $\frac{3}{8}$ in. I. P. size brass supplies to wall. Chromium plated brass "P" trap with escutcheon. Size of lavatory 20x24 in., size of bowl 12x16 in., approximate shipping w't 165 lbs.

With Chromium Fixtures

W840ULD0—Whiteeach **\$29.95**
W841 $\frac{1}{2}$ ULD0—Acid Resisting White.....each **32.95**

For Fittings to Floor.....add **\$1.50**

Without Fixtures

W840LD0—Whiteeach **\$19.75**
W841 $\frac{1}{2}$ LD0—Acid Resisting White.....each **22.65**



ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard LAVATORIES



- DRESSING TABLE SHELF
- TRIP ACTION WASTE
- DEEP ROOMY BOWL

New shelf pattern enameled iron apron lavatory with integral back, and patent overflow, concealed hangers. Chromium plated combination supply fixture with pop-up through back, pop-up drain fixture. $\frac{3}{8}$ in. I. P. size chromium brass supplies to wall, $1\frac{1}{4}$ in. chromium plated brass "P" trap with escutcheon.

White

W1562MLD0 —17×19 in., w't 85 lbs.....each	\$19.00
W1563MLD0 —18×21 in., w't 105 lbs.....each	21.45

Acid Resisting White

W1562$\frac{1}{2}$MLD0 —17×19 in., w't 85 lbs.....each	\$20.25
W1563$\frac{1}{2}$MLD0 —18×21 in., w't 105 lbs.....each	24.00

For Fittings to Floor.....add **\$1.50**

Colonial Pedestal Lavatory



White Vitreous China

Octagonal Vitreous China Lavatory with paneled top, octagonal basin with hooded overflow, anti-splash rim, paneled octagonal pedestal and wall brackets; fitted with combination supply pop-up waste. Chromium handles and escutcheons, $\frac{3}{8}$ in. I. P. S. supplies and $1\frac{1}{4}$ in. cast brass "P" trap. Size 22×27 in., w't each 20 lbs.

W330OCLD0each **\$49.65**

For Fittings to Floor.....add **\$1.50**

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Dressing Table



White Vitreous China

30 in. long, 18 in. wide, complete with chromium plated hexagonal stepped pattern legs and chromium plated wall brackets, w't each 125 lbs.

W4475LD0each **\$61.25**

Hibbard

COLONIAL WALL LAVATORIES

Chromium Unit Type Faucet

Enameled Iron Apron Lavatory with integral back, and concealed hangers. Combination supply fixture. Chain and plug waste, chromium plated. 3/8 in. I. P. size brass supplies to wall, chromium plated. 1 1/4 in. chromium plated brass "P" trap with escutcheon.

Size, in.	17x19	18x21
Approx. shipping w't, lbs.	75	90

With Chromium Fixtures

White		
Size, in.	17x19	18x21
Nos.	W850PLD0	W845PLD0
Each.	\$16.40	18.35
Acid Resisting White		
Size, in.	17x19	18x21
Nos.	W851 1/2 PLD0	W846 1/2 PLD0
Each.	\$17.25	18.95
For Fittings to Floor.....add \$1.50		

Without Fixtures

White		
Size, in.	17x19	18x21
Nos.	W850LD0	W845LD0
Each.	\$8.00	9.90
Acid Resisting White		
Size, in.	17x19	18x21
Nos.	W851 1/2 LD0	W846 1/2 LD0
Each.	\$8.50	10.60



COLONIAL UNIT TYPE FAUCET WITH POP-UP WASTE

Enameled Apron Lavatory with integral back, concealed hangers. Compression combination supply and pop-up drain fixture. Chromium plated 3/8 in. I. P. size brass supplies to wall, less cocks in supply pipes. Chromium plated 1 1/4 in. plated brass "P" trap with escutcheon.

Size, in.	17x19	18x21
Approx. shipping w't, lbs.....	75	90

With Chromium Fixtures

White		
Size, in.	17x19	18x21
Nos.	W850ULD0	W845ULD0
Each.	\$17.75	19.75
Acid Resisting White		
Size, in.	17x19	18x21
Nos.	W851 1/2 ULD0	W846 1/2 ULD0
Each.	\$18.35	20.35
For Fittings to Floor.....add \$1.50		

Without Fixtures

White		
Size, in.	17x19	18x21
Nos.	W850LD0	W845LD0
Each.	\$8.00	9.90
Acid Resisting White		
Size, in.	17x19	18x21
Nos.	W851 1/2 LD0	W846 1/2 LD0
Each.	\$8.50	10.60



ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Hibbard COLONIAL APRON LAVATORIES



High Back Protects the Wall

Enameled Apron Lavatory with integral back, and concealed hangers. Compression Faucets and pop-up drain fixture. $\frac{3}{4}$ in. I. P. size brass supplies to wall, less cocks in supply pipes. $1\frac{1}{4}$ in. plated brass "P" trap with escutcheon. Size 18x21 in., approx. shipping w't 90 lbs.

With Chromium Fixtures

W45ELD0 —White	each	\$18.25
W46$\frac{1}{2}$ELD0 —Acid Resisting White.....	each	18.95

With Fittings to Floor.....add **\$1.50**

Without Fixtures

W45LD0 —White	each	\$ 9.90
W46$\frac{1}{2}$LD0 —Acid Resisting White.....	each	10.60

Compare These Values

Enameled Apron Lavatory, integral back, concealed hanger and chain. P. O. plug, chain and stopper. Compression lavatory faucets, index button 4 arm handles, $\frac{3}{4}$ in. I. P. size brass supplies to wall, less cocks in supply pipe. $1\frac{1}{4}$ in. chrome plated brass "P" trap with escutcheon. Size, in. 17x19 18x21
approx. shipping w't, lbs. 75 90

With Nickel Fixtures

W50HLD0 —White,	
17x19 in.	each \$13.75
18x21 in.	each 15.65
W51$\frac{1}{2}$HLD0 —Acid Resisting White,	
17x19 in.	each \$15.65
18x21 in.	each 16.25

With Chromium Fixtures

W50JLD0 —White,	
17x19 in.	each \$14.35
18x21 in.	each 16.25
W51$\frac{1}{2}$JLD0 —Acid Resisting White,	
17x19 in.	each \$16.25
18x21 in.	each 16.95

With Fittings to Floor.....add **\$1.50**



Without Fixtures

W50LD0 —White,		W51$\frac{1}{2}$LD0 —Acid Resisting White,	
17x19 in.	each \$8.00	17x19 in.	each \$ 9.90
18x21 in.	each 9.90	18x21 in.	each 10.60

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard WALL LAVATORIES



Enameled Iron Round Front Narrow Wall Lavatory with Back and Apron, Oval Basin with Center Outlet, on Concealed Wall Hanger, Chromium Compression Faucets, $1\frac{1}{4}$ in. chromium "P" Trap, $\frac{3}{8}$ in. Chromium Supplies, less Angle Stop Valves. Size 14×26 in. overall, 10×16 in. basin. W't each 80 lbs.

With Chromium Fixtures

W61JLD0—Whiteeach **\$19.15**

Without Fixtures

W61LD0—Whiteeach **\$12.90**



One of our outstanding values. Specially priced to enable you to meet any competition. Enameled Iron Round Front Apron Lavatory, integral back, patent overflow and concealed hanger. Nickel plated compression faucets, supply and drain fixtures. $\frac{3}{8}$ in. I. P. size brass supplies to wall $1\frac{1}{4}$ in., brass "P" trap. Size 17×19 in. W't 75 lbs.

With Chromium Fixtures

W53JLP0—Whiteeach **\$13.15**

Without Fixtures

W53LD0—Whiteeach **\$7.10**

W64LD0—Whiteeach **\$6.75**

If Wanted with Fittings to Floor Instead of Wall.....add **\$1.50**



Vitreous China Narrow Pattern Lavatory with Octagonal Front and Integral Back, Rectangular Basin with Patent Overflow and Concealed Hanger; fitted with Chromium Combination Supply and Pop-up Waste Lever on back, $\frac{3}{8}$ in. Chromium Supplies and $1\frac{1}{4}$ in. Chromium "P" Trap. Size 13×20 in. overall, basin $9\frac{1}{2}\times 13$ in. W't each 55 lbs.

W99KLD0—Whiteeach **\$26.35**



White Enameled Iron Round Front Roll Rim Lavatory with integral back, patent overflow, concealed hanger and nickel plate chain stay. Nickel plated P. O. plug, chain and stopper. Compression lavatory faucet, index button 4-arm handle. Nickel plated $\frac{3}{8}$ in. I. P. size brass supplies to wall. $1\frac{1}{4}$ in. plated brass "P" trap with escutcheon. Size 17×19 in. W't each 60 lbs.

With Nickel Fixtures

W64HLD0—Whiteeach **\$11.95**

Without Fixtures

Hibbard

WALL LAVATORIES



SPECIFY

SIZE

WANTED

Enameled Iron Corner Apron Lavatory with integral back, patent overflow, concealed hanger chain stay. P. O. plug, chain and stopper. Compression lavatory faucet. Nickel plated $\frac{3}{8}$ in. I. P. size brass supplies to wall. $1\frac{1}{4}$ in. plated brass "P" trap with escutcheon.

With Chromium Fixtures

Size, in.	$16\frac{1}{2} \times 16\frac{1}{2}$	19x19
Approx. shipping w't, lbs.	75	100
W60JLD0	each \$17.45	20.35

Without Fixtures

No. W60LD0

$16\frac{1}{2} \times 16\frac{1}{2}$ in.	each \$11.15
19 x 19 in.	each 15.10

For Fittings to Floor.....add **\$1.50**



Enameled Iron Apron Lavatory with integral back, concealed hanger with chain stay. P. O. plug, chain and stopper. Compression lavatory faucets, index button 4-arm handle. $\frac{3}{8}$ in. I. P. size brass supplies to wall. $1\frac{1}{4}$ in. plated brass "P" trap with escutcheon. Size 18x24 in. W't each 105 lbs.

With Chromium Fixtures

W55JLD0—Whiteeach **\$16.50**

Without Fixtures

W55LD0—Whiteeach **\$10.25**

PORCELAIN ENAMELED STEEL LAVATORIES AND SINKS



Faucets and Strainer Not Included

Stamped in one piece, 20 gauge steel, finished inside and outside with three coats of porcelain enamel. Rounded corners.

W692LD0—14x16 $\frac{1}{2}$ in. overall, can be used only with individual faucets, not drilled for pop-up waste, w't each 14 lbs., each**\$4.50**

LIGHT WEIGHT
IDEAL FOR USE IN
TRAILERS,
SUMMER HOMES,
GARAGES, ETC.



Without Fittings

W1624LD0—16x24 in. overall, can be used with any regular strainer, w't each 8 lbs.....each **\$3.75**

Prices Net F.O.B. Chicago, Add Freight to _____

SPECIAL!

Hibbard "CLASSIC"

THE MODERN NEW STYLE CLOSET



1752

**A Quality Closet at a
Very Low Cost—Very
Quiet in Operation**



This type of closet is rapidly growing in popularity. It is not only better but better looking, more compact and more easily installed.

Just think it costs you only very little more than a regular wash down closet, because of the special construction of the bowl and special fittings in the tank the closet is practically noiseless in operation. Heavy, full size, syphonic jet action bowl with whirl pool action.

The tank sets away from the wall so that the roughing may vary from 12 to 14 in. from center of outlet to wall.

You will be more than pleased with this closet. Complete with guaranteed 1 1/4 in. seat and supply to floor, w't each 120 lbs.

3 ATTRACTIVE MONEY SAVER OFFERS

W23LD0—Without seat and supply pipe,
each **\$19.25**

W24LD0—Complete with 5 year
guaranteed white enameled seat
and supply pipe,
each **\$23.95**

W25LD0—Complete with 5 year
guaranteed mother of pearl celluloid covered seat and supply pipe,
each **\$26.95**

PRICES ON ABOVE IN COLORS ON APPLICATION

Prices Net F.O.B. Chicago, Add Freight to _____



Hibbard "New Era" Wash Down Closet Combination

This combination combines the distinctive features of the New Era bowl with the Colonial pattern, shelf top tank. Regularly furnished with chromium-plated trip lever, flush elbow and supply to floor.

The bowl combines the "humpless" feature of the New Era washdown, with the outstanding sanitary features. Does not require a special seat. Any recognized manufacturers' seat will fit.

Regularly furnished for 14 in. rough-in. For 12 in. specify on order. W't each 120 lbs.

With 11¼ In. Seat Guaranteed for Three Years

W16LD0 —With Mahogany Seat	each	\$18.45
W17LD0 —With White Seat	each	18.75
W18LD0 —With Golden Oak Seat.....	each	18.45

With 11½ In. Seat Guaranteed for Five Years

W516LD0 —With Mahogany Seat	each	\$19.50
W517LD0 —With White Seat	each	19.85
W518LD0 —With Golden Oak Seat.....	each	19.50

Bowls Only, w't 50 lbs.

W221LD0 —14 in. rough-in	each	\$6.75
W221½LD0 —12 in. rough-in	each	6.75

Tank Only, w't 70 lbs.

W231LD0	each	\$9.25
----------------------	------	---------------

Tank Covers

W232LD0 —For W231LD0 Tank.....	each	\$3.75
---------------------------------------	------	---------------

Hibbard Wash Down Closet Combination

Heavy Syphon Wash Down Closet, back inlet. Vitreous china low tank, chrome flushing lever, high pressure flush valve and copper ball float, 2 in. chromium plated flush elbow, shipping w't 120 bs.

Will be furnished to rough-in at 14 in. unless otherwise specified, can be furnished in 12 in. at same price. Specify on order.

With 11¼ In Seat and Supply to Floor

W116LD0 —Mahogany Seat	each	\$17.25
W117LD0 —White Seat	each	17.55
W118LD0 —Oak Seat	each	17.25

With 11¼ In. Seat, Without Supply Pipe

W116½LD0 —Mahogany Seat	each	\$16.80
W117½LD0 —White Seat	each	17.10
W118½LD0 —Oak Seat	each	16.80

Bowls Only

W't each 50 lbs.

W678LD0 —14 in. rough-in	each	\$6.35
W680LD0 —12 in. rough-in	each	6.35
W221¾LD0 —10 in. rough-in	each	9.75


Tank Only

W679LD0 —W't each 70 lbs.	each	\$8.75
---------------------------------------	------	---------------

Tank Covers

W682LD0 —For W679LD0 Tank	each	\$3.75
--	------	---------------

PRICES ON ABOVE IN COLORS ON APPLICATION



Hibbard CLOSETS

Heavy Syphon Jet



Heavy Syphon Jet Bowl with Top Inlet; Vitreous China Octagonal Pattern Tank, fitted with High Grade Flushing Valve, Full Elevated High Pressure Ball Cock, Chromium Double Acting Top Swinging Lever and Straight China Flush Connection, Chrome Supply Less Angle Stop. All White Seat and Cover with Chrome Finished Hinge. W't each 150 lbs.

W109LD0each **\$33.95**

Regular Syphon Jet



Regular Syphon Jet Bowl, with Top Inlet; Vitreous China Octagonal Pattern Tank, fitted with High Grade Flushing Valve, Full Elevated High Pressure Ball Cock, Chromium Double Acting Top Swinging Lever, 2 in. Chromium Offset Flush Connection, Chrome Supply Less Angle Stop. All White Seat and Cover with Chrome Finished Hinge. W't each 140 lbs.

W108LD0each **\$26.75**

Reverse Trap



Reverse trap syphon action bowl, back inlet, vitreous China octagonal pattern tank, fitted with high grade flushing valve, full elevated high pressure ball cock, chromium double acting top swinging lever, 2 in. chromium flush ell, chromium supply less angle stop. High grade white finish seat and cover with chrome heavy bar hinge. W't each 140 lbs.

W120LD0each **\$23.25**

Seat Action



Syphon action washdown bowl with plain rim, back inlet and jet, vitreous China concealed tank fitted with high grade flushing valve, full elevated high pressure ball cock, 2 in. chromium flush ell and wall flanges, seat action tripping device with chromium lever through wall and wall flange, heavy mahogany seat with chrome bar hinge. W't each 145 bs.

F5401LD0each **\$43.25★**

HEAVY SYPHON JET CLOSETS



Heavy syphon jet bowl with plain rim and top inlet, fitted with chromium flushing valve with oscillating handle, chromium shut-off and volume control union angle stop and wall flange. All white seat and cover with chrome finished hinge, w't each 80 lbs.

F130LD0each \$32.25★



Heavy syphon jet bowl with oval extended rim and top inlet, fitted with chromium flushing valve with oscillating handle, chromium shut-off and volume control union angle stop and wall flange. Guaranteed ebony finish vulcanized hard rubber open front seat with chrome heavy bar hinge, w't each 85 lbs.

F131LD0each \$37.50★

CONCEALED VALVE SYPHON JET CLOSETS

Valve closets of unique design having practically the entire valve concealed. This presents a very clean cut appearance which is specially appreciated when the advantage of a flushing valve closet is desired for the better home, apartment or hotel.



Syphon jet bowl with extended lip, integral valve housing on back with removable china cover, fitted with flushing valve with oscillating handle and adjustable flange, chromium shut-off and volume control union angle stop and wall flange. All white extended lip closed front seat and cover with chrome finished hinge, w't each 85 lbs.

F5850LD0each \$39.95★



Syphon jet bowl with extended lip, integral valve housing on back with removable china cover, fitted with flushing valve with oscillating handle and adjustable flange, chromium shut-off and volume control union angle stop and wall flange. Ebony finish vulcanized hard rubber extended lip open front seat with chrome heavy bar hinge, w't each 85 lbs.

F5851LD0each \$42.25★

WALL HANGING CLOSETS



Wall hanging blowout bowl with extended lip and back inlet, extra large water area, large trapway and deep seal, supported on cast iron hanger, fitted with concealed flushing valve with exposed oscillating handle and shut-off and volume control union stop. Ebony finish vulcanized hard rubber seat with chromium heavy bar hinge. W't each 100 lbs.

F6511LD0each **\$37.25★**



Wall hanging blowout bowl with extended lip and side inlet, extra large water area, large trapway and deep seal, supported on cast iron hanger, fitted with chromium flushing valve with oscillating handle, chromium shut-off and volume control union straight stop and wall flange. Ebony finish vulcanized hard rubber seat with chromium heavy bar hinge. W't each 100 lbs.

F6512LD0each **\$37.25★**

Heavy Syphon Jet Closets



Heavy syphon jet bowl with oval extended rim and side inlet, fitted with chromium flushing valve with oscillating handle, chromium shut-off and volume control union straight stop and wall flange. Ebony finish vulcanized hard rubber open front seat with chromium heavy bar hinge. W't each 85 lbs.

F132LD0each **\$37.50★**

Bidet Closets



Vitreous china bidet with flushing rim and center spray douche, combination hot and cold water supply to flushing rim and douche with metal cross handles and escutcheons, chromium supply pipes to floor. Chromium snap action pop-up waste with metal escutcheon and knob. (Rim and douche not separately controlled.) W't each 70 lbs.

F4485LD0each **\$43.25★**

Closet Bowls

NEW ERA WASHDOWN



Syphon wash down closet bowl with jet and plain front with 2 in. back inlet spud. Approx. shipping w't 45 lbs.

White, for 12 in. Rough-in
W221 $\frac{1}{2}$ LD0...each **\$6.75**

White, for 14 in. Rough-in
W221LD0....each **\$6.75**

REGULAR WASHDOWN

Syphon wash down closet bowl with jet and hump front with 2 in. back inlet spud. Approx. shipping w't 45 lbs.

White, for 14 in. Rough-in
W678LD0....each **\$6.35**

White, for 12 in. Rough-in
W680LD0....each **\$6.35**

White, for 10 in. Rough-in
W221 $\frac{3}{4}$ LD0...each **\$9.75**



REVERSE TRAP



Reverse trap syphon wash down closet bowl with plain front, 2 in. back inlet spud. For 14 in. rough. Approx. shipping w't 55 lbs.

W222 $\frac{1}{2}$ LD0 White, for 12 in. Rough-ineach **\$8.25**

W222LD0 White, for 14 in. Rough-ineach **\$8.25**

SYPHON JET

Syphon jet closet bowl, plain front and 2 in. top inlet spud. For 14 in. rough. Approx. ship. w't 55 lbs.



W210LD0 White, for 14 in. Rough-ineach **\$12.75**

Closet Tanks

LOW DOWN TYPE



Vitreous China


6 gal. vitreous low pattern closet tank with shelf cover and screws. Operating lever chromium finish. High pressure float valve, refill and copper ball concealed supply. Douglas type flush valve and rubber ball 2 in. chromium elbow flush connection with slip joint coupling. Approx. shipping w't 80 lbs.

W679LD0each **\$8.75**

Enameled Cast Iron

6 gal. low pattern closet tank with shelf cover and screws. Operating lever chromium finish. High pressure float valve, refill and copper ball concealed supply. Douglas type flush valve and hard rubber ball 2 in. chrome elbow flush connection with slip joint coupling, w't each 100 lbs.

W1000LD0—each**\$13.50**



HIGH TYPE



6 gal. cast iron, white enameled inside, painted outside, high pattern closet tank with hanger, top supply high pressure float valve and copper ball, galvanized flush valve and gasket with lever and rest, brass tank seat, with chain and wood pull. Approx. shipping w't 80 lbs.

F235LD0each **\$17.50***

6 gal. size, light oak finish. Copper lined with float valve and copper tank float. Quality ball cock with brass seat and lever. Complete with chain and pull.

Length at top 19 $\frac{1}{2}$ in., width at top 10 $\frac{1}{4}$ in. Length at bottom 18 $\frac{1}{2}$ in., width at bottom 7 $\frac{3}{4}$ in., w't each 20 lbs.

For 1 $\frac{1}{2}$ in. Flush Pipe

W375LD0—Top Supplyeach **\$8.35**

W376LD0—Bottom Supplyeach **8.35**

For 1 $\frac{1}{2}$ in. Flush Pipe


W377LD0—Top Supplyeach **\$8.35**

W378LD0—Bottom Supplyeach **8.35**



VITREOUS CHINA STALL URINALS

Made of Genuine Vitreous China, the same high grade vitreous china as our finest lavatories; they will not discolor or craze, the glaze will not chip and they are guaranteed to be non-absorbent and to withstand the U. S. Government "Red Ink" test.



No. F8300LD0

Battery Vitreous China Urinal stalls with 3/4 in. top inlets and integral flushing rims with interlocking china partitions with extended wing shields; vitreous china high tank, automatic top supply fittings, C. P. offset flush pipe and cast brass outlet strainers with china grates and couplings for 3 in. iron pipe. Height overall 42 in., height above floor 38 1/4 in., wall to front of lip 15 in.

Furnished with 2 In., 3 In. and 6 In. Partitions Between Stalls—Specify Width Wanted in Ordering—Prices Below Are for 3 In. Width Partitions

With Wing Shields

No. F8000LD0

- 18 in. Single Stall, w't each 250 lbs.....each \$78.00★
- 21 in. Single Stall, w't each 280 lbs.....each 83.50★

No. F8020LD0

- 18 in. Double Stalls, w't each 500 lbs.....each \$147.00★
- 21 in. Double Stalls, w't each 575 lbs.....each 159.00★

No. F8030LD0

- 18 in. Triple Stalls, w't each 750 lbs.....each \$220.35★
- 21 in. Triple Stalls, w't each 850 lbs.....each 238.35★

Without Wing Shields

No. F8001LD0


- 18 in. Single Stall, w't each 240 lbs.....each \$72.60★
- 21 in. Single Stall, w't each 265 lbs.....each 78.00★

No. F8200LD0


- 18 in. Double Stall, w't each 480 lbs.....each \$135.00★
- 21 in. Double Stall, w't each 530 lbs.....each 147.00★

No. F8300LD0

- 18 in. Triple Stall, w't each 725 lbs.....each \$202.35★
- 21 in. Triple Stall, w't each 800 lbs.....each 220.35★




No. F8000LD0



No. F8001LD0

VITREOUS CHINA STALL URINALS

Made of Genuine Vitreous China, the same high grade vitreous china as our finest lavatories: they will not discolor or craze the glaze will not chip and they are guaranteed to be non-absorbent and to withstand the U. S. Government "Red Ink" test.



No. F8026LD0

Battery Vitreous China Urinal Stalls with $\frac{3}{4}$ in. top inlets and integral flushing rims with interlocking china partitions with extended wing shields; fitted with C. P. urinal flushing valves with china oscillating handles and C. P. shut-off and volume control union angle stops and wall flanges, cast brass outlet strainers with china grates and couplings for 3 in. iron pipe. Height overall 42 in., height above floor 38 $\frac{1}{4}$ in., wall to front of lip 15 in.

With Wing Shields

No. F8005LD0

18 in. Single Stalls, w't each 205 lbs.....	each	\$73.20★
21 in. Single Stalls, w't each 225 lbs.....	each	81.00★

No. F8025LD0

18 in. Double Stalls, w't each 425 lbs.....	each	\$147.90★
21 in. Double Stalls, w't each 475 lbs.....	each	165.25★

No. F8035LD0

18 in. Triple Stalls, w't each 635 lbs.....	each	\$231.50★
21 in. Triple Stalls, w't each 700 lbs.....	each	253.75★

Without Wing Shields

No. F8006LD0


18 in. Single Stalls, w't each 205 lbs.....	each	\$70.50★
21 in. Single Stalls, w't each 225 lbs.....	each	77.40★

No. F8026LD0

18 in. Double Stalls, w't each 425 lbs.....	each	\$139.50★
21 in. Double Stalls, w't each 475 lbs.....	each	155.75★

No. F8036LD0

18 in. Triple Stalls, w't each 635 lbs.....	each	\$216.90★
21 in. Triple Stalls, w't each 700 lbs.....	each	\$229.75★




No. F8006LD0



No. F8005LD0

WALL HANGING URINALS




Wall Hanging Urinal Stall with 1½ in. back inlet, integral extended wing shields, strainer and trap with cleanout and 2 in. flanged back outlet connection.

Less all fittings.


Width overall, in.....	18	24
Height overall, in.....	31½	31½
W't each, lbs.....	130	170
Nos.	F8102LD0	F8103LD0
Each.....	\$46.25★	81.50★

Wall Hanging Urinal Stall with ¾ in. top inlet, integral extended wing shields, strainer and trap with cleanout and 2 in. flanged back outlet connection.

Valve not included in price.



Width overall, in.....	18	24
Height overall, in.....	31½	31½
W't each, lbs.....	130	170
Nos.	F8100LD0	F8101LD0
Each.....	\$46.25★	81.50★



Vitreous China Urinal with integral strainer, ¾ in. top inlet and 1½ in. bottom outlet, size 13½×18 in., w't 45 lbs.

F8230LD0.....each \$14.75★

Urinal Tanks




Vitreous China High Tank with automatic top fill fittings.

Size, in.	10×7½×12½	15×7½×12½	17×8½×12½
Capacity, gal.	2½	4	5
W't each, lbs.....	35	50	60
Nos.	F2LD0	F4LD0	F6LD0
Each.....	\$20.45★	21.75★	25.25★

Troughs

Enameled cast iron roll rim Urinal Trough with 10 in. integral back, concealed hanger, nickel plated brass beehive strainer, coupling and tail-piece, nickel plated brass perforated wash down pipe with end cap and supports. Loose key compression stop for continuous flow.

Length, in.	24	36	48	60
Approx. shipping w't, lbs.....	80	125	150	190
F11LD0	each \$25.35★	31.85★	43.75★	54.25★



SHOWER BATH STALLS

"Junior"

Completely Equipped, Self-Contained Cabinet That Combines
Three Outstanding Features

ECONOMY OF SPACE

LOWEST INSTALLATION COST

EFFICIENCY IN OPERATION

Easily and quickly installed in any room, closet or space in the home or building where water supply lines and wastepipes are available. Especially adaptable for use in basements or "clean-up" rooms where people who work or play outdoors can step in for a cooling and refreshing shower. Easily installed as a single unit or in groups in clubs, workshops, dormitories and public buildings.

Size: 30x30x76 In.

The walls are made of galvanized copper bearing steel, prepared for enamel or duco finish. The receptor or base is made of heavy gauge copper bearing steel, hot galvanized after fabrication and chemically treated in preparation for enamel or duco finish. Crated in "knock-down" sections, each section easily carried through any door or hallway to the place of installation.

Complete with satin finish chromium plated brass two valve shower with self-cleansing shower head and arm, waste strainer, soap dish and white duck curtain equipped with rings, w't each 160 lbs.

W30LD0—Right hand valves.....each **\$37.95**
W31LD0—Left hand valves.....each **37.95**

SHIPPED KNOCKED DOWN

Ambassador

Walls made of galvanized copper bearing steel prepared for enamel or duco finish. Receptor or base is made of heavy gauge copper bearing steel hot galvanized after making and chemically treated for enamel or duco finish. Outlet connection is a part of base making a leak proof 2 in. connection for caulking iron pipe. Complete with chromium plated strainer, shower head and valves. Soap dish and curtain rod and white waterproof duck curtain.

Size 32x32x76 in., w't 225 lbs.

W32LD0—Right hand valves.....each **\$64.95**
W33LD0—Left hand valves.....each **64.95**

Size 36x36x76 in., w't 285 lbs.

W36LD0—Right hand valves.....each **\$67.95**
W37LD0—Left hand valves.....each **67.95**

SHIPPED KNOCKED DOWN

Weistall Integral

The original Weis Cabinet Shower developed 16 years ago—a one-piece heavy-duty unit designed for sturdy utility. It has earned and holds a definite place for many institutional and industrial applications.

Construction—The Weistall walls are formed from a single piece of $\frac{3}{8}$ in. metal with the $\frac{1}{2}$ in. bottom electrically welded into a one-piece integral unit. Building door or window openings must be large enough to accommodate the one-piece unit in size selected.

Material—Series S— $\frac{1}{2}$ in. copper bearing steel walls with $\frac{1}{2}$ in. galvanized steel bottom. Series A— $\frac{1}{2}$ in. aluminum alloy walls and bottom.

Finish—Grey metal primer baked on at 350° F.

Baked enamel finish not available. After installation, cabinets should be given two coats of good quality air drying enamel. Weistall baked on metal primer will not bleed through finish coats.

The bottom and sides, too, if designated to be placed against masonry walls will be given an additional coat of acid proof paint.

Standard Equipment—Brass chromium plated: Two valve unit with adjustable water saver type self cleaning head. Cast waste and strainer for 2 in. pipe, inside caulking. Soap dish. Curtain rod. White duck curtain with chromium rings.

72 In. High—Aluminum Alloy Walls and Base				
Size, in.....	36x36	40x28	28x40	32x32
W't, lbs.....	220	220	220	220
Nos.....	F1ALD0	F2ALD0	F3ALD0	F4ALD0
Each.....	\$86.75★	86.75★	86.75★	78.75★
72 In High—Copper Bearing Steel Walls, Galvanized Bottom				
Size, in.....	36x36	40x28	28x40	32x32
W't, lbs.....	360	360	360	360
Nos.....	F1SLD0	F2SLD0	F3SLD0	F4SLD0
Each.....	\$147.50★	147.50★	147.50★	141.50★

LEHMAN SHOWER BATH DOORS AND BATH TUB SPRAYSHIELDS

Custom Made to Fit Your Own Bath Room—Easy to Install in New or Old Buildings

Beautiful—Sparkling plate glass and rustless chromium bronze are ideal for confining shower splash. The glass is sanitary, ornamental, watertight, light transmitting, non-absorbent, and not subject to mold or deterioration. The bronze, durable and attractive, is brilliant in non-tarnishing chromium. We offer a wide selection of artistic designs, moderate in cost, with ornamented or plain glass, to fulfill your conception of the perfect bath.

Sanitary—Lehman enclosures are clean when new, and built to stay clean, constructed of impervious materials, with a minimum of dirt catching crevices and screw heads. Being reversible, the same elegant finish and freedom from unsanitary corners and pockets are maintained both inside and outside. Nothing to rot, rust, or mold in the Bath Immaculate.



Watertight—Individual tailoring assures accurate fitting and efficiency under severe service conditions. Lehman equipment is structurally rugged, yet flexibly adjustable for settling buildings and walls out of plumb. Its perfection is the result of years of specialization by skilled craftsmen in a specially equipped factory.

Lifetime Service is true economy. The cost is surprisingly low, with no expenditure for maintenance, replacement, or laundering, none of the annoyance and upkeep cost of shower curtains.

Comfort—Lehmanize your bath room and enjoy an invigorating needle shower with freedom from a dark, musty compartment. It will pay daily dividends in health and comfort.

Choice of Models

- Any enclosure made in any quality.
- All custom made, any design or size.
- All frames solid bronze, not thin metal.
- Polished chromium is the regular finish.
- Gold plating and special finishes on order.
- Glass ornamentation is not regular equipment.

Easy Fitting—Lehman equipment is designed for erection after tile, marble and fixtures are in place. It is not necessary to delay building construction for Lehman shower enclosures. Just send us finished dimensions. Do not build your bathroom for us, we fit your bath room.

Guarantee—The design, workmanship and materials are guaranteed by the manufacturer, and the installation is guaranteed by reputable dealers backed by our nation-wide service organization. You may purchase or handle Lehman equipment with assurance and safety, as we recognize our responsibility to render faithful service and to maintain our reputation for superior quality.

Prices on Request—Specify Size of Enclosure



RECESS TYPE DOUBLE DRAINBOARD PANTRY SINKS



Cabinet not Included

Double Drainboard pattern, built integral with single compartment unit, grooved top, back, return ends and partial apron; all metal clad, chrome fittings.

F142WLD0—White Metal

Size, in.	48×24	60×24	72×24
W't each, lbs.....	200	250	300
Each	\$182.50★	202.75★	225.75★

F142SLD0—Stainless Steel

Size, in.	48×24	60×24	72×24
W't each, lbs.....	200	250	300
Each	\$182.50★	202.75★	225.75★

F142MLD0—Monel Metal

Size, in.	48×24	60×24	72×24
W't each, lbs.....	200	250	300
Each	\$182.50★	202.75★	225.75★

Double Drainboard pattern, built integral with single compartment unit, flat top (no groves); all metal clad. Especially adapted for use with kitchen cabinets, chrome fittings.

F132WLD0—White Metal

Size, in.	48×24	60×24	72×24
W't each, lbs.....	150	175	210
Each	\$133.80★	150.50★	167.00★

F132SLD0—Stainless Steel

Size, in.	48×24	60×24	72×24
W't each, lbs.....	150	175	210
Each	\$133.80★	150.50★	167.00★

F132MLD0—Monel Metal

Size, in.	48×24	60×24	72×24
W't each, lbs.....	150	175	210
Each	\$133.80★	150.50★	167.00★



Cabinet not Included

Lady Hibbard *De Luxe* CABINET SINK



Acid Resisting Steel Sink

**THE ULTIMATE IN SMART KITCHEN FURNISHINGS
AN ENTIRELY NEW AND EXCLUSIVE DESIGN**

Styled in Good Taste for Today's and Tomorrow's Home

Equipped with linen drawer and extra large storage compartment with adjustable shelf on left hand side. Has cutlery drawer and two large drawers for storing large utensils, roasters, etc., on right hand side. Large center compartment for dish pan, cleaners, etc.

Top of sink is 36 in. from the floor.

Height 42 in. over all.

Length 60 in., width 24 in.

White Acid Resisting Steel Sink.

Cabinet finished in white baked enamel.

New design chromium pulls.

Complete with chromium plated faucet, 4 in. Duo Strainer and trap to wall. Weight 200 lbs.

W760VLD0—With Faucet as shown each \$73.75

W761VLD0—With Dish Sprayer Faucet each 82.75


With Fittings to Floor add \$1.50



Fitted with Large Duo-Strainer


OUTSTANDING VALUE IN ALL RESPECTS

- Recessed Knee Space.
- Semi-Concealed pattern Chromium Plated, Ledge Type Faucet.
- Handy ledge for holding tumblers, coasters, etc.
- Paneled Design Low Back.



Lady Hibbard

CABINET SINK



Fitted with Large Duo-Strainer

54 IN. DOUBLE DRAINBOARD SINK AND CABINET

LARGE ENOUGH FOR ANY HOME—SAVES VALUABLE SPACE

Equipped with linen drawer and extra large storage compartment with adjustable shelf on left hand side. Has cutlery drawer and large compartment for storing large utensils, roasters, etc., on right hand side. Large center compartment for dish pan, cleaners, etc.

White Acid Resisting Steel Sink.

Cabinet finished in white baked enamel.

New design chromium pulls.

Complete with chromium plated faucet, 4 in. chromium Duo Strainer and trap to wall. W't 160 lbs.

Acid Resisting Steel Sink

- 54 in. long, 24 in. wide.
- Recessed Knee Space.
- Semi-Concealed pattern Chromium Plated Ledge Type Faucet.
- Handy ledge for holding tumblers, coasters, etc.
- Fluted Drainboard, for self-draining.
- Paneled Design low back.
- Built-in Soap Dishes.
- 36 in. high to top of drainboard.

W754VLD0

each \$56.9

With Fittings to Floor.....add \$1.50

Prices Net F.O.B. Chicago, Add Freight to _____

Lady Hibbard CABINET SINK



A DOUBLE DRAINBOARD SINK AND CABINET ONLY 54 IN. LONG

LARGE ENOUGH FOR ANY HOME,
SAVES VALUABLE SPACE

Acid Resisting Steel Sink with Double Drainboard

- Recessed Knee Space.
- Semi-Concealed pattern Chromium Plated Ledge Type Faucet
- Handy ledge for holding tumblers, coasters, etc.
- Fluted Drainboard, for self draining.
- Paneled Design low back.
- Built-in Soap Dishes.



Large Basket
Strainer



Doors and Drawers
Heavily Insulated

Top of sink is 36 in.
from the floor.
Height 42 in. over all,
54 in. long, 24 in.
wide.

An Entirely New and Exclusive Design Cabinet

Equipped with linen drawer and extra large storage compartment with adjustable shelf on left hand side. Has cutlery drawer and large compartment for storing large utensils, roasters, etc., on right hand side. Large center compartment for dish pan, cleaners, etc. White Acid Resisting Steel Sink. Cabinet finished in white baked enamel. New design chromium pulls. Complete with chromium plated faucet, 4 in. Duo Strainer and trap to wall. Weight 160 lbs.

W755VLD0—With Faucet as shown,
each\$64.45

W756VLD0—With Dish Sprayer Faucet,
each\$69.95

With Fittings to Floor.....add \$1.50

Hibbard MODERN KITCHENS

COMBINE BEAUTY, UTILITY AND CONVENIENCE



COURTESY LIBBEY-OWENS-FORD GLASS CO.

Today's Labor-Saving Kitchens

NOW WITHIN THE REACH OF EVERY HOME OWNER



Every woman knows that the all-steel kitchen is "the thing." The sanitary qualities, extra protection, greater durability of steel make ideal for kitchen equipment. The glistening, smooth, easy-to-clean surfaces provide a work place that is an inspiration and a joy to behold. What woman has not longed for such a kitchen — a place for everything, and everything in its place? If only it were possible!


Now it **is** possible! The small home owner and apartment dweller can afford a really modern steel kitchen. **Hibbard** Steel Kitchen Cabinets offer a complete line of standardized units in a variety ample to suit any kitchen arrangement. Begin with one, if you wish, and **add a unit any time** until the kitchen is fully equipped.

CALL UPON OUR SERVICE FOR PLANS
SPECIFICATIONS AND ITEMIZED QUOTATIONS

Hibbard

MODERN PLANNED KITCHENS

COMPLETE UNITS TO FIT ANY KITCHEN



STRAIGHT WALL INSTALLATIONS

In kitchens or kitchenettes where cabinets are wanted on only one wall, and a clear space on that wall of nine to twelve feet is open for cabinets, here are some custom planned groupings all ready to install. Continuous one piece linoleum tops are provided where these set-ups can be used.

9 FOOT KITCHEN

Consists of two F2430—24x30 in. wall cabinets, two F241—24 in. table base cabinets, two moulding strips for water tight connections and W1938—60 in. acid resisting sink with cabinet, complete with chromium fittings.

F108LD0—W't each 820 lbs. each **\$197.95★**

10 FOOT KITCHEN

Consists of four F1830—18x30 in. wall cabinets, two F301—30 in. table base cabinets, two moulding strips for water tight connections and W1938—60 in. acid resisting sink with cabinet, complete with chromium fittings.

F120LD0—W't each 920 lbs. each **\$221.85★**

12 FOOT KITCHEN

AS ILLUSTRATED ABOVE

Consists of one F1830—18x30 in. wall cabinet, two F2430—24x30 in. wall cabinets, One F802—18x84 in. broom cabinets, one F181—18 in. and two F241—24 in. table bases, two moulding strips for water tight connections and W1938—60 in. acid resisting sink with cabinet, complete with chromium fittings.

F144LD0—W't each 1100 lbs. each **\$261.75★**


THE 42 IN. SINKS AND CABINETS SHOWN ON PAGE 800 MAY ALSO BE USED IN ABOVE UNITS
Prices and Complete Layout to Meet Your Specifications Furnished At Your Request without Obligation

★Items Marked Thus ★ Are Shipped From Factory Only

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard MODERN PLANNED KITCHENS

COMPLETE UNITS TO FIT ANY KITCHEN



FOR "L" SHAPED INSTALLATIONS

These kitchens represent a grouping of standard size steel kitchen units arranged to provide storage and working space in such a manner that the work to be done in the kitchen may proceed, from beginning to completion in orderly, step and time saving sequence as possible.

Designed and made with a thorough knowledge of sink specifications, roughing-in dimensions and details of confirmation. Consequently they fit into those details smoothly and without necessity for making difficult and, as might otherwise happen, unsatisfactory installations. This did not just happen. It was deliberately planned in the knowledge that the sink is the most used of the three "working centers" making up the planned kitchen.

11 x 4 FT. UNIT FOR KITCHEN WITH WINDOW

AS SHOWN IN ABOVE ILLUSTRATION

Consists of three F2430—24x30 in. wall cabinets, one corner wall cabinet, three F241—24 in. table base cabinets, one corner base cabinet, two moulding strips for water tight connections and W1938—60 in. sink and cabinet, complete with chromium fittings.

F132LD0—W't each 1120 lbs. each **\$279.00**

11 x 4 FT. UNIT FOR KITCHEN WITHOUT WINDOW

Consists of three F2430—24x30 in., two F1830—18x30 in. and one F2418—24x18 in. wall cabinets, one corner wall cabinet, three F241—24 in. table base cabinets, one corner base cabinet, two moulding strips for Water tight connections and W1938—60 in. sink and cabinet, complete with chromium fittings.

F133LD0—W't each 1260 lbs. each **\$307.00**


THE 42 IN. SINKS AND CABINETS SHOWN ON PAGE 800 MAY ALSO BE USED IN ABOVE UNITS
Prices and Complete Layout to Meet Your Specifications Furnished At Your Request without Obligation

★Items Marked Thus ★ Are Shipped from Factory Only

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard STEEL WALL AND FLOOR CABINETS

Steel cabinet assembly units are available in a complete range of sizes, and can be grouped into hundreds of different combinations to fit size space in a way that will be most efficient and pleasing for the housewife. All doors and drawers close against rubber bumpers and are themselves sound insulated. Coat of the highest quality enamel available. This enamel is baked on under high temperatures and an exceptionally and durable pure white finish results. All hardware, such as drawer and door pulls, handsomely chrome plated.



WALL CABINETS

Height, in...	18	18	18	18	30	30	30	30
Width, in...	18	21	24	30	18	21	24	30
Depth, in...	13	13	13	13	13	13	13	13
Weight, lbs.	0	0	0	0	2	2	2	2
Each, lbs.	30	35	40	45	50	55	60	65
	F1818LDO	F2118LDO	F2418LDO	F3018LDO	F1830LDO	F2130LDO	F2430LDO	F3030LDO
	\$7.95★	9.60★	10.50★	11.65★	10.75★	12.95★	13.75★	15.50★



BROOM CABINETS

Two stationary shelves in upper compartment for storage of cleaning materials, etc., lower section accommodates vacuum cleaner, broom, etc., and has hooks for hanging. Width 18 in., height 84 in.

Depth, in.	13	24½
Weight each, lbs.	130	150
No.	F801LDO	F802LDO
Each	\$25.85★	28.25★

TABLE BASE FLOOR CABINETS

Black linoleum top with chrome border. 4 in. base with recessed toe space. Depth 24½ in., height 30½ in.

Width, in...	18	21	24	30	18	21	24	30
Depth, in...	1	1	1	1	3	3	3	3
Weight, lbs.	1	1	1	1	0	0	0	0
Each, lbs.	85	90	100	110	95	100	115	125
	F181LDO	F211LDO	F241LDO	F301LDO	F183LDO	F213LDO	F243LDO	F303LDO
	\$25.20★	27.75★	28.90★	33.05★	29.60★	30.90★	32.20★	38.50★

THREE MODERN SINKS FOR Hibbard KITCHEN ENSEMBLES

Square Corners for Watertight Connections



No. W1938, 60 In., Page 800

No. W1950, 60 In., Page 800B

No. W1936, 42 In., Page 800

★Items Marked Thus ★ Are Shipped from Factory Only

Prices Net F.O.B. Chicago, Add Freight to _____

THREE MODERN CABINET SINKS

ESPECIALLY DESIGNED FOR USE IN KITCHEN ENSEMBLES



ACID RESISTING ENAMELED IRON

Not effected by acids, fruit juices, etc.
Low back matches modern trend design, allows deeper windows.

3 in. ledge full length of sink gives reserve space for glasses, cleaner, soap, etc.

Straight ends make it easy to install continuous cabinets. Make water tight joints by using union strips with adjoining cabinet.

Heavy chromium plated swing sprayer faucet with dish spray.

Spacious white enameled cabinet with recessed toe space, chromium pulls.

DOUBLE DRAINBOARD

60 in. long, 25 in. wide, height to top of back 42 in., sink bowl 8 in. deep. Cabinet has two drawers, 3 large compartments. Complete with 4 in. chrome duo strainer 1 1/2 in. trap to wall, w't 500 lbs.

W1938VLD0each \$105.50



DOUBLE COMPARTMENTS

ACID RESISTING ENAMELED IRON

42 in. long, 25 in. wide, height to top of back 42 in. Both compartments 8 in. deep. For washing and rinsing. Cabinet has 2 large compartments. Complete with two 4 in. duo strainers, 1 1/2 in. chrome waste connection and trap to wall, w't 375 lbs.

W1935VLD0each \$71.95

With Fittings to Floor.....



SINGLE DRAINBOARD

ACID RESISTING ENAMELED IRON


42 in. long, 25 in. wide, height to top of back 42 in. Sink bowl 8 in. deep. Cabinet has 2 drawers and 2 large storage compartments. Complete with 4 in. chrome duo strainer and 1 1/2 in. trap to wall, w't 350 lbs.

W1936VLD0—Right hand drainboard.....each \$73.50

W1937VLD0—Left hand drainboard.....each 73.50

add \$1.50

Hibbard DOUBLE DUTY CABINET SINK



Work top 36 in. from floor . . . Overall height 37½ in.
 . . . Dimensions of top 24x48 in. Depth of right bowl—
 7 in., left bowl—11 in. . . . each 20 in. wide, 17 in. front
 to back.

SOLID BRASS CHROMIUM PLATED FIXTURES. SWING
 SPOUT FAUCET WITH DIVERTER TYPE SPRAY ATTACH-
 MENT. SPRAY HOSE SLIPS BACK INTO CABINET WHEN
 NOT IN USE.

SINK COMPARTMENT FITTED WITH 4 INCH DUO
 STRAINER. TRAY COMPARTMENT HAS A 2 INCH FLAT
 TOP STRAINER. 1½ INCH TRAP TO WALL.


Entirely New . . . utility combined
 with rugged beauty . . . Double purpose non-
 mechanical dishwashing unit . . . Can be used
 as a conventional kitchen unit or a light
 laundry unit as well . . . Saves trips to the
 basement for washing out small things . . .
 Saves time, space and effort. Accessible, use-
 ful and beautiful . . . Acid-resisting white
 porcelain enameled steel sink . . . Baked
 enameled finished cabinet . . . Ideal for all
 homes and apartments.

REMOVABLE DRAIN BOARD CAN BE USED ON
 EITHER COMPARTMENT. HEAVY CADMIUM
 PLATED RACK FOR DISHES AND SILVERWARE.
 1½ IN. RAISED LEDGE AT BACK. CHROMIUM
 PLATED CABINET PULLS. CABINET FITTED WITH
 TWO ADJUSTABLE SHELVES. W'T EACH 220 LBS.

W700VLDO each **\$63.45**

With Fittings to Floor add \$1.50

Hibbard "Duo" CABINET SINKS



DUO-SINK—TWO COMPARTMENTS

① WASHING ② RINSING


COMBINES THE UTMOST IN CONVENIENCE AND ATTRACTIVENESS. CONSISTS OF ACID RESISTING ENAMELED IRON SINK, TWO COMPARTMENT, DOUBLE DRAINBOARD WITH 4 IN. LOW BACK AND SHELF LEDGE. SPECIAL DE LUXE STEEL CABINET WITH HIGH QUALITY WHITE FINISH AND CONTINUOUS BLACK BASE. FOUR DRAWERS, TWO COMPARTMENTS, CHROMIUM PLATED PULLS.

Chromium plated special combination faucet with swing spout—transfer valve and chromium plated spray with disappearing hose. Two 4 in. chromium plated duo strainers, chromium plated waste and 1½ in. "P" trap to wall. Length 60 in., width 25 in., height to rim of sink 36 in., depth of basins 8 in., w't each 525 lbs.

W1950VLD0each \$112.50
With Fittings to Flooradd \$1.50



NOTE THE CONVENIENCE OF THE TWO COMPARTMENTS EACH 8 IN. DEEP




Chromium plated fixtures, handy spray unit between the two compartments. When not in use, spray unit rests flush in its socket with the hose concealed under the sink.

Hibbard Classic KITCHEN CABINET SINKS

THE MODERN KITCHEN UNIT

Acid Resisting Steel Sink



Sink Fitted with
Large Duo-Strainer

CONVENIENT—QUIET—DURABLE—MODERN DESIGN

SINK—60 in. long, 22 in. wide, sound proofed and of one piece, drainboard and bowl formed integrally from 14 gauge steel. Finish is highest quality, white, acid-resisting porcelain enamel.

CABINET—Of heavy gauge steel, thoroughly sound deadened, finished in white baked enamel inside and out. Has four large drawers and three spacious compartments

for waste container and cleaning utensils. Shelf space for pots and pans. Black enameled adjustable steel base, chromium handles. Sink height adjustable from 33 to 36 in. to top of drainboard. W't each 285 lbs.

FITTINGS—Include chrome swingspout faucet, with soap dish and renewable seats, 4 in. chromium Duo-Strainer and trap to wall.


W660VLD0

each **\$71.75**

With Fittings to Flooradd **\$1.50**

Hibbard Classic KITCHEN CABINET SINKS

ENAMELED IRON DOUBLE DRAINBOARD SINK



Sink Fitted with Large Duo-Strainer

EVERY HOUSEWIFE WILL WANT ONE OF THESE NEW MODERN
COMBINATION SINK AND SPACE SAVERS CABINET
CONVENIENT — QUIET — DURABLE — MODERN DESIGN

Enameled Iron Sink, finished in finest white porcelain enamel. Size: 60 in. long, 22 in. deep.

White Enameled Cabinet of heavy gauge steel, with large compartment for garbage receiver. Two 17½x12x3 in. drawers, two 19x20x11 in. compartments with shelves for storing pots, pans, etc. Black enameled adjustable

steel base. Height to top of drainboard 36 in. Chromium pulls, w't 440 lbs.

COMPLETE OUTFIT includes chromium-plated brass swingspout faucet, with soap dish and renewable seats, chromium 4-in. Duo-Strainer, and 1½ in. brass "P" trap.

V3500VLD0—With Regular Enameled Sink.....each \$69.95
V3510VLD0—With Acid Resisting Enameled Sink.....each 74.25

With Fittings to Floor.....add \$1.50

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard

"DELUXE" KITCHEN CABINET SINKS

THE MODERN KITCHEN UNIT

Enameled Iron Sink and Heavy Steel Cabinet



No. 240D
New
Concealed
Valve
Faucet

No. 340D
New
Concealed
Valve Faucet
with Handy
Sprayer

Length of Sink 60x22 In.

Fitted with Large
Duo-Strainer

CONVENIENT — QUIET — DURABLE — MODERN DESIGN

SINK is 22 in. wide, one piece, drainboards and bowl formed integrally. Finish is highest quality, white, acid-resisting porcelain enamel.

CABINET of heavy gauge steel, thoroughly sound deadened, finished in white baked enamel inside and out. Ornamental chrome lines on door of large compartment. Has four large drawers and three spacious compartments for waste container and cleaning utensils. Shelf space for

pots and pans. Black enameled adjustable steel base. Heavy brass chrome plated handles. Sink height adjustable from 33 to 36 in. to top of drainboard. W't each 440 lbs.


COMPLETE including newest design concealed valve faucet heavily chrome plated with swing spout, large soap dish and hexagon escutcheons, 4 in. chromium Duo-Strainer and trap to wall.

W4500VLD0—With No. 2440 D Faucet.....	each	\$79.75
W4505VLD0—With No. 340D Faucet and Sprayer.....	each	82.50
With Fittings to Floor.....	add	\$1.50

Hibbard "DE LUXE" KITCHEN CABINET SINKS

Enameled Iron Acid-Resisting 60x25 In. Shelf Type Sink

LATEST DESIGN DE LUXE STEEL CABINET



New
Concealed
Valve
Faucet

Fitted with Large
Duo-Strainer



THE IDEAL SINK FOR USE WITH WALL AND FLOOR CABINETS

25 in. wide, one piece sink, drainboards and bowl formed integrally, wide shelf at back of each drainboard, square ends make this unit especially suited for use with work table at either end. Finish is highest quality, white, acid-resisting porcelain enamel.

Heavy gauge steel cabinet, thoroughly sound deadened, finished in white baked enamel inside and out. Ornamental chrome lines on door of large compartment. Has four large drawers and three spacious compartments

for waste container and cleaning utensils. Shelf space for pots and pans. Black enameled steel base. Heavy brass chrome plated handles. Sink height 35 in. from floor to top of drainboard. W't each 490 lbs.

Complete including newest design concealed valve faucet, heavily chrome plated with swing spout, large soap dish and hexagon escutcheons, 4 in. chromium Duo-Strainer and trap to wall.

W4510VLD0each \$83.75


With Fittings to Floor.....add \$1.50

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard "CLASSIC" KITCHEN CABINET SINKS

THE MODERN KITCHEN UNIT

Acid Resisting Steel Sink



Fitted with Large Duo-Strainer

CONVENIENT — QUIET — DURABLE — MODERN DESIGN

SINK—22 in. wide, sound proofed and of one piece, drainboard and bowl formed integrally from 14 gauge steel. Finish is highest quality, white, acid-resisting porcelain enamel.

CABINET—Made of heavy gauge steel thoroughly sound deadened. Finished in white acid-resisting baked enamel inside and out. Has three drawers and spacious

compartment for waste container and cleaning utensils. Black enameled adjustable steel base. Chromium handles. Sink height adjustable from 33 in. to top of drainboard.

FITTINGS—Include chrome swing spout faucet with soapdish and renewable seats. 4-in. chromium Duo-Strainer and trap to wall.

42 In., W't Complete 215 Lbs.

W642VLD0—Right hand drain board.....each \$53.25
W643VLD0—Left hand drain board.....each 53.25

With Fittings to Floor.....add \$1.50


52 In., W't Complete 245 Lbs.

W652VLD0—Right hand drain board.....each \$62.35
W653VLD0—Left hand drain board.....each 62.35

Prices Net F.O.B. Chicago, Add Freight to _____

Hibbard "CLASSIC" KITCHEN CABINET SINKS

ENAMELED IRON SINK AND STEEL CABINET IN ONE UNIT



Fitted with Large Duo-Strainer

EVERY HOUSE WIFE WILL WANT ONE OF THESE NEW MODERN COMBINATION SINK AND SPACE SAVERS CABINET

DOUBLE THICKNESS DOOR

IDEAL FOR STORING GARBAGE RECEIVERS, KITCHEN UTENSILS, SILVERWARE, ETC.

Enameled iron sink, finished in finest white porcelain enamel. Height adjustable from 33 to 36 in. to top of drain board, width 20 in.

Cabinet made of steel, white enameled, with large compartment for garbage receiver. Two drawers, and

compartment for storing pots, pans, etc. Black enameled adjustable steel base. Chromium handles.

Furnished complete with chromium swing spout faucet with soap dish, chromium strainer and 1½ in. trap to wall.

42x20-in. Sink, W't Complete 275 Lbs.

Regular Enameled Sink with 4-in. Chromium Flat Top Strainer
W4560ALD0—Right Hand Drain Board.....each \$46.75
W4660ALD0—Left Hand Drain Board.....each 46.75

Acid Resisting Enameled Sink with 4-in. Chromium Duo Strainer
W5560½VLD0—Right Hand Drain Board.....each \$48.50
W5660½VLD0—Left Hand Drain Board.....each 48.50

52x20-in. Sink, W't Complete 375 Lbs.


Regular Enameled Sink with 4-in. Chromium Flat Top Strainer
W1550ALD0—Right Hand Drain Board.....each \$54.95
W1650ALD0—Left Hand Drain Board.....each 54.95

Acid Resisting Enameled Sink with 4-in. Chromium Duo Strainer
W3550½VLD0—Right Hand Drain Board.....each \$56.75
W3650½VLD0—Left Hand Drain Board.....each 56.75

With Fittings to Floor.....add \$1.50

Hibbard

"CLASSIC" KITCHEN CABINET SINKS



AN OUTSTANDING VALUE

LARGE CABINET FOR STORING GARBAGE RECEIVERS, KITCHEN UTENSILS, SILVERWARE, ETC.

Enameled iron sink, finished in white porcelain enamel: Size: 42 in. long, 20 in. deep. Height adjustable from 36 to 39 in., to top of drain board.

White enameled steel cabinet, with large compartment for garbage receiver. Also large compartment for storing

pots, pans, etc. Black enameled adjustable steel base. Bakelite pulls, w't 260 lbs.

Complete including chromium-plated brass swing spout faucet with soap dish, 4 in. chromium strainer and 1 1/2 in. trap to wall.



W1560ALDO—Right Hand Drain Board.....	each	\$33.25
W1660ALDO—Left Hand Drain Board.....	each	33.25
With Fittings to Floor.....	add	\$1.50

Hibbard

APRON KITCHEN SINKS

Enameled iron one piece apron kitchen sink with 8 in. integral back and drainboard, concealed hanger. Chromium compression combination sink faucet with swing spout and soap dish. 1½ in. chromium plated brass "P" trap with escutcheon.

All **Hibbard** sinks now furnished drilled for 4 in. strainers. All Nos. on this page when ordered with fixtures will be shipped with No. 391D0 strainer as illustrated.



Size of sink 42×20 in. overall, approx. shipping w't 210 lbs.

Size of sink 52×20 in. overall, approx. shipping w't 275 lbs.

ALL WHITE

With Chromium Fixtures

W0175ALD0—Right hand drain board.....each **\$24.95**

W0185ALD0—Left hand drain board.....each **24.95**

With Fittings to Floor.....add **\$1.50**

Without Fixtures

W0175LD0—Right hand drain board.....each **\$18.75**

W0185LD0—Left hand drain boardeach **18.75**

With Chromium Fixtures


W0195ALD0—Right hand drain board.....each **\$37.25**

W0205ALD0—Left hand drain board.....each **37.25**

Without Fixtures

W0195LD0—Right hand drain board.....each **\$30.75**

W0205LD0—Left hand drain board.....each **30.75**



Enameled iron one piece apron kitchen sink with 8 in. integral back and double drainboard, concealed hanger. Chromium compression combination sink faucet with swing spout and metal soap dish. 1½ in. chromium plated brass "P" trap with escutcheon.

Size of sink 60×22 in. overall, approx. shipping w't 350 lbs.

With Chromium Fixtures

W0280ALD0each **\$44.35**

With Fittings to Floor.....add **\$1.50**

Without Fixtures

W0280LD0each **\$37.50**


ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Prices Net F.O.B. Chicago, Add Freight to _____


Hibbard

APRON KITCHEN SINKS

Enameled iron one piece apron kitchen sink with 8 in. integral back and drainboard, concealed hanger. 4 in. chromium plated brass Duo strainer, with tail piece. Chromium compression combination sink faucet with swing spout and soap dish. 1½ in. chromium plated brass "P" trap with escutcheon.



All **Hibbard** sinks now furnished drilled for 4 in. strainers. All Nos. on this page when ordered with fixtures will be shipped with No. 491D strainer as illustrated.




Size of sink 42×20 in. overall, approx. shipping w't 210 lbs.

Size of sink 52×20 in. overall, approx. shipping w't 275 lbs.

ALL WHITE

With Chromium Fixtures	
White	
W0175VLD0—Right hand drain board.....each	\$26.25
W0185VLD0—Left hand drain board.....each	26.25
Acid Resisting White	
W0176VLD0—Right hand drain board.....each	\$27.75
W0186VLD0—Left hand drain board.....each	27.75
With Fittings to Floor.....add \$1.50	
Without Fixtures	
White	
W0175LD0—Right hand drain board.....each	\$18.60
W0185LD0—Left hand drain board.....each	18.60
Acid Resisting White	
W0176LD0—Right hand drain board.....each	\$20.25
W0186LD0—Left hand drain board.....each	20.25

With Chromium Fixtures	
White	
W0195VLD0—Right hand drain board.....each	\$38.35
W0205VLD0—Left hand drain board.....each	38.35
Acid Resisting White	
W0196VLD0—Right hand drain board.....each	\$40.75
W0206VLD0—Left hand drain board.....each	40.75
Without Fixtures	
White	
W0195LD0—Right hand drain board.....each	\$30.60
W0205LD0—Left hand drain board.....each	30.60
Acid Resisting White	
W0196LD0—Right hand drain board.....each	\$32.95
W0206LD0—Left hand drain board.....each	32.95





Enameled iron one piece apron kitchen sink with 8 in. integral back and double drain board, concealed hanger. 4 in. chromium plated brass Duo strainer with tailpiece. Chromium compression combination sink faucet with swing spout and metal soap dish. 1½ in. chromium plated brass "P" trap with escutcheon.

Size of sink 60×22 in. overall, approx. shipping w't 350 lbs.

With Chromium Fixtures		Without Fixtures	
W0280VLD0—White	each \$45.60	W0280LD0—White	each \$37.50
W0281VLD0—Acid resisting white.....	each \$48.75	W0281LD0—Acid resisting white.....	each \$40.50
With Fittings to Floor.....add \$1.50			

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Hibbard ROLL RIM KITCHEN SINKS



All **Hibbard** sinks now furnished drilled for 4 in. strainers. All Nos. on this page when ordered with fixtures will be shipped with No. 391D0 strainer as illustrated.

Enameled iron roll rim one piece kitchen sink with 8 in. integral back and right hand drain board, concealed hangers. Chromium compression sink faucet, with swing spout and soap dish. 1 1/2 in. cast brass "P" trap with escutcheon.

ALL WHITE

Size of sink 42x20 in. overall, approx. shipping w't 175 lbs.

With Chromium Fixtures

W0156ALD0—Right hand drain board.....each **\$22.00**
W0166ALD0—Left hand drain board.....each **22.00**

With Fittings to Floor.....add **\$1.50**

Without Fixtures

W0156LD0—Right hand drain board.....each **\$15.65**
W0166LD0—Left hand drain board.....each **15.65**


Size of sink 52x20 in. overall, approx. shipping w't 200 lbs.

With Chromium Fixtures

W0155ALD0—Right hand drain board.....each **\$28.45**
W0165ALD0—Left hand drain board.....each **28.45**

Without Fixtures

W0155LD0—Right hand drain board.....each **\$21.95**
W0165LD0—Left hand drain board.....each **21.95**



Enameled iron roll rim one piece kitchen sink with 8 in. integral back and double drainboard, concealed hanger. Chromium compression combination sink faucet with swing spout and soap dish. 1 1/2 in. brass "P" trap with escutcheon.

Size of sink 60x22 in. overall, approx. shipping w't 250 lbs.

With Chromium Fixtures


W0150ALD0each **\$35.95**

With Fittings to Floor.....add **\$1.50**

Without Fixtures

W0150LD0each **\$30.65**

Hibbard ROLL RIM KITCHEN SINKS



Size of sink 42x20 in. overall, approx. shipping w't 175 lbs.

With Chromium Fixtures White

W0156VLD0—Right hand drain board.....each **\$23.25**
W0166VLD0—Left hand drain board.....each **23.25**

Acid Resisting White

W0156½VLD0—Right hand drain board.....each **\$24.65**
W0166½VLD0—Left hand drain board.....each **24.65**


With Fittings to Floor.....add **\$1.50**

Without Fixtures White

W0156LD0—Right hand drain board.....each **\$15.65**
W0166LD0—Left hand drain board.....each **15.65**

Acid Resisting White

W0156½LD0—Right hand drain board.....each **\$17.25**
W0166½LD0—Left hand drain board.....each **17.25**



With Chromium Fixtures


W0150VLD0—Whiteeach **\$37.25**
W0151VLD0—Acid resisting white.....each **39.65**

With Fittings to Floor.....add **\$1.50**

ACID RESISTING IN COLORS ADD 25 % TO PRICE OF ACID WHITE—USING SAME NUMBERS AND SPECIFY COLOR

Enameled iron roll rim one piece kitchen sink with 8 in. integral back and right hand drain board, concealed hangers, chromium plated 4 in. Duo Strainer and tailpiece. Chromium compression sink faucet with swing spout and soap dish 1½ in. cast brass "P" trap with escutcheon.

All **Hibbard** sinks now furnished drilled for 4 in. strainers. All Nos. on this page when ordered with fixtures will be shipped with No. 491D Duo strainer as illustrated.



Size of sink 52x20 in. overall, approx. shipping w't 200 lbs.

With Chromium Fixtures White

W0155VLD0—Right hand drain board.....each **\$29.60**
W0165VLD0—Left hand drain board.....each **29.60**

Acid Resisting White

W0155½VLD0—Right hand drain board.....each **\$31.50**
W0165½VLD0—Left hand drain board.....each **31.50**

Without Fixtures White

W0155LD0—Right hand drain board.....each **\$21.95**
W0165LD0—Left hand drain board.....each **21.95**


Acid Resisting White

W0155½LD0—Right hand drain board.....each **\$23.75**
W0165½LD0—Left hand drain board.....each **23.75**

Enameled iron roll rim one piece kitchen sink with 8 in. integral back and double drainboard, concealed hanger, chromium plated 4 in. Duo strainer, and tailpiece. Chromium compression combination sink faucet with swing spout and soap dish. 1½ in. brass "P" trap with escutcheon.

Size of sink 60x22 in. overall, approx. shipping w't 250 lbs.

All **Hibbard** sinks now furnished drilled for 4 in. strainers. All Nos. on this page when ordered with fixtures will be shipped with No. 491D Duo strainer as illustrated.



Without Fixtures


W0150LD0—Whiteeach **\$30.75**
W0151LD0—Acid resisting white.....each **32.95**

Hibbard ACID RESISTING STEEL KITCHEN SINKS

Easier to Install because they are lighter and much easier to handle—can be installed by one man.

Construction—Made of one-piece 14 gauge steel, finished in acid-resisting white porcelain enamel fused right into the steel in electric furnaces. Weigh only about one-third as much as cast iron but are much stronger. Tests have shown that steel sinks withstand twice as much abuse as cast iron sinks.

Acid Resisting—Cut a lemon in halves—rub one half firmly on sink. Place the other half on any cast iron sink—leave them both for 20 minutes. Wash off the steel sink and see the effect on the cast iron sink.




Double drain board, height of back 8 in., depth of sink 6 in., overall size 60×22 in. Concealed hanger, chromium plated brass 4 in. duo waste strainer, coupling and tailpiece. Chromium compression combination sink faucet with swing spout and soap dish. 1½ in. brass "P" trap with escutcheon. Shipping w't 106 lbs.

W660VLD0—With Fixtures.....each **\$36.95**

With Fittings to Floor.....add **\$1.50**

W660LD0—Without Fixtures.....each **\$29.75**



Size of sink 42×20 in. overall, w't 85 lbs.

With Fixtures

W24VLD0—Right hand drain board.....each **\$26.10**

W25VLD0—Left hand drain board.....each **26.10**

With Fittings to Floor.....add **\$1.50**

Without Fixtures

W24LD0—Right hand drain board.....each **\$19.15**

W25LD0—Left hand drain board.....each **19.15**

All **Hibbard** sinks now furnished drilled for 4 in. strainers. All Nos. on this page when ordered with fixtures will be shipped with No. 491D strainer as illustrated.



8 in. integral back, concealed hanger, 4 in. chromium plated brass Duo strainer, coupling and tail piece. Chromium compression combination sink faucet with swing spout and soap dish. 1½ in. brass "P" trap with escutcheon.

Size of sink 52×20 in. overall, w't 95 lbs.

With Fixtures

W22VLD0—Right hand drain board.....each **\$32.35**

W23VLD0—Left hand drain board.....each **32.35**

Without Fixtures


W22LD0—Right hand drain board.....each **\$25.35**

W23LD0—Left hand drain board.....each **25.35**

Hibbard

CORNER APRON KITCHEN SINKS

Enameled Iron One-Piece Apron Kitchen Sink with 8 in. integral back and drainboard, concealed hanger 4 in. chromium plated brass Duo strainer, with tail piece. Chromium compression combination sink faucet with swing spout and soap dish. 1½ in. chromium plated brass "P" trap with escutcheon.



Size of sink 42×20 in., overall w't 210 lbs.

With Fixtures

W144VLD0—Whiteeach **\$30.30**
W145VLD0—Acid Resisting White.....each **36.85**

Without Fixtures

W144LD0—Whiteeach **\$23.25**
W145LD0—Acid Resisting Whiteeach **29.75**

Size of sink 52×20 in., overall w't 240 lbs.

With Fixtures


W135VLD0—Whiteeach **\$38.10**
W136VLD0—Acid Resisting Whiteeach **42.90**

Without Fixtures

W135LD0—Whiteeach **\$31.10**
W136LD0—Acid Resisting Whiteeach **35.75**

For Fittings to Floor.....Add **\$1.50**

All **Hibbard** Sinks now furnished drilled for 4 in. strainers as illustrated.



Size of sink 42×20 in. overall, w't 210 lbs.

With Fixtures

W140VLD0—Whiteeach **\$30.30**
W141VLD0—Acid Resisting Whiteeach **36.85**

Without Fixtures

W140LD0—Whiteeach **\$23.25**
W141LD0—Acid Resisting Whiteeach **29.75**

Size of sink 52×20 in. overall, w't 240 lbs.


With Fixtures

W125VLD0—Whiteeach **\$38.10**
W126VLD0—Acid Resisting Whiteeach **42.90**


Without Fixtures

W125LD0—Whiteeach **\$31.10**
W126LD0—Acid Resisting Whiteeach **35.75**

For Fittings to Floor.....Add **\$1.50**



Roll Rim Kitchen Sinks



Enameled Iron Roll Rim One-piece Kitchen Sink with 8 in. integral back and concealed hanger.

Size, in. 18×24 18×30 20×30
Approx. shipping w't, lbs..... 85 110 120

With Chromium Fixtures as Shown


W171BLD0each **\$12.45** **16.85** **17.25**

If Wanted with Fittings of Floor Instead of Wall.....Add **\$1.50**

Without Fixtures

W171LD0each **\$8.00** **12.50** **12.95**

Flat Rim Kitchen Sinks



Enameled Iron Flat Rim One-piece Kitchen Sink with 8 in. integral back and concealed hanger.

Size, in. 18×30 20×30
Approx. shipping w't, lbs..... 105 115

With Chromium Fixtures as Shown

W170VLD0each **\$20.25** **20.85**

Without Fixtures

W170LD0each **\$13.10** **13.75**



Hibbard

Kitchen Sinks

**BUILD YOUR OWN
CABINET SINK**

FLAT RIM MAKES A TIGHT, WATER-PROOF JOINT WITH EITHER WOOD OR STEEL CABINETS. CAN BE USED WITH LINOLEUM OR PORCELAIN TOP




Double Compartment

Acid-Resisting Enameled Iron.

With two outlets for Nos. 391D0 and 491D0 4-inch strainers.

Size, in.	32x20	42x22
W't each, lbs.	100	150
W2325LD0	each \$21.65	30.25




**LARGE DUO
STRAINER
WITH CRUMB
CUP AND
STOPPER
ELIMINATES
DISH PAN**



Acid-Resisting Enameled Iron

With center drilling for Nos. 391D0 and 491D0 4-inch strainers.

Size, in.	18x30	20x24	20x30
W't each, lbs.	55	50	60
W174LD0	each \$8.00	8.50	9.00




Acid-Resisting Enameled Steel

With center drilling for Nos. 391D0 and 491D0 4-inch strainers.

Size overall, in.	16x24	18x30	20x30
Shipping w't each, lbs.....	12	17	18
Pkg. of 3 *	W6LD0	W8LD0	W9LD0
Each	\$5.00	5.95	6.50

**STRAINERS
NOT
INCLUDED
IN PRICE OF
SINKS.
SEE PAGE 836B
FOR
STRAINERS
AND PAGE 832
FOR
FAUCETS**



Enameled Iron

With end drilling for Nos. 391D0 and 491D0 4-inch strainers.

Size, in.	16x24	18x30	20x30	20x36
Approx. ship. w't, lbs.....	40	55	60	80
W173LD9 —Open Stock.ea.	\$5.00	5.75	6.75	12.95
W173LD0 —Pkg. 3 * .				



HIBBARD'S ~~ONE~~ Buffet Four-Burner Gas Ranges

A Smartly Designed, Streamlined Gas Range—
a New Creation!

Compact, neat, modern, embodying every practical convenience . . . heavily insulated ovens . . . automatic top lighters. Double duty oven burner . . . oven heat regulator . . . porcelain enameled throughout . . . rustproof ovens.

- Robertshaw Clock Dial Oven Heat Regulator
- Recessed Instrument Panel
- Heavily Insulated Oven
- Slide-out Broiler with Roller Bearings
- Smokeless Broiler Grill
- Convertible Top and Splasher
- Harper High-Speed Round Burners
- Automatic Top Lighter
- Semi-Solid Grid Top
- Chanel Iron One Piece Dovetail Frame
- Double Duty Burner for Oven and Broiler
- One Large Utensil Compartment
- One Large Roller Bearing Utensil Drawer for Kitchen Cutlery
- All Porcelain Enamel
- Porcelain Enamel Lined Ovens

True Value "De Luxe" Washers



Turns out lovely, fresh, spotless clothes with wear or tear. Your clothes will last longer. Largest size tub, largest agitator and most massive safety wringer enables you to turn out the largest washings in shortest time.

The finest and fastest washer you can buy. You can pay more, but you cannot get finer washing quality. Has massive streamlined Chamberlain wringer, large bar type pressure release, 2½ in. balloon rubber rolls. Streamlined porcelain tub. Oversize, heavy cast aluminum agitator, 20% greater washing area. All steel kettle type chassis, built like a bridge. Column type legs reduce vibration. "Oiled-for-life" G. E. motor. Tub finished in "dawn grey" porcelain, all other surfaces, except wringer, matching color enamel. 110 A.C., 60 cycle.

Hibbard Refrigerator




You Get These Genuine Plus Conveniences and
Extra Service Features:

- 1—Handsome White Hylux Finished Exterior.
- 2—All White Porcelain Interior.
- 3—Triple Sealed Insulation.
- 4—Dependable Super-Powered.
- 5—All Copper Freezing Unit.
- 6—13 Point Cold Control Mechanism.
- 7—"Cool" Defrosting.
- 8—Automatic Interior Light.
- 9—Snap Seal Door Handle.
- 10—Round Wire Shelves.
- 11—Lower Operating Cost.
- 12—Faster Freezing.
- 13—Graceful Streamlined Design.

FOR COMPLETE LINE SEE PAGES 898J TO 898ZB


Drain Boards



Enameled Iron

Enameled Reversible Drain Board with painted iron bracket and rim clamp. Specify size.

Size, in.	18×24	20×18	20×24
Approx. shipping w't, lbs.	48	45	55
W5754D0	each \$8.35	8.00	8.65




Acid Resisting Steel

Fits any sink—easy to install. Edges rolled and center grooved to insure easy drain. Complete with brackets. Specify size.

Size, in.	18×24	20×18	20×24
Approx. shipping w't, lbs.	12	15	22
W5755D0	each \$5.50	5.25	6.00

Sink Backs



Enameled iron, 2 1/4 in. deep. 12 in. back with two faucet holes 8 in. centers. Length 30 in., approx. shipping w't 35 lbs.

W5748D0	each \$5.95
----------------------	--------------------

Enameled Sink Legs



No.	No.	No.
F2390D	F2393D	F2395D

F2390D0 —For use under rim of apron sinks.....	each \$2.75★
F2393D0 —For use under drainboard of sink.....	each 3.25★
F2395D0 —For use under sink part of sink.....	each 2.50★

★Items Marked Thus ★ Are Shipped From Factory Only

Roll Rim Slop Sinks



Specify Size Desired

Enameled Inside Cast Iron Roll Rim Slop Sink with 12 in. integral back. 2 in. enameled inside cast iron adjustable "P" trap standard for iron pipe for cleanout. Chromium plated cast brass waste strainer with compression sink faucets with lever handles.

Size, in.	18×22×12	20×24×12
Approx. ship. w't, lbs.	155	175
F6518D0	each \$33.65★	35.80★

Flat Rim Slop Sinks



Cast Iron Flat Rim Slop Sink with old style plain outlet. Chromium plated open strainer, cast iron collar for lead pipe with bolts. Enameled inside, exterior painted.

Size, in.	16×16×10	20×16×12	24×20×12
Approx. shipping w't, lbs.	50	65	90
F6524D0	each \$9.65★	12.80★	16.15★

SINK AND TRAY COMBINATIONS




Enameled Iron Sink and Tray Combination. Sink on left side, tray on right side. Chrome combination swing spout faucet with soap dish, strainer in sink and waste plug with stopper in tray.

Drain Board and Legs Not Included

Length over all, in.....	42	51
Width over all, in.....	22	23½
Sink inside, in.....	17½×17½	19½×21¼
Depth of Sink inside, in.....	8	8
Tray inside, in.....	17½×17½	19½×21¼
Depth of Tray inside, in.....	13¼	13¼
Back, in.	8	8

F2511AD0each **\$34.95★** **41.25★**




Enameled Iron Sink and Tray Combination. Sink on right side, tray on left side. Chromium combination swing spout faucet with soap dish, strainer in sink and waste plug with stopper in tray.

Drain Board and Legs Not Included

Length over all, in.....	42	51
Width over all, in.....	22	23½
Sink inside, in.....	17½×17½	19½×21¼
Depth of Sink inside, in.....	8	8
Tray inside, in.....	17½×17½	19½×21¼
Depth of Tray inside, in.....	13¼	13¼
Back, in.	8	8

F2516AD0each **\$34.95★** **41.25★**

ENAMELED WASH SINKS




Enameled Iron Roll Rim Wash Sink, with 8 in. back, center outlet, on concealed wall hanger and painted brackets with chromium plated faucets and strainers, soap dish and trap. Width 18 in., depth 8 in.

Lengths, ft.	3	4	5	6
Number of Faucets.....	2	2	3	3
Number of Soap Dishes.....	1	1	2	2
W't each, lbs.....	180	240	300	400

F1800BD0each **\$45.95★** **54.75★** **65.50★** **73.75★**

★Items Marked Thus ★ Are Shipped From Factory Only

LAUNDRY TRAYS



Enameled Iron, Two Compartment, One Piece Roll Rim Laundry Tray. 8 in. Integral Back, on Concealed Wall Hangers and Painted Adjustable Legs; Chromium Plated Soap Dishes and Chromium Plated Compression Bibbs, Chromium Plated Waste Plugs with Stopper. Painted Exterior. Size 53×26×14 in. W't each 300 lbs.

F2630D0each **\$67.25★**



Enameled Iron, Roll Rim Laundry Tray. 8 in. Integral Back on Concealed Wall Hanger and Painted Adjustable Leg; Chromium Plated Soap Dish and Chromium Plated Compression Bibbs, Chromium Plated Waste Plug with Stopper. Painted Exterior. Size 28×26×14 in. W't each 150 lbs.

F2640D0each **\$35.50★**



SEAT ACTION FREEZE-PROOF CLOSETS


MODERN-KELLY FREEZE-PROOF water closets are designed for installation in any unheated building, vault or porch, and are built "for keeps." If the closet is used, it is bound to flush, because when the seat is occupied the tank fills with water, and when the seat is released the closet flushes. Then all the water in the fixture drains out through the copper drain tube, which is placed below the frost line. Satisfactory operation through years to come is insured by the exclusive features shown in sectional view to right.

The valve plunger is positively removed by merely unscrewing the top nut, because the non-swelling packings will not stick down in the valve as they are made of laminated treated leather. The tall oval flushing rim hopper is cast in one piece—rim integral with hopper, and the inside of the rim is full porcelain enameled so that it cannot clog with soil, or rust out. The appearance of the fixture is greatly improved by our white enameled outside finish, and in the event of stoppage the hopper cannot overflow into the valve, contaminating the fresh water, as an "S" offset connects valve and hopper above rim. The easily replaced standard pipe size valve rod and casing, and the removable valve seat promise low repair costs years hence.

Seat-action compression tank FREEZE-PROOF water closet is equipped with tall oval cast iron flushing rim hopper, to caulk with flushing rim cast integral with hopper . . . white porcelain enameled inside, and inside of rim . . . painted outside with three coats best white enamel . . . heavy bronze seat-operated valve with "S" connection from valve to hopper, offset above top of hopper . . . copper drain tube . . . galvanized iron pressure tank 8×24 in. . . galvanized malleable iron combination seat ring and hinge . . . 1½ in. oak seat . . . removable bronze seat at supply . . . packing of non-swelling laminated treated leather, complete as shown and described. Roughts in at 19 in. from finished wall.


F103D0each **\$30.75★**

GALVANIZED STEEL SCULLERY SINKS



One compartment, with roll rim on front and ends and with 15-inch high integral back, with legs and soap dish. Chrome faucets, waste and overflow, and trap. Width 24 in., depth, 12 in.


No. F815D0				
Length, in.	42	48	54	60
W't each, lbs.	150	165	175	190
Each	\$60.85★	63.35★	65.95★	68.50★



One compartment, with roll rim on front and ends, and with 15-inch high integral back, 36 in. detachable right hand drainboard, with legs and soap dish. Chrome faucets, strainer and trap. Width 24 in., depth, 12 in.


No. F825D0				
Length, in.	36	42	48	60
W't each, lbs.	190	210	215	240
Each	\$60.65★	63.35★	65.85★	70.95★

Bar Sinks



Two compartment, with roll rim on front and ends and with 15-inch high integral back, with legs and soap dish. Chrome faucets, waste and overflows, and traps. Width 24 in., depth 12 in.

No. F820D0				
Length, in.	42	48	54	60
W't each, lbs.	160	175	185	200
Each	\$79.95★	84.30★	88.75★	92.95★



Double drainboard pattern, built integral with single compartment unit, flat top (not grooved), back and return ends, also apron in front; all metal clad. Width 24 in., depth 6 in., 8 in. back.

F169WD0—White Metal				
Size, in.	36	42	48	
W't each, lbs.	150	175	200	
Each	\$147.95★	158.95★	169.65★	


F169SD0—Stainless Steel				
Size, in.	36	42	48	
W't each, lbs.	150	175	200	
Each	\$147.95★	158.95★	169.65★	

F169MD0—Monel Metal				
Size, in.	36	42	48	
W't each, lbs.	150	175	200	
Each	\$147.95★	158.95★	169.65★	

Hibbard TOILET SEATS

GUARANTEED FOR FIVE YEARS

Double Doweled at Front and Back

**Mother-of-Pearl Sheet Celluloid Covered**

Guaranteed not to chip or discolor. 1 1/4 in. thick. W't each 8 lbs.

Choice of five beautiful colors: green, ivory, black, orchid, white. Heavy chrome plated hinges.

W411LD0 —Green	each	\$5.95
W412LD0 —Ivory	each	5.95
W413LD0 —Black	each	5.95
W410LD0 —Orchid	each	5.95
W401LD0 —White	each	5.95

**Ebony Hard Rubber****Will Last Indefinitely**


Open front, with integral hinge. W't each 7 1/4 lbs.

Without Cover

W450LD0 —For regular bowl	each	\$5.95
W460LD0 —For extended lip bowls.....	each	5.95


With Cover

W400LD0 —For regular bowl.....	each	\$9.75
W500LD0 —For extended lip bowl.....	each	9.75

**White Sheet Celluloid Covered**

Guaranteed not to chip or discolor. 1 1/4 in. thick. W't each 8 lbs. Heavy chrome plated hinges.

W245LD0 —Open Stock	each	\$4.50
W245LD2 —Lots of 3		

Dressing Table Bench

3/4 in. chromium plated tubing, height 17 in., padded seat 12 x 18 in., leatherette covered. W't each 15 lbs.

F315LD0 —Green	each	\$10.75
F316LD0 —Ivory	each	10.75
F317LD0 —Black	each	10.75
F318LD0 —Red	each	10.75
F319LD0 —White	each	10.75

Hibbard TOILET SEATS

GUARANTEED FOR FIVE YEARS

Double Doweled at Front and Back



Extra Heavy—1½ In. Stock, Colonial Hinge


Finest stock, 1½ in. thick, sprayed Pyralin finish protects seat from acids and germs. Heavy colonial chromium plated hinge. Fitted with four live rubber bumpers. W't each 9 lbs.

W243LD0—Open Stock,
each **\$3.25**

W243LD2—Lots of 3,

1½ in.
stock.

Weight
8 lbs.



No. W43D

W43LD0—Birch, white sprayed Pyralin finish, heavy chrome plated brass bar hingeeach **\$2.98**

In lots of 6

W239LD0—Birch, mahogany finish, seat and cover with heavy chrome plated bar hingeeach **\$2.75**

In lots of 6

W239½LD0—Oak, seat with cover, heavy chrome plated bar hinge,
eacheach **\$2.75**

In lots of 6




Without
Cover

No.
W103D

1½ in. stock. Birch, extended lip, open front, less cover, with chrome plated hinge. W't 5 lbs.

W123LD0—Whiteeach **\$3.25**
W103LD0—Mahoganyeach **3.00**
W113LD0—Golden Oak.....each **3.00**



No. W241D

1½ in. Stock. Birch, regular open front seat and cover with chrome hinge. Shipping w't 8 lbs.

W240LD0—Whiteeach **\$3.75**
W241LD0—Mahoganyeach **3.50**
W241½LD0—Golden Oak.....each **3.50**




No. W203D

Without Cover


1½ in. stock. Birch, regular open front, less cover, with chrome plated hinge. W't 5 lbs.

W223LD0—Whiteeach **\$3.25**
W203LD0—Mahoganyeach **3.00**
W213LD0—Golden Oak.....each **3.00**



A good quality seat. Well made. Wood doweled. 1½ in. thickness. White Enameled finish. Chromium plated bar hinge. W't each 8 lbs.


W143LD0—Open Stock.....each **\$2.75**
W143LD2—Lots of 6.



No. W142D

1½ in. stock. Birch, extended lip open front seat and cover with chrome hinge. Shipping w't 8 lbs.

W142LD0—Whiteeach **\$4.75**
W140LD0—Mahoganyeach **4.25**
W141LD0—Golden Oak.....each **4.25**



No. F303D

Self-Raising

Birch, 1½ in. stock, regular open front without cover. Equipped with highest quality, Chrome Spring Hinge, making them self raising. W't each 6 lbs.

F303LD0—White Enameled,
each**\$6.95★**
F313LD0—Mahogany Finish,
each **6.50★**
F323LD0—Oak Finish.....each **6.50★**

FREE!

**THIS ATTRACTIVE TOILET
SEAT DISPLAY RACK FREE
WITH EVERY DEAL**

Helps You Sell More Toilet Seats with Less Effort

**Rack Is Sturdily Made of Steel — Heavily Cadmium
Plated Throughout — Stands 4 Feet High and
Holds 4 Seats—Has Holders for Price Cards**

ASSORTED FINISHES

No. W892D0—Deal—Consists of:

**5—W43D—1 1/4 in. thick, white sprayed Pyralin finish,
Birch seat and cover with heavy chrome plated brass hinge.
Retails for \$2.85**

**2—W239D—1 1/4 in. thick, mahogany finish, birch seat and
cover with heavy chrome plated brass hinge.
Retails for \$2.79**

**1—W239 1/2 D—1 1/4 in. thick, oak seat with cover, heavy
chrome plated brass hinge.
Retails for \$2.79**


ALL WHITE FINISH


No. W992D0—Deal Consists of:

**3—W43D—1 1/4 in. thick, white sprayed Pyralin finish,
birch seat and cover with, heavy chrome plated brass hinge.
Retails for \$2.85**

**2—W245D—1 1/4 in. thick, white sheet celluloid covered
seat and cover, with heavy chrome plated brass hinge.
Retails for \$4.95**

**1—W401D—1 1/4 in. thick, white pearl finish celluloid cov-
ered seat and cover with heavy chrome plated brass hinge.
Retails for \$5.95**





“Wolverine” Chemical Toilets

For Use Where Running Water Is Not Available


Vault type chemical toilets work on the principle of the chemical liquification and disintegration of sewage. Each toilet has a steel tank, fitted with an agitator and a drain valve. In this tank is placed three or four inches of water, to which is added a proper charge of chemical, (depending on the size of the tank) which has been previously dissolved in water. All sewage drops straight into the tank and is agitated whenever toilet is used. This promotes the chemical liquification, which renders the sewage into a sterile liquid that is then drained when the tank is full into a cesspool built for that purpose. The sewage then seeps away into the soil. This forms the complete chemical process of sewage disposal, and is safe and sanitary, and where running water is not available, is the most sanitary method known.

All outfits come complete with tank, with 4 in. drain valve and agitating device.

Units below 100 gallon capacity have 16 feet of ventilation pipe, those over 100 gallon capacity have 20 feet of pipe, one-half galvanized and one-half gray enameled, complete roof, safe skirt pipe and ventilator, can of chemical, toilet paper holder and roll of paper.

The time shown below to serve four people means between drainings.

The china bowl is made of finest clays, thoroughly vitrified and is the highest grade china made. Steel bowls are made of copper bearing steel, galvanized and painted with grey enamel baked on at a high temperature.



Nos.	Cap., Gals.	Time Will Serve Four People	Type of Bowl	W't, Lbs.	Each
LC100D0	45	6 weeks	Steel	164	\$31.25★
LC125D0	45	6 weeks	China	202	41.75★
LC150D0	65	8 weeks	Steel	182	37.25★
LC175D0	65	8 weeks	China	220	48.00★
LC200D0	170	6 months	Steel	297	50.50★
RC200D0	170	6 months	China	323	68.00★
LC250D0	200	7 months	Steel	350	58.50★
RC250D0	200	7 months	China	375	76.25★

“Wolverine” Multiple Chemical Toilets

Made in sizes from 2 to 6 bowls on one tank for boys camps, etc. We figure a bowl for every 15 users, for schools one bowl for every 20 users. Ventilation pipe is built to fit building at prices quoted. All tanks 14 gauge copper alloy steel and fitted with valves and agitator for each bowl.

Nos.	Cap., Gals.	Bowls	Type of Bowls	W't, Lbs.	Each
LC300D0	285	2	Steel	490	\$101.00★
RC300D0	285	2	China	542	136.00★
LC400D0	385	3	Steel	665	151.20★
RC400D0	385	3	China	743	204.00★
LC500D0	485	4	Steel	840	201.60★
RC500D0	485	4	China	944	272.50★
LC600D0	585	5	Steel	1015	252.00★
RC600D0	585	5	China	1145	336.00★
LC700D0	685	6	Steel	1190	302.40★
RC700D0	685	6	China	1346	408.00★

★Items Marked Thus ★ Are Shipped from Factory Only


Prices Net F.O.B. Factory, Add Freight to _____

Chemical Toilets



Finished in green enamel. Sturdy construction. Green enamel seat with double action hinge, causing no inconvenience when the inner pail is removed. Equipment consists of: 6 joints of green enameled pipe, two elbows, one wall collar, 6 in. reducer, one package of chemical, one roll of toilet paper, one toilet paper holder and complete instructions. W't each 24 lbs.

W52D0each **\$5.95**
PACKED SINGLY



Economy

The outer casing and container pail are made from 26 ga. galvanized sheet steel.

The outer casing and container pail has a roll top edge, which is reinforced with a 1/2 in. steel rod. All bottoms are double seamed on. The seams in the pail are loaded and soaked full of solder. The bail is a heavy steel rod attached to the pail with steel ears.

The ventilation pipe is made from 30 ga. galvanized sheet steel.

Finish—The outer casing and ventilation pipe is finished in grey enamel.


Toilet Seat—It is a high grade solid oak seat, glass finish fitted with heavy cast brass bar hinges, and securely fastened to the outer casing.

The Economy Outfit consists of the outer casing with solid oak seat, container pail, eight gallon capacity, six lengths of 3x15 in. ventilation pipe, one elbow, one collar, one roll toilet paper and paper holder, and one qt. Shiel's pine tree oil chemical.

Guaranteed for one year against defects in material and workmanship. W't each 30 lbs.

W56D0each **\$10.95**
PACKED SINGLY

Chem-O Self-Draining Indoor Chemical Toilets



Attached to seat cover is rod of automatic agitator. Every time seat is moved up or down, paddle part of agitator works—agitator mixes chemical with sewage and renders sewage liquid.

Tank holds approximately 25 gallons, made of 16 gauge steel, coated inside and outside with a positive rust proof mineral process, then coated again with asphalt. This makes a tank that will withstand corrosion and last.

Tank contains a patent internal valve which is used, when tank is full, for emptying—you reach it from top of bowl and lift it by a wrench furnished for that purpose.



Chem-o with steel bowl, tank and bowl made in one piece, bowl enameled gray.

One tank with agitator and patented valve.

One valve wrench.

One bowl. One 3 in. elbow. One roof safe.

One seat and cover. One 3 in. iron elbow.

One wall collar. One roll of toilet paper.

Four joints (8 ft.) 4x12 in. white enameled vent pipe. One vent cap.

One 2 in. skirted vent pipe.

One 1/2 gallon Lavolet chemical.

One toilet paper holder.

Tank—14 in. diam. x 34 in. long, shipping w't 107 lbs.

W54D0each **\$26.25**
PACKED COMPLETE IN ONE PACKAGE

Chem-o with china bowl—this is vitreous china of good quality.

One tank with agitator and patented valve.

One valve wrench.

One vitreous china bowl. One 3 in. elbow. One roof safe.

One seat and cover. One 3 in. iron elbow.

One wall collar. One roll of toilet paper.

Four joints (8 ft.) 4x12 in. white enameled vent pipe. One vent cap.

One 2 in. skirted vent pipe.

One 1/2 gallon Lavolet chemical.

One toilet paper holder.

Tank—14 in. diam. x 35 in. long, shipping w't 170 lbs.

F58D0each **\$49.95**
PACKED COMPLETE IN THREE PACKAGE

Closet Chemicals




Hibbard—Pine Tar

Dark color, tar base, for use in any style indoor, sanitary closet. Guaranteed to give perfect results.

1 Gal. Cans

60D0—Open Stock.....can **\$1.20**

M60D4—Lots 6 cans *



Chemi-Clos Sweet Pine Odor


Very dark color, sweet pine odor, for use in any style indoor, sanitary closet, gives perfect results.

1 Gal. Cans

55D0can **\$1.**

★Items Marked Thus ★ Are Shipped from Factory Only

RUST-RESISTING STEEL SEPTIC TANKS



Sewage Disposal with Safety for Any Home

All Septic Tanks are equipped with built-in inlet and outlet connections or collars.

The Steel Septic Tank provides an economical and a safe method for sewage disposal in unsewered areas. Will take care of all house wastes, including those from kitchen. Most approved type of construction and design. Built for lasting and satisfactory service. Design recommended by best health and sanitation authorities. May be had in a capacity suitable for almost any need—from a single home to schools, etc. Each tank comes equipped with a tightly fitting flanged steel cover.

Made of No. 14 gauge Keystone "Copper Steel" throughout. This material is unequalled for service and rust-resistance. All seams are heavily welded, and all tanks are water-tight. Each tank is heavily coated inside and outside with best quality of asphalt. This gives complete protection against moisture, acids, etc. Easy to install. Complete installation instructions furnished with each tank.

Capacity, gals.	150	200	300	500	750
Accommodating number of persons, home....	4	6	10	20	30
Accommodating number of persons, school....	7	15	25	40	60
Accommodating number of persons, factory...	6	12	20	35	50
Diameter, in.	30½	38	47	52	58
Height, in.	48	48	48	60	66
Shipping w't lbs.	160	180	245	330	700
No.	W1D0	W2D0	W3D0	F4D0	F5D0
Each	\$18.75	20.75	24.75	43.25★	64.00★





Illustration Showing Proper Installation of Septic Tanks

Grease Traps




Increase the efficiency of the septic tank by keeping kitchen sink grease, which stops bacterial action, out of it. Made of 14-gauge copper bearing steel, tar coated. Heavy cover steel; baffle plate.

Size, in.	18×24	24×24
Capacity, gal.	25	45
Weight each, lbs.	50	92
No.	W010D0	F020D0
Each	\$8.00	19.25

Self Skim Grease Interceptors

A Sanitary Necessity—Insurance Against Clogged Lines



It separates the grease and fat, permitting only clean water to pass into the drain lines. Only a minute or two is required to clean this Interceptor from the smallest to the largest size. Merely the turn of a valve, the removal and dumping of the receptacle and its return to its chamber is all that is needed. Designed to harmonize with the finest type of sink equipment. Water flow cap. 60 gals. per hour, 20 lbs. fat capacity. Size 15½×9×9½ in., w't 50 lbs.

For Installing Immediately Under the Sink

White enamel finish, with 1½ in. I. P. threaded outlet. Finished with 1½ in. slip joint connection, and is equipped for adjustable wall bracket for support. If desired, a straight pipe and floor flange can be used instead of the bracket.

F100D0—Top Inlet.....	each	\$21.75★
F110D0—End Inlet.....	each	21.75★
F115D0—Wall bracket for above.....	each	2.00★

For Installing on the Floor Under Sink

White enameled finish, with 1½ in. threaded I. P. outlet. Furnished with 1½ in. slip joint connection and flat flanged base.

F120D0—Top Inlet.....	each	\$21.75★
F130D0—End Inlet.....	each	21.75★

★Items Marked Thus ★ Are Shipped from Factory Only

DRINKING FOUNTAINS


Eljer Automatic Stream Regulator

Non-Squirting—Completely Automatic



Millson Octagonal Vitreous China Wall Drinking Fountain with integral strainer, non-squirting center bubbling nozzle, C. P. self-closing valve with oscillating handle, stop and regulating valve and 1 1/2-in. galvanized concealed trap. W't 50 lbs.

F4551D0each \$39.25★



Millson Octagonal Vitreous China Wall Drinking Fountain with integral strainer, hooded slant stream with integral guard to prevent contamination of nozzle, C. P. automatic stream regulator and non-squirt device, C. P. self-closing valve with oscillating handle, stop and regulating valve and 1 1/2-in. galvanized concealed trap. W't 50 lbs.

F4556D0each \$35.00★



Bristol Vitreous China Hooded Slant Stream Drinking Fountain with C. P. self-closing valve, supply to wall with stop and regulating valve and 1 1/2-in. iron "P" trap. Size 8x14 in., w't 30 lbs.

F4951D0each \$18.25★



Duluth Vitreous China Drinking Fountain with 8-in. integral back, strainer and trap with 1 1/2-in. brass outlet connection and concealed hanger, non-squirting nozzle with self-closing valve, supply to wall with stop and regulating valve and ice water faucet. Size 13x12 in., w't 55 lbs.

F4700D0each \$36.00★



Alcove Vitreous China Recess Drinking Fountain with C. P. strainer and C. P. ice water faucet with regulating stop. Recess is 4 1/2 in. deep and basin projects 4 1/2 in. from wall. Size 14x18 in., w't 40 lbs.

F4805D0each \$24.75★



Glendale Vitreous China Recess Drinking Fountain, hooded slant stream with integral guard to prevent contamination of nozzle, C. P. automatic stream regulator and non-squirt device, C. P. self-closing valve, stop and regulating valve for 3/8-in. I. P. supply, C. P. outlet strainer with 1 1/2-in. cast brass trap and cleanout extension to face of wall, metal wall flange and cap, C. P. push button ice water faucet with regulating stop. Dimensions, 16 1/2 x 30 in., recess 9 in. deep, w't 75 lbs.

F4810D0each \$79.50★



Norman Vitreous China Semi-Recess Drinking Fountain with projecting basin, hooded slant stream with integral guard to prevent contamination of nozzle, C. P. automatic stream regulator and non-squirt device, C. P. self-closing valve, stop and regulating valve for 3/8-in. I. P. supply, C. P. outlet strainer with 1 1/2-in. cast brass trap and cleanout extension to face of wall, metal wall flange and cap, C. P. push button ice water faucet with regulating stop. Dimensions, 14x26 in., recess 4 in. deep, projection 6 in., w't 60 lbs.

F4825D0each \$58.75★

★Items Marked Thus ★ Are Shipped from Factory Only


DRINKING FOUNTAINS

MEET ALL SANITARY CODE SPECIFICATIONS



Chromium-plated cast brass bubbler with porcelain bowl, controlled by self-closing push button valve, loose key volume regulator, $\frac{1}{2}$ -in. I.P.S. thread.
Diam. of bowl, 4 in., w't 7 lbs.

F221D0each \$9.00




Chromium-plated cast brass bubbler with vitreous china bowl, controlled by Rasco patented ball-bearing self-closing valve with metal 4-ball handle and integral volume regulator. Supply and drain outlets, $\frac{3}{4}$ -in. female I.P.S. thread.
Diameter of bowl, 6 in., w't 10 lbs.

Particularly adapted for use on electric ice water coolers.

Bubbling head non-squirting and self-draining.

F214D0each \$14.00



Pedestal Fountain of heavy vitreous china, modernistic octagonal design with brass octagonal pattern center stream non-squirting drinking head above rim of bowl, preventing dangerous syphonage if drain from bowl becomes clogged, integral china strainer, controlled by Rasco patented ball-bearing self-closing valve with metal 4-ball handle and loose key regulating valve under head, $1\frac{1}{2}$ in. galvanized drain and $\frac{3}{4}$ in. supply to floor, concealed in pedestal. Fastened to floor with two brass headed

bolts.
Exposed metal chromium-plated. Diam. of bowl 11 in., diam. of base 15 in. Height 30 in., w't 100 lbs.

F12D0each \$63.00★




Wall Fountain with extra heavy vitreous china bowl, integral angle stream drinking head above rim of bowl, preventing dangerous syphonage if drain from bowl becomes clogged, brass bee-hive strainer; controlled by Rasco patented ball-bearing self-closing valve with metal 4-ball handle and $\frac{3}{4}$ in. loose key volume regulator; $1\frac{1}{2}$ in. cast iron deep seal-P-trap with cleanout and integral wall flange.

Iron parts are aluminum painted.

Exposed brass, rough nickel-plated.

Diameter of bowl 12 in. Projection from wall $15\frac{1}{2}$ in. W't 35 lbs.

F184D0each \$30.00★




Pedestal Fountain enameled base, extra heavy vitreous china bowl, brass bee-hive strainer, china bubbler head above rim of bowl with loose key volume regulator, controlled by Rasco patented ball-bearing self-closing valve, metal 4-ball handle, $1\frac{1}{2}$ -in. galv. drain, $\frac{3}{4}$ -in. supply to floor, concealed in pedestal. Exposed metal chrom. plated.

Diam. bowl 12 in., diam. base 15 in.

Height, in. 30 36

W't, lbs. 90 100

F41D1each \$36.00★ 38.00★




Wall Fountain with extra heavy vitreous china bowl, with integral drinking head above rim of bowl preventing dangerous syphonage if drain from bowl becomes clogged, integral strainer; controlled by Rasco patented ball-bearing self-closing valve with metal lever handle. Brass combination supply and drain fitting with concealed volume regulator; $\frac{3}{4}$ in. supply to wall with flange, and $1\frac{1}{2}$ in. drain connection to wall with flange. Mounted on heavy cast iron wall bracket.

Exposed metal chromium plated.

Diameter of bowl $9\frac{1}{2}$ in. Projection from wall 11 in. W't 25 lbs.

F164D0each \$21.00★



Pedestal Fountain of heavy vitreous china, modernistic octagonal design with integral angle stream non-squirting drinking head above rim of bowl, preventing dangerous syphonage if drain from bowl becomes clogged, integral china strainer; angle of stream does not allow water to be forced back onto point of discharge, controlled by Rasco patented ball-bearing self-closing valve with metal 4-ball handle and loose key angle compression volume regulating

valve, $1\frac{1}{2}$ in. galvanized drain and $\frac{3}{4}$ in. supply to floor, concealed in pedestal. Fastened to floor with two brass headed bolts.

Exposed metal chromium-plated.

Diam. of bowl 11 in., diam. of base 15 in., height 30 in., w't 100 lbs.

F14D0each \$66.00★

★Items Marked Thus ★ Are Shipped from Factory Only

Puro Sanitary Drinking Fountains




Straight stream, Push Button type fountain with brass nickel plated bowl. Equipped with flow control valve. Size 5x4½ in., ½ in. I. P. supply, ¾ in. I. P. waste. Shipping w't 4 lbs.

W40D0—Fountain only,
each\$7.25

W44D0—Fountain fitted with
basin slab adapter,
each\$9.75

Puro Cooler Complete


Can also be furnished to supply Puro Jr. Fountains at a point distant from the tank, if desired. The ice tank contains a 40-foot coil and with the special cover construction which hermetically seals the cooling chamber, 50 lbs. of ice will give a cool, refreshing drink for eight to ten hours. Connects directly with your city pressure, and is equipped with loose key valve control on supply line entering tank. To clean inside of tank unscrew standpipe with wing nut in the interior. Supplied with either straight or side stream tip. Diam. of base 13 in., diam. of cooler 18 in., height to top of cooler 27½ in., height to top of bowl 38 in., ¾ in. I. P. supply, ½ in. I. P. waste, shipping w't 185 lbs.



F8D0.....each \$75.00★

★F.O.B. Haydenville, Mass.

Self-Closing Drinking Fountain Stop




Ball bearing, straight pattern, renewable seat, four ball handle, plain metal cap, chromium plated, w't 1 lb.

Size, in.	¾	½
Nos.	331D0	332D0
Each	\$3.00	3.00

★Items Marked Thus ★ Are Shipped from Factory Only

Drinking Fountain Bubblers

Meet All Sanitary Code Specifications



Many of the City Health Departments throughout the country have adopted side stream bubblers as compulsory equipment on all drinking fountains. In many places they are insisting that old style bubblers be replaced with slant stream in all public buildings.

This bubbler will comply with various codes and can be used on either new installations or for replacement purposes.


Made extra heavy to withstand abuse. It is entirely sanitary with projecting outlets so that no water can run back into the supply and has a guard so that the users' lips cannot come in contact with the outlets.

Can be installed on fountains having ¾ in. supply, w't each 1 lb.

375D0—¾ in., I. P. Female Connections.....each \$3.00

376D0—¾ in., I. P. Male Connections.....each 3.00

Angle Stream Drinking Fountains



Brass, chromium plated, ½ in. I. P. Male connection, standard lavatory shank, self-closing, renewable seat, w't each 3 lbs.

F368D0each \$8.75★





Brass, chromium plated, ¾ in. I. P. Female connection, self-closing, renewable seat, w't each 3 lbs.

F373D0each \$6.00★

BUILT-IN LIGHTED MEDICINE CABINETS

APPROVED BY UNDERWRITERS' LABORATORIES



Heavy gauge stretcher-level steel, finished in fine quality hot-baked white enamel, plate glass mirror with 5-year silver-spoil guarantee, removable door, "Jiffy" ratchet mirror clips, two bulb-edge glass shelves, glass bottom shelf cover, toothbrush holder, razor blade drop, bullet door catch, sturdy chromium door stop and piano hinge. The required 40 watt, T8 Bulb not included. 16x24 in. beveled plate glass mirror, wall opening 13½x19½x3½ in., w't 35 lbs.

M997D2each \$23.50

The best value in lighted medicine cabinet on the market. A Venetian cabinet, smart chromium-plated side lights, and a surprisingly low cost. Wired complete, with switch located on return flange. Cabinet made of medium gauge automobile body steel, baked enamel finish, crystal mirror with 5-year silver-spoil guarantee, "Jiffy" ratchet mirror clips, two bulb edge glass shelves, tooth-brush holder, razor blade drop, bullet door catch, nickel plated door stop, selective shelf adjustment, sturdy butt hinges. The recommended 25 watt flame shaped frosted bulbs are not furnished. Size of mirror 15½x22 in., wall opening 13½x19½x3½ in., w't 30 lbs.

M457D0each \$16.95



DeLuxe Cabinet with Round Mirror

This handsome cabinet meets the present vogue for round mirrors. It is designed for bathrooms and dressing rooms in the ultra-modern or modern classic styles.

Heavy gauge stretcher-level steel, guaranteed "Whitecap" ELECTRO-RUST-PROOFED lacquer finish over baked red oxide prime coat, plate glass mirror with 5-year silver-spoil guarantee, "Jiffy" ratchet mirror clips, heavy bulb-edge glass shelf cover, toothbrush compartment, razor blade drop, bullet door catch, sturdy chromium-finish door stop. Diameter 25 in., wall opening 13½x18½x3½ in. W't each 42 lbs.

F700D0—Less Side Lights.....each \$27.75★


Tubular Side Lights

Designed for use with any cabinet—are particularly effective with the cabinet shown above. These units provide efficient, glareless lighting—sufficient to illuminate the entire bathroom. Price includes: frosted candles, set screws and switch—but not the required 40 watt T8 bulb, easily obtainable. 17x2½ in. overall, w't pair 6 lbs.

F333D0pair \$12.75★


★Items Marked Thus ★ Are Shipped from Factory Only

BUILT-IN MEDICINE CABINETS



Cabinet made of heavy gauge stretcher-level steel, finished in fine quality hot-baked white enamel. Plate glass mirror with 5-year silver-spoil guarantee, removable doors on framed cabinets, "Jiffy" ratchet mirror clips. Bulb-edge glass shelves. Glass bottom shelf cover. Toothbrush holder. Razor blade drop. Bullet door catch.

Mirrors, in.	16×24	18×26
Number of shelves.....	3	4
Wall opening, in.	13½×19½×3½	15½×21½×3½
Shipping w't, lbs.	30	34
Nos.	M799D0	M888D0
Each	\$12.75	17.50



For Hotels and Apartments

Cabinet made of heavy gauge stretcher-level steel finished in high quality, hot-baked enamel. Mirror plate glass, with 5-year silver-spoil guarantee. Bulb-edge glass shelves. Glass bottom shelf cover. Razor blade drop. Bullet door catch. Sturdy, chromium-plated door stop. Shelf adjustment. Semi-concealed nickel-plated hinge.


Mirrors, in.	12×16	14×18
Number of shelves.....	2	3
Wall opening, in.	13½×17½×3½	15½×19½×3½
W't each, lbs.	17	24
Nos.	M3100D0	M4100D0
Each	\$9.25	13.50



Cabinet made of medium gauge automobile body steel, baked enamel finish. 15½×22 in. crystal mirror with 5-year silver-spoil guarantee. "Jiffy" ratchet mirror clips. 2 bulb-edge glass shelves. Toothbrush holder. Razor blade drop. Bullet door catch. Nickel-plated door stop. Selective shelf adjustment. Sturdy butt hinges.

Requires wall opening of 13½×18½×3½ in., w't each 20 lbs.

M445D0each \$9.00



Cabinet made of medium gauge automobile body steel, baked enamel finish. 15½×23 in. crystal mirror with 5-year silver-spoil guarantee. Polished stainless steel frame. 2 bulb-edge glass shelves. Toothbrush holder. Razor blade drop. Bullet door catch. Nickel-plated door stop. Selective shelf adjustment. Sturdy butt hinges.

Requires wall opening of 15½×18½×3½ in., w't each 17 lbs.

M421D0each \$8.50

HIBBARD

Chrome Plated

FIXTURES

816C

WITH
WALL TYPE
CONCEALED SCREW



METAL BACK PLATE
SCREWS TO THE WALL—FIRST




THEN
FIXTURE IS
ATTACHED TO
BACK PLATE
WITH SET
SCREW
SET SCREW
CHROME
PLATED TO
MATCH FIXTURE
MAKING IT
PRACTICALLY
INVISIBLE

RECESSED FIXTURES


Require wall opening 5 in. square, 2 in. deep. Cast lugs on back for easy installation, approx. w't each 2 lbs.

Soap Dish and Grab Rail

Removable Black Rubber Inset.
629D0—4½×4½ in. overall,
each.....\$3.85
628D0—6×6 in. overall,
each.....\$4.25




Tumbler Holder



Without Tumbler
621D0—4½×4½ in. overall,
each.....\$2.40
620LD0—6×6 in. overall,
each.....\$2.65

Removable Black Rubber Inset.
610D0—6×6 in. overall,
each.....\$2.75

Black Wood Roller.
605D0—6×6 in. overall,
each.....\$2.75



Give Beauty.. Durability.. Added Value

Heavy Cast Metal, Octagon Design, 2½ In. Wall Plate

Soap Dishes

614D0—Plaineach \$1.50
615D0—Self drainingeach 1.45

Tooth Brush Holder

616D0each \$1.20

Plate Glass Shelves

618D0—5×18 in.....each \$3.75
624D0—5×24 in.....each \$4.25

Paper Holder

611D0each \$1.50

Grab Rail

¾×8 in.

648D0each \$2.00

Powdered Soap Dispenser

617D0each \$4.25

Tumbler Holder

612D0each \$1.25

Robe Hook



619D0each \$0.85

Towel Bars

638D0—¾×18 in.....each \$2.65
634D0—¾×24 in.....each 2.95
630D0—¾×30 in.....each 3.25

Paper Holder

Soap Dish



CHROMIUM PLATED SOLID FORGED BRASS BATHROOM FIXTURES

A beautiful and distinctive design which may be matched with cabinets and lighting fixtures, and which will add charm to the most luxurious bathroom. Glass furnished in clear crystal, brackets of fixtures are furnished chromium plated, concealed screw installation.



Square Metal Towel Bar

$\frac{3}{4}$ in. bar, wall flange $2\frac{1}{2} \times 2\frac{3}{4}$ in., projection $3\frac{3}{4}$ in.


Length, in.	18	24	30
W't each, lbs.	1 $\frac{1}{4}$	2	3
Nos.	5018D0	5024D0	5030D0
Each	\$3.50	3.85	4.35



Crystal Glass Shelf

$5 \times \frac{1}{8}$ glass shelf, spring brackets, wall flange $2\frac{1}{2} \times 2\frac{3}{4}$ in., projection $5\frac{3}{4}$ in.

Length, in.	18	24
W't each, lbs.	2	3
Nos.	6018D0	6024D0
Each	\$5.00	5.50



Paper Holder

Width overall $8\frac{1}{2}$ in., wall flange $2\frac{1}{2} \times 2\frac{3}{4}$ in., w't each $\frac{1}{2}$ lb.

8590D0each \$2.50



Crystal Soap Holder

Size of dish $6\frac{1}{2} \times 5 \times 2$ in., wall flange $2\frac{1}{2} \times 2\frac{3}{4}$ in., projection 6 in., w't each $\frac{3}{4}$ lbs.

7040D0each \$3.65



Tumbler Holder

Size $3\frac{1}{2} \times 3\frac{1}{2}$ in., wall flange $2\frac{1}{2} \times 2\frac{3}{4}$ in., projection $3\frac{3}{4}$ in., w't each $\frac{1}{2}$ lbs.

8156D0each \$3.00



Square Metal Grab Bar

Width $11\frac{1}{2}$ in., wall flange $2\frac{1}{2} \times 2\frac{3}{4}$ in., projection $3\frac{3}{4}$ in., w't each $1\frac{1}{2}$ lbs.

5120D0each \$3.25



Metal Soap Holder

Width $4\frac{1}{2}$ in., wall flange $2\frac{1}{2} \times 2\frac{3}{4}$ in., projection $4\frac{1}{2}$ in., w't each $\frac{3}{4}$ lbs.

7170D0each \$2.00



Metal Soap Holder and Grab Bar

Width $11\frac{1}{2}$ in., wall flange $2\frac{1}{2} \times 2\frac{3}{4}$ in., projection $4\frac{1}{2}$ in., w't each 2 lbs.

7300D0each \$4.00



Tumbler and Toothbrush Holder

Width $4\frac{1}{2}$ in., wall flange $2\frac{1}{2} \times 2\frac{3}{4}$ in., projection $4\frac{1}{2}$ in., w't each $\frac{1}{2}$ lbs.

8150D0each \$2.00



Toothbrush Holder

Width $2\frac{3}{4}$ in., wall flange $2\frac{1}{2} \times 2\frac{3}{4}$ in., projection $3\frac{1}{4}$ in., w't each $\frac{1}{4}$ lbs.

8130D0each \$1.85



Single Hook

Width $2\frac{3}{4}$ in., wall flange $2\frac{1}{2} \times 2\frac{3}{4}$ in., projection $2\frac{1}{4}$ in., w't each $\frac{1}{4}$ lbs.

40D0each \$1.10



Double Hook

Width 3 in., wall flange $2\frac{1}{2} \times 2\frac{3}{4}$ in., projection 3 in., w't each $\frac{3}{4}$ lbs.

80D0each \$1.65

Hibbard

SUPER-SEAT FAUCET

DEAL

*Here's Why We Can
Guarantee This Faucet
for Ten Years*

- (1) Has no rubber washers to wear out.
- (2) Has no sharp brass seat to cut special metal washers.
- (3) Washer is made of special soft metal and any cuts or rough edges made by water passing thru faucet are leveled off when faucet closes and seat rubs on hard metal stem.
- (4) Has only four working parts.

A cut open faucet section mounted on every display.

Any customer can see why this faucet WILL NOT LEAK.

GUARANTEED 10 YEARS

Here's Why!

THEY'RE EQUIPPED
WITH NEW SUPER-SEAT
METALLIC SHUT-OFF
GASKET that will give you
Years of Trouble-Free Service



Hibbard

**SUPER-SEAT
FAUCETS**

RENEWABLE
DISC NOT
AFFECTED
BY HEAT
OR COLD



DEAL CONSISTS OF:

		Retail Value
2 No. 44LD0 Chromium Plated Sink Faucets	@ \$4.98	9.96
2 No. 7451LD0 Chromium Plated Hot Basin Faucets	@ 1.75	3.50
2 No. 7452LD0 Chromium Plated Cold Basin Faucets	@ 1.75	3.50
1 Display Selling Card	FREE	
1 Cut Open Section Showing non-wearing seat	FREE	
1 Display Stand	FREE	
6 Faucets in all.		

No. M44LD0—Deal of 6 Faucets Per Deal \$16.96

A SINK FAUCET with a REAL *Selling Point*

EQUIPPED WITH NEW SUPER-SEAT
METALLIC SHUT-OFF GASKET THAT
WILL GIVE YEARS OF TROUBLE-
FREE SERVICE WITHOUT RENEWAL



GUARANTEED 10 YEARS



RENEWABLE METAL
GASKET NOT EFFECTED
BY HEAT OR COLD

SLEEVE
ALSO IS
RENEWABLE
AND SLIPS
OUT OF
BODY
AS SHOWN

Hibbard SUPER-SEAT FAUCETS

Truly Beautiful Sink Fitting, designed to grace the finest of modern kitchens. Has a brilliant, silvery lustre that will not tarnish or corrode.

Brass throughout, chromium-plated with self-draining soap dish, eccentric female flanges. Anti-splash spout. W't each 7 lbs.

44D0 each \$4.98

Read What Exhaustive Engineering Test Proved

Water was kept running constantly and the faucet turned off and on, by mechanical means, 591,300 times without damage or any considerable wear on the Super-Seat gasket. Such an engineering test proves that Super-Seat faucets should operate under normal service conditions for years without replacement of gasket or other expense.

Super-Seat Faucet Parts



208D9—Hot Sleeve,
each\$0.45

209D9—Cold Sleeve,
each\$0.45



211D9—Seat Rings,
each\$0.10



213D9—Hot Stem,
each\$0.40

214D9—Cold Stem,
each\$0.40

Here is
something
you've
needed for a
long time - -

A New
Counter Display
That Brings the
Every-Day
Sellers Out
Where They Can
Be Seen

2 DISPLAY
STANDS
FREE

EVERY DEALER SHOULD
USE ONE IN HIS STORE
AND ONE IN HIS WINDOW

ORDER NOW

ALMOST 40% MARGIN
ON DEALERS SELLING
PRICE



CLOSET TANK *Replacement Parts* **DEAL**

Contents of M1395D4 Deal

			Retail Value
6 only	No. 92D	China Set Ball Cocks	@ \$1.10 \$ 6.60
6 only	No. 77D	Flushing Levers	@ .60 3.60
6 only	No. 2 3/4 D	2 3/4 in. Tank Balls	@ .25 1.50
12 only	No. 2 1/2 D	2 1/2 in. Tank Balls	@ .25 3.00
12 only	No. 34D	Copper Floats	@ .25 3.00
2 only	No. 21D	Flush Tanks	@ 1.25 2.50
2 only	Display Stands	FREE FREE

44 Items.


No. M1395D4—1 Deal.....deal \$20.20

W't deal 35 lbs.


Prices Net F.O.B. Chicago, Add Freight to _____

Toilet Seat Hinges

Heavy chromium plated brass offset bar hinge and bar bumpers, size 4x6 in., w't 1½ lbs.



9D9—Open Stockset \$0.85
Lots of 6 sets *



Flushing Levers

Double acting, chromium plated handle and rose. W't each ½ lb.

77D0—Open Stockeach \$0.60
77D2—Lots of 6 *

Flush Valves

Rough Brass beveled seat insuring positive seating of ball, heavy cast brass lock nut, beveled rubber spud gasket, flush ball guide U-shaped, upper and lower lift wires.

Complete with overflow tube 1½x11 in., w't each 1½ lbs.

21D9—Open Stock, each\$1.25
21D1—Lots of 6 *


Closet Spuds

Rough Brass, size 2 in., w't per doz. 12 lbs.

22D9.....each \$0.45



Guide Holders



Adjustable, unfinished. Made to slip on 1 in. overflow tube on a low tank valve and the guide is made adjustable to fit any Douglas type valve with rubber ball, w't each ¼ lb.

Size, in. 1 1½
Lots of 5.....970D9 971D9
Each\$0.25 .30


Lots of 25.....970D1 971D1



Not adjustable, unfinished. Made to slip on 1 in. overflow tube on a low tank valve. Size 1 in., w't per doz. 1 lb.

120D0—Pkg. of 1 dz *each \$0.15

Spud Reducers



Cast Brass, Nickel Plated


Size, in.	2x1½	2x1½
W't doz., lbs.....	2	2
Nos.	595D0	596D0
Each	\$0.60	.60

Closet Floor Flanges

Brass, outside diam. 6½ in., inside diam. 4½ in.

182D9—each\$0.39

LOOSE




Closet Pulls

Birch, natural finish with N. P. chain, w't per doz. 3 lbs.

318D0each \$0.39


Closet Screws



Complete with brass cap, nuts and oval nickel plated washers, w't doz. ½ lb.

Solid Brass		
Size, in.	¼x2½	⅝x2½
Pkg. of 100 *	78D1	79D1
Each	\$0.05	.10

Steel Screw, Brass Plated		
Size, in.	¼x2½	⅝x2½
Pkg. of 100 *	571D1	572D1
Each	\$0.05	.10




Closet Bolts

Wrought Brass Bolt with nickel plated nut and washers. Bolts tapped, 18 threads to the inch, w't per doz. 5 lbs.

Size, in.	⅝x1½	⅝x2½
Pkg. of 100 *	24D1	241D1
Each	\$0.10	.10

Closet Ells


With Cast Hex Nuts
Brass, diameter 2 in., w't each 1 lb.



Size, in. ...	4x6	4x6	5x6	5x6
Finish	Nickel	Chrome	Nickel	Chrome
Nos.	880D9	882D9	883D9	885D9
Each	\$1.20	1.40	1.30	1.50

Size, in. ...	5x7	5x7	6x8	6x8
Finish	Nickel	Chrome	Nickel	Chrome
Nos.	888D9	886D9	889D9	887D9
Each	\$1.35	1.65	1.65	1.85

Closet Elbow Nuts



For closet elbows and closet connections, chrome plated. 2 in. I. P. size.

88D0—Lots of 1 dz *each \$0.25

Closet Ells



For High Tanks

Nickel plated brass, diam. 1½ in. 6 in. long, with cast nuts and rubber washers, w't each ½ lb.

188D9each \$0.85

Offset Closet Connections


Chrome plated, 2 in. diam., 6 in. high, complete with nuts.

884D0.....each \$1.75

LOOSE



Rubber Closet Elbows



Complete With Fittings

Size, in.	1½	1½
W't doz., lbs.....	6	9
Nos.	1212D0	1213D0
Each	\$0.30	.60

HIBBARD *Tailor Made* ENAMEL FINISH PIPE COVERING

*A Permanent Glazed Color
Beauty Plus Pipe Insulation*

Dress Up Your Basement At No Extra Cost

Easy to Keep Clean. Four Attractive Colors, Red, White, Silver and Green
3 ft. Lengths. Furnished Complete with Black Metal Bands

No. F33D0— $\frac{3}{4}$ in. Thickness

For pipe, in.....	1/2	3/4	1	1 $\frac{1}{4}$	1 $\frac{1}{2}$	2	3	4
Foot	\$0.12★	.14★	.15★	.17★	.18★	.21★	.24★	.33★

No. F44D0—1 in. Thickness


For pipe, in.....	1/2	3/4	1	1 $\frac{1}{4}$	1 $\frac{1}{2}$	2	3	4
Foot	\$0.14★	.15★	.17★	.18★	.21★	.23★	.27★	.36★

IN ORDERING SPECIFY COLOR DESIRED


Boiler Jackets

Silver Finish

For tank, gal.....	30	40	52
W't each, lbs.....	18	19	22
Nos.	W730D0	W740D0	W752D0
Each	\$4.50	5.50	6.75



Smooth silver finish outside and contrasting black enameled bands adds a note of cleanliness to the kitchen or basement.




★Items Marked Thus ★ Are Shipped From Factory Only

Prices Net F.O.B. Chicago, Add Freight to _____

INSULATE TO PREVENT WASTE


Excel Range Boiler Tank Jacket

3 plies of $\frac{1}{4}$ in. Air Cell Paper. Comes in two sections, with bands, 5 lb. Asbestos Cement for finishing the top, and strips of Asbestos Paper for sealing the joints.



Cap., gals.	30	40	52
Nos.	W530D1	W540D1	W520D1
Each.....	\$3.00	3.50	3.75
Cap., gals.	66	80	
Nos.	W660D1	W880D1	
Each.....	\$4.00	4.50	

Asbestos Air-Cell Paper




Made of two sheets asbestos paper cemented together, one sheet flat, one sheet with $\frac{1}{4}$ in. high corrugations, making dead air cells for extra insulation. This sheet is flexible and can be wrapped to as many plies as required and easily fastened by wire around the outside or by flat asbestos paper pasted around. Used extensively on warm air furnace pipes to confine the heat to the pipes and insure full delivery of warm air at the register.

Air-Cell Corrugated Paper, in rolls 36 in. wide, 83 $\frac{1}{2}$ ft. long, 250 sq. ft., w't per roll about 50 lbs.

F19D0—1 to 3 rolls.....roll \$6.00★
F19D1—Crate of 4 rolls.

WE DO NOT CUT ROLLS

Asbestos Aircell Pipe Covering



For Low Pressure Steam and Hot Water Pipes


Made in sections 36 in. long to fit all standard pipe sizes. Finished with canvas jacket and brass lacquered metal bands. So constructed as to form a great number of small aircell spaces. The plies of Aircell Paper (alternating one flat and one corrugated) used in building up this covering are very rigid and have in themselves a high insulating value. The corrugations are like a reinforced bridgework that makes it a firm, sound section. **Aircell Pipe Covering** is light, yet sturdy and durable. Each section is encased in a canvas wrapper with a good side lap and end lap. Each ply of Aircell Covering is $\frac{1}{4}$ in. thick.

Per Lineal Ft.

Nos.	FC2D9	FC3D9	FC4D9
For Pipe, Inside Diam., In.	$\frac{1}{2}$ in. Thick- ness, 2 Ply	$\frac{3}{4}$ in. Thick- ness, 3 Ply	1 in. Thick- ness, 4 Ply
$\frac{1}{2}$	\$0.22★	\$0.22★	\$0.22★
$\frac{3}{4}$.24★	.24★	.24★
1	.27★	.27★	.27★
1 $\frac{1}{4}$.30★	.30★	.30★
1 $\frac{1}{2}$.33★	.33★	.33★
2	.36★	.36★	.36★
2 $\frac{1}{2}$.40★	.40★	.40★
3	.45★	.45★	.45★
3 $\frac{1}{2}$.50★	.50★	.50★
4	.60★	.60★	.60★
4 $\frac{1}{2}$.65★	.65★	.65★
5	.70★	.70★	.70★
6	.80★	.80★	.80★
7	1.00★	1.00★	1.00★
8	1.10★	1.10★	1.10★
9	1.20★	1.20★	1.20★
10	1.30★	1.30★	1.30★
12	1.85★	1.85★	1.85★

FC2D9—2 Ply—Disc.	50%
FC3D9—3 Ply—Disc.	50%
FC4D9—4 Ply—Disc.	45%

Wool Felt Pipe Covering



For Cold Water Pipe

Designed to provide inexpensive insulation for cold water pipes and gives fair results in preventing sweating or freezing. Perfecto pipe covering consists of laminations of insulating felt with a waterproof felt liner.

Furnished in 36-in. long sections, with cotton duck jackets and bands, in $\frac{1}{2}$, $\frac{3}{4}$, 1-in. double $\frac{1}{2}$ -in. and double $\frac{3}{4}$ -in. thicknesses.

Per Lineal Ft.

Nos.	F12D9	F13D9	F14D9
For Pipe, Inside Diam., In.	$\frac{1}{2}$ in. Thick- ness,	$\frac{3}{4}$ in. Thick- ness,	1 in. Thick- ness,
$\frac{1}{2}$	\$0.22★	\$0.22★	\$0.22★
$\frac{3}{4}$.24★	.24★	.24★
1	.27★	.27★	.27★
1 $\frac{1}{4}$.30★	.30★	.30★
1 $\frac{1}{2}$.33★	.33★	.33★
2	.36★	.36★	.36★
2 $\frac{1}{2}$.40★	.40★	.40★
3	.45★	.45★	.45★
3 $\frac{1}{2}$.50★	.50★	.50★
4	.60★	.60★	.60★
4 $\frac{1}{2}$.65★	.65★	.65★
5	.70★	.70★	.70★
6	.80★	.80★	.80★
7	1.00★	1.00★	1.00★
8	1.10★	1.10★	1.10★
9	1.20★	1.20★	1.20★
10	1.30★	1.30★	1.30★
12	1.85★	1.85★	1.85★

F12D9—Disc.	25%
F13D9—Disc.	40%
F14D9—Disc.	30%

Carton Contents and Weights

Pipe Size, In.	2 Ply		3 Ply		4 Ply	
	Lgths. Per Carton	W't Per Carton	Lgths. Per Carton	W't Per Carton	Lgths. Per Carton	W't Per Carton
1/2	68	61	40	70	36	60
3/4	55	60	36	61	26	54
1	42	48	30	60	24	52
1 $\frac{1}{4}$	36	48	25	54	19	50
1 $\frac{1}{2}$	28	46	20	52	17	46
2	20	36	16	46	12	44
2 $\frac{1}{2}$	16	34	12	40	11	40
*3	16	42	11	38	10	38
*3 $\frac{1}{2}$	14	43	10	37	9	35
*4	12	48	9	40	7	32

*This denotes lengths packed with the sections opened.

★Items Marked Thus ★ Are Shipped from Factory Only

Fire Pot Heaters and Hot Water Generators




Cast Iron

Most popular and efficient type. For vertical installation in bed of fire in Hot Air Furnace and Hot Water Boilers. Fins permit air circulation around body, preventing clinkers and deadening of fire. Do not interfere with firing. Easily installed as they have tapped holes on 2½, 6, and 9 in. centers to fit openings in side of various boilers. They are very efficient in boilers using soft coal as they extend below caked surface.

Capacity, gal.	30	40	60
W't each, lbs.	6½	8	16
Nos.	W10D0	W11D0	W12D0
Each	\$1.15	1.60	2.85

Hot Water Generator



Heat intensified at base of fins, causing reverse water currents to be formed, thus completely agitating water at all times. This prevents precipitation and accumulation of lime or foreign matter within generator.

This system is the reverse principle of the air cooled engine.

The hot water generator replaces the old fashioned pipe and return bend in furnace or boiler.

Heats more, and hotter water than ordinary pipe.

Specifications

Fifty gallon capacity. Size 12×4½×2½ in., w't 8½ lbs. Tapped for ¾ or 1 in. pipe. Standard 2½ in. centers. Cubic content 98% more than 1 in. pipe.

Vertical Coils

100D0each \$3.25

Thirty gallon capacity. Size 9½×4½×2½ in., w't 7½ lbs. Tapped for ¾ or 1 in. pipe. Standard 2½ in. centers. Cubic content 93% more than 1 in. pipe.

Horizontal Coils

50D0each \$2.00

"Hi-Temp" One-Piece Hot Water Coils

Made of one-piece welded steel pipe, without a single joint these coils have no place where leakage can occur, no break in inner surface where pockets may form. Because of their carefully designed curve much greater water travel is possible. Hugging sides of dome snugly they lie in hottest area in furnace.

They are so perfectly fitted to contour of dome section and of such length that they are not only twice as efficient as ordinary coils, but out of way of coal shovel and therefore not subject to damage.

Adapted to any make of furnace having holes for water coil alongside feed door. Fit either right or left side. So made that they fit holes spaced anywhere from 2½ to 3½ in.




Steel

Length 25½ in.

Male connection, in.....	3/4	1
W't each, lbs.....	4½	6½
Open stock	74D0	75D0
Each	\$1.20	1.40

Lots of 3 * 74D0 75D0

Mor-Flo Heater Coil



Cast Iron

1 in. female connection, 2½ in. centers. Length 15½ in. overall, w't each 10 lbs.

17D0each \$2.00

Thread Cutting Oil




In Cans

A high grade oil used in cutting threads on pipe and fittings.

Cap.	1/2 Pt.	1 Pt.	1 Qt.
W't doz., lbs.....	6	10	18
Nos.	20D0	21D0	24D0
Each	\$0.25	.30	.50

ONE DOZEN IN A CARTON

Skinner Emergency Pipe Clamps



For stopping leaks in pipe lines, instantly, permanently.

Malleable iron cylinder, halved, hinged along one side and fitted with bolts on the other. A gasket completes the clamp. Resists rust.

For the larger sizes of pipe, clamps are reinforced with heavy ribs, which insure security under high pressure.

Size of pipe, in...	1/2	3/4	1	1½	1½
Lgth. overall, in..	3½	3½	3½	3½	4
W't each, lbs.....	½	1½	1½	1½	1½
26D0..... each	\$0.80	.90	1.00	1.20	1.40

Size of pipe, in.....	2	2½	3	4
Length overall, in....	4½	4½	5	6
W't each, lbs.	2½	3½	4½	7½
26D0..... each	\$1.60	2.00	2.50	4.00

½ TO 2 IN., 12 IN A CARTON; 2½ TO 4 IN., 6 IN A CARTON

Smooth-On Iron Cement

Factory No. 1



A chemical iron cement for repairing leaks or breaks in iron or steel. Sold in powdered form. Applied by mixing with water, metalizes quickly, invaluable for household repairs and will withstand water, fire, steam, gas

or oil. Will not deteriorate. Ready for use at any time.

1 Lb. Cans

10N9—Open Stockcan \$0.50

10N2—Lots 12 cans *

7 Oz. Cans

30N9—Open Stockeach \$0.30

30N2—Lots of 1 dz *

1½ Oz. Cans

28N0—Pkg. of 2 dz *each \$0.10

Pipe Joint Compound

"Mitee"

Especially Good
for Use on Brass

Unequalled for use on Pressure Tight Joints or on joints requiring frequent attachment and removal. It lubricates, preventing stripping or corroding of threads and will not shrink, crumble, harden or crack. Remains

pliable indefinitely on either hot or cold water pipes. Entirely free from grit and lumps, being perfectly ground and does not squeeze out when joints are made tight. Put up in one pound tins, w't per doz. 7 lbs.

81D0—Lots of 1 dz *each \$0.25

LOOSE

"John Sunshine"




For use in sealing all pipe connections on air pressure, gas, steam and hot or cold lines. Contains no dry hardening cement or white lead, waterproof.

In Handy Tubes, wt' doz. 3 lbs.

8D9—Pkg. of 1 dz *each \$0.10

IN COUNTER DISPLAY BOX

C-Ler-Tite White Lead Pipe Joint Compound



Just the thing for the small job, such as gas connections, steam pipes, furnace coils and screw thread joints. Handy for any work requiring pure white lead and oil. Always ready for use and many uses for it. Lithographed tubes, size $\frac{3}{4} \times 3\frac{1}{4}$ in., one dozen on a counter card, w't doz. 2 lbs.

140D9—Pkg. of 1 dz *each \$0.10

Horn Pipe Joint Cement



Unlike red lead or white lead because it never dries out—it is made by combining extremely finely ground pigments with durable, water-repelling oils that remain elastic and do not taint the water. Sets pipe joints absolutely tight and it remains pliable and plastic, never drying out or shrinking.

20D9—Lots of 6, one-lb cans *\$0.25

25D9—5 lb. canscan 1.25

M50D0—50 lb. canscan 9.00

M100D0—100 lb. cans,15.00

"Mitee" Boiler Liquid

For Repairing
Leaky Boilers
Works in Hot or
Cold Water

A high quality boiler repair liquid. Will stop leaks in steam or hot water boilers while in operation. Makes it unnecessary to cut off heating system. Put up in quart cans, lithographed in colors. No label to tear off or soil. W't doz. 31 lbs.

200D0—Lots of $\frac{1}{4}$ dz *each \$0.50

200D2—Pkg. of 1 dz *



X Boiler Liquid



Repairs leaks in high and low pressure boilers and hot water heating systems.

Size, qts.	1	2
W't per can, lbs.	2½	4½
Nos.	20D0	30D0
Each	\$3.00	5.00

PACKED SIX CANS

X Boiler Flush



Removes scale, sludge and rust from high and low pressure boilers, hot water systems. Cap. 2 qts., w't per can 2½ lbs.

15D0—Lots 3 cans *can \$2.00

PACKED SIX CANS

"X" Boiler "Flush" and "Rustoff"



A complete heating system treatment in a combination package of two interlocking cans.


"X" Flush in the upper can is used to clean the system. It stops foaming and contains no acid.

"X" Rustoff in the lower can keeps the water clean, retarding the formation or rust and scale and is guaranteed harmless. It requires no mixing before use.

W't can 2½ lbs.
40D0can \$3.50

Hibbard UNIT HEATERS

Take place of cast iron radiators on steam heating systems. Their purpose is to give better distribution of heat, economical operation. Saves floor space, eliminating radiators, permitting boiler on first floor.



Front View

Scientific Design

Every construction feature has been proven by a large number of units in everyday use. Sound engineering and careful design of the radiator and fan makes a quieter unit heater without annoying vibration.

Particular attention was given to design and spacing of fins, the result that resistance is very low. Copper used because this metal has highest heat conductance and transfer capacity. Balanced, independent suspension takes strain off steam pipes.

Individual 3-in. copper tubes with 1-in. fins brazed into heavy copper headsheets by special process. Heavy wall tubing used to insure against tube failures. Copper heat transfer surface or core is bolted special cast iron steam inlet and outlet tanks by means of large cap screws on 1-in.



Rear View

centers. A special, long fibre asbestos super-heat gasket is placed between the ground surfaces, thus making a permanent leakproof header, removable for cleaning, repairs or replacement. Expansion and contraction is taken care of in every core to prevent undue strains. Entire heating core removable from electrically welded steel shell.

High grade motors with a standard NEMA base are mounted on simple shelf brackets, permitting any make of standard base motor to be installed. Fans used are the development of many tests in an effort to secure maximum velocity and quietness. Finished in black crystal baked enamel. Heaters are carefully inspected and tested for 150 pounds working steam pressure.

Hibbard UNIT HEATERS are offered in a carefully and standardized range of sizes and capacities to meet the specific requirements of a large variety of conditions. **SEND US YOUR SPECIFICATIONS.**

Hibbard Classic BOILER

Guaranteed for Five Years

Any Parts Giving Out Within Five Years Will Be Replaced Free of Charge



20 in. Size—The Most Popular Size for Most Homes

Attractive, Two-Tone Gray Enameled Streamlined Jacket

Heavy asbestocel insulation, front, back, top and sides.

Large combustion chamber entirely surrounded by water; ample space for complete combustion.

High efficiency, quick pick-up and low fuel cost.

Convenient grate-shaking mechanism, easily operated.

Large size ashpit eliminates the necessity of frequent removal of ashes.

The roomy fire box with large coal capacity makes frequent attention unnecessary.

Ample space in the fire box insures burning of gases at high temperatures.

Long fire travel through six flue ways formed by numerous water tubes insures high operating efficiency.

Large fire door makes firing easy and prevents spilling coal.

Large flue door exposes flues, making cleaning a simple task.

Boiler sections are shipped assembled; the base assembled and crated, making erection an easy job.

Substantial construction throughout assures long life.

The **Hibbard** "Classic" Sectional Boiler was designed by skilled engineers, according to the most scientific heating principles. The deep fire box holds a large charge of coal, making frequent attention unnecessary. There is ample space above the coal bed for proper burning of the gases at high temperatures. The double tier of three flue ways formed by water tubes causes the burning gases to travel up and forward and then back the full length of the boiler. The numerous water tubes extract all of the available heat and send it up to the radiators, instead of wasting it up the chimney. The **Hibbard** "Classic" Boiler, because of its design has a quick pick-up and gives a lot of heat in a hurry when needed.



View of Boiler Base Showing Sturdy Construction and Heavy Slicer Door Liner. Removable Panels in the Base Sides Facilitates Removal of Grates

To attractive appearance are added ease of installation, economical operation, and thoroughly dependable performance. The burning gases rise to the crown sheet which provides a large amount of direct heat absorbing surface. They are then drawn to the rear of the boiler where they pass up into the two outside flues through which they travel to the front of the boiler and then back through the two center flue ways the entire length of the boiler.

Hibbard Classic BOILER

"TWENTY SERIES"

STANDARD EQUIPMENT

RATINGS AND DIMENSIONS

STEAM BOILERS				WATER BOILERS		STEAM AND WATER BOILERS								
Nos.	Guaranteed * Load, Sq. Ft. E. D. R.	Commercial Rating, Sq. Ft.	Water Line, In.	Guaranteed * Load, Sq. Ft. E. D. R.	Commercial Rating, Sq. Ft.	Grate Area, Sq. Ft.	Supply Outlets, No. and Size, In.	Return Inlets, No. and Size, In.	Height to Outlet, In.	Width, In.	Height Overall, In.	Smoke Pipe, In.	Fire Door Opening, In.	Ash Pit Door Opening, In.
F420	400	900	47¾	640	1440	2.60	2 — 3	2 — 3	55	27	55	9	8½x16	8½x16
F520	525	1180	47¾	840	1890	3.46	2 — 3	2 — 3	55	27	55	9	8½x16	8½x16
F620	650	1460	47¾	1040	2340	4.32	2 — 3	2 — 3	55	27	55	9	8½x16	8½x16
F720	775	1740	47¾	1240	2790	5.18	2 — 3	2 — 3	55	27	55	9	8½x16	8½x16

* Guaranteed loads are based on 12,500 B.T.U. coal with an allowance of 20% for piping. In selecting boiler size it is not necessary to add for normal piping.

Hibbard Classic Jacketed and Unjacketed Boilers

STEAM

Supplied with Safety Valve, Compound Gauge, Water Gauge and Glass, Try Cocks, Metal Automatic Steam Regulator, Fusible Plug, Metallic Jacket and Insulation and Firing Tools.

Boiler No.	Shipping W't, Lbs.	Guaranteed Load, Sq. Ft., E. D. R.	Jacketed, Each	Un-Jacketed, Each
F420SD0	1500	400	\$116.95★	\$104.35★
F520SD0	1750	525	154.00★	140.00★
F620SD0	1960	650	191.25★	176.00★
F720SD0	2200	775	228.50★	212.50★

WATER

Supplied with a combined Altitude Gauge, and Thermometer, Metal Automatic Regulator, Metallic Jacket and Insulation, and Firing Tools.

Boiler No.	Shipping W't, Lbs.	Guaranteed Load, Sq. Ft., E. D. R.	Jacketed, Each	Un-Jacketed, Each
F420WD0	1480	640	\$116.95★	\$104.35★
F520WD0	1730	840	154.00★	140.00★
F620WD0	1940	1040	191.25★	176.00★
F720WD0	2180	1240	228.50★	212.50★

★Items Marked Thus ★ Are Shipped From Factory Only

Prices Net F.O.B. Chicago, Add Freight to

Hibbard "Classic" BOILER

With Five Year Guaranty

"SEVENTEEN SERIES"

STANDARD EQUIPMENT

Steam boilers are supplied with Safety Valve, Compound Gauge, Water Gauge and Glass, Try Cocks, Metal Automatic Steam Regulator, Fusible Plug, Metallic Jacket and Insulation and Firing Tools.

Water boilers are supplied with a combined Altitude Gauge, and Thermometer, Metal Automatic Regulator, Metallic Jacket and Insulation, and Firing Tools.

Ratings and Dimensions

STEAM BOILERS				WATER BOILERS		STEAM AND WATER BOILERS								
Nos.	Guaranteed* Load, Sq. Ft. E. D. R.	Commercial Rating, Sq. Ft.	Water Line, In.	Guaranteed* Load, Sq. Ft. E. D. R.	Commercial Rating, Sq. Ft.	Grate Area, Sq. Ft.	Supply Outlets, No. and Size, In.	Return Inlets, No. and Size, In.	Height to Outlet, In.	Width, In.	Height Overall, In.	Smoke Pipe, In.	Fire Door Opening, In.	Ash Pit Door Opening, In.
417	200	400	44½	330	675	1.5	2—2½	2—2½	55½	25	55½	9	8½×16½	9×14½
517	290	575	44½	480	950	2.0	2—2½	2—2½	55½	25	55½	9	8½×16½	9×14½
617	380	750	44½	630	1250	2.5	2—2½	2—2½	55½	25	55½	9	8½×16½	9×14½
717	470	925	44½	780	1550	3.0	2—2½	2—2½	55½	25	55½	9	8½×16½	9×14½
817	560	1100	44½	930	1850	3.5	3—2½	2—2½	55½	25	55½	9	8½×16½	9×14½
917	650	1275	44½	1080	2150	4.0	3—2½	2—2½	55½	25	55½	9	8½×16½	9×14½
1017	740	1450	44½	1230	2450	4.5	3—2½	2—2½	55½	25	55½	9	8½×16½	9×14½

*Guaranteed loads are based on 12,500 B.T.U. coal with an allowance of 20% for piping. In selecting boiler size it is not necessary to add for normal piping.

Hibbard "Classic" Jacketed and Unjacketed Boilers

Steam

Boiler No.	Shipping W't, Lbs.	Guaranteed Load, Sq. Ft., E.D.R.	Jacketed Each	Un-Jacketed Each
F417SD0	900	200	\$ 90.25	\$ 77.65
F517SD0	1050	290	97.75	83.95
F617SD0	1185	380	112.65	97.75
F717SD0	1350	470	127.50	111.75
F817SD0	1500	560	142.50	125.50
F917SD0	1640	650	156.50	139.25
F1017SD0	1800	740	172.25	153.00

Water

Boiler No.	Shipping W't, Lbs.	Guaranteed Load, Sq. Ft., E.D.R.	Jacketed Each	Un-Jacketed Each
F417WD0	880	330	\$ 81.95	\$ 70.25
F517WD0	1040	480	88.25	75.50
F617WD0	1175	630	102.00	88.25
F717WD0	1335	780	115.95	100.95
F817WD0	1490	930	129.65	113.75
F917WD0	1635	1080	143.50	126.50
F1017WD0	1780	1230	156.50	139.25

Entire Page for Factory Shipment Only

Net F.O.B. Chicago, Add Freight to _____

Hibbard "Classic" BOILER

Guaranteed for Five Years

Any Parts Giving Out Within Five Years Will Be Replaced Free of Charge

THE STREAMLINED BOILER

Easy to Install : Low Fuel Cost

The **Hibbard** "Classic" Sectional Boiler was designed by skilled engineers, according to the most scientific heating principles. The deep fire box holds a large charge of coal, making frequent attention unnecessary. There is ample space above the coal bed for proper burning of the gases at high temperatures. The double tier of three flue ways formed by water tubes causes the burning gases to travel up and forward and then back the full length of the boiler. The numerous water tubes extract all of the available heat and send it up to the radiators, instead of wasting it up the chimney. The **Hibbard** "Classic" Boiler, because of its design, has a quick pick-up and gives a lot of heat in a hurry when needed.



The 17 Series **Hibbard** "Classic" Water Boiler

Hibbard "Classic" Features

1. Attractive appearance . . . high efficiency . . . quick pick-up . . . low fuel cost.
2. Streamlined jacket, insulated thoroughly to prevent heat loss.
3. Convenient grate-shaking mechanism, easily operated.
4. Large size ashpit eliminates the necessity of frequent removal of ashes.
5. The roomy fire box with large coal capacity makes frequent attention unnecessary.
6. Ample space in the fire box insures burning of gases at high temperatures.
7. Long fire travel through six flue ways formed by numerous water tubes insures high operating efficiency.
8. Large fire door makes firing easy and prevents spilling coal. Large flue door exposes flues, making cleaning a simple task.
9. Boiler sections are shipped assembled; the base assembled and crated, making erection an easy job.
10. Substantial construction throughout assures long life.



Cut-Away View of the 17 Series **Hibbard** "Classic" Boiler Showing Deep Fire Box and Water Tube Construction

To attractive appearance are added ease of installation, economical operation, and thoroughly dependable performance. The forward and back fire travel is illustrated at the right. The burning gases rise to the crown sheet which provides a large amount of direct heat absorbing surface. They are then drawn to the rear of the boiler where they pass up into the two outside flue ways through which they travel to the front of the boiler and then back through the two center flue ways the entire length of the boiler.



View of Boiler Base Showing Sturdy Construction and Heavy Slicer Door Liner. Removable Panels in the Base Sides

Hibbard "Classic" BOILER

Guaranteed for Five Years

Any Parts Giving Out Within Five Years Will Be Replaced Free of Charge



Cut-Away View of the 25 Series Hibbard "Classic" Boiler Showing Long Fire Travel and Large Combustion Chamber

Hibbard "Classic" Features

1. Attractive appearance . . . high efficiency . . . quick pickup . . . low fuel cost.
2. Streamlined jacket, insulated thoroughly to prevent heat loss.
3. Convenient grate-shaking mechanism, easily operated.
4. Large size ashpit eliminates the necessity of frequent removal of ashes.
5. The roomy fire box with large coal capacity makes frequent attention unnecessary.
6. Ample space in the fire box insures burning of gases at high temperatures.
7. Long fire travel through six flue ways formed by numerous water tubes insures high operating efficiency.
8. Large fire door makes firing easy and prevents spilling coal. Large flue door exposes flues, making cleaning a simple task.
9. Boiler sections are shipped assembled; the base assembled and crated, making erection an easy job.

It assures long life.

THE STREAMLINED BOILER

Easy to Install : Low Fuel Cost

The new 25 Series Hibbard "Classic" Boiler is truly a deluxe heat machine. The baked enameled jacket and the boiler doors follow the modern trend toward streamlining.

To attractive appearance are added ease of installation, economical operation and thoroughly dependable performance. The forward and back fire travel is illustrated at the right. The burning gases rise to the crown sheet which provides a large amount of direct heat absorbing surface. They are then drawn to the rear of the boiler where they pass up into the two outside flue ways through which they travel to the front of the boiler and then back through the two center flue ways the entire length of the boiler.

Designed by skilled engineers according to the most scientific heating principles. The deep fire box holds a large charge of coal, making frequent attention unnecessary. There is ample space above the coal bed for proper burning of the gases at high temperatures. The double tier of three flue ways formed by water tubes causes the burning gases to travel up and forward and then back the full length of the boiler. The numerous water tubes extract all of the available heat and send it up to the radiators, instead of wasting it up the chimney. The Hibbard "Classic" Boiler, because of its design, has a quick pick-up and gives a lot of heat in a hurry when needed.



Rear View Showing Two-Way Smoke Box and Positive Damper Control

Hibbard "Classic" BOILER

With Five Year Guaranty

"TWENTY-FIVE SERIES"

STANDARD EQUIPMENT

Steam boilers are supplied with Safety Valve, Compound Gauge, Water Gauge and Glass, Try Cocks, Metal Automatic Steam Regulator, Fusible Plug, Metallic Jacket and Insulation and Firing Tools.

Water boilers are supplied with a combined Altitude Gauge, and Thermometer, Metal Automatic Regulator, Metallic Jacket and Insulation, and Firing Tools.

Ratings and Dimensions

STEAM BOILERS				WATER BOILERS		STEAM AND WATER BOILERS								
Nos.	Guaranteed* Load, Sq. Ft. E. D. R.	Commercial Rating, Sq. Ft.	Water Line, In.	Guaranteed* Load, Sq. Ft. E. D. R.	Commercial Rating, Sq. Ft.	Grate Area, Sq. Ft.	Supply Outlets, No. and Size, In.	Return Inlets, No. and Size, In.	Length at Base, In.	Width, In.	Height Overall, In.	Smoke Pipe, In.	Ash Pit Door Opening, In.	Fire Door Opening, In.
525	620	1200	49	990	1950	4.00	2—4	2—4	30½	34½	57	12	9½×17½	9×17
625	775	1500	49	1240	2425	5.02	2—4	2—4	36½	34½	57	12	9½×17½	9×17
725	930	1800	49	1490	2900	6.04	2—4	2—4	42½	34½	57	12	9½×17½	9×17
825	1085	2100	49	1740	3375	7.06	3—4	2—4	48½	34½	57	12	9½×17½	9×17
925	1240	2400	49	1990	3850	8.08	3—4	2—4	54½	34½	57	12	9½×17½	9×17
1025	1395	2700	49	2240	4325	9.10	3—4	2—4	60½	34½	57	16	9½×17½	9×17
1125	1550	3000	49	2490	4800	10.12	4—4	2—4	66½	34½	57	16	9½×17½	9×17
1225	1705	3300	49	2740	5275	11.14	4—4	2—4	72½	34½	57	16	9½×17½	9×17

*Guaranteed loads are based on 12,500 B.T.U. coal with an allowance of 20% for piping. In selecting boiler size it is not necessary to add for normal piping.

Hibbard Classic Jacketed and Unjacketed Boilers

Steam

Boiler No.	Shipping W't, Lbs.	Guaranteed Load, Sq. Ft., E.D.R.	Jacketed, Each	Un-Jacketed Each
F525SD0	2130	620	\$188.25	\$168.95
F625SD0	2420	775	217.85	196.65
F725SD0	2740	930	247.65	224.25
F825SD0	3060	1085	277.35	251.85
F925SD0	3360	1240	307.10	279.45
F1025SD0	3650	1395	334.85	307.25
F1125SD0	3970	1550	354.25	334.75
F1225SD0	4260	1705	383.85	362.35

Water

F525WD0	2130	990	\$188.25	\$168.95
F625WD0	2420	1240	217.85	196.65
F725WD0	2740	1490	247.65	224.25
F825WD0	3060	1740	277.35	251.85
F925WD0	3360	1990	307.10	279.45
F1025WD0	3650	2240	334.85	307.25
F1125WD0	3970	2490	354.25	334.75
F1225WD0	4260	2740	383.85	362.35

Entire Page for Factory Shipment Only

Prices Net F.O.B. Chicago, Add Freight to —

Hibbard OIL BURNING BOILER

With Five Year Guaranty

FOR USE WITH ALL OIL BURNERS

Features

Attractive, two-tone gray enameled streamlined jacket.


Heavy asbestocel insulation, front, back, top and sides.

Large combustion chamber entirely surrounded by water; ample space for complete combustion of oil.

High efficiency, quick pick-up and low fuel cost.

Large front jacket panel, easily removable. Gives ready access to burner and boiler flues.

Long gas travel through six flue ways formed by numerous water tubes.



Oil Burner Not Included



Net loads are based on net cast iron radiation required to properly heat the building. Nothing need be added for normal piping and pickup. For indirect heater add to radiator load 1 sq. ft. per gallon for steam and 2 sq. ft. per gallon for water. If a circulator is used on a water job and the amount of radiation is reduced, use steam net loads in selecting boiler size.

Steam and water boilers are furnished with extended two-tone gray jacket to house the burner. Water boilers are equipped with combination thermometer and altimeter. Steam boilers are equipped with complete steam trimmings and manifold for indirect water heater.

Jacket width—Water boiler 25½ in., steam boiler 28½ in.

Water line 46½ in., overall height 55½ in., floor to crown sheet 34½ in.

STEAM BOILER

No.	Net Load, Sq. Ft.	W't, Lbs.	Overall Length, In.	Each
F0A5SD0	345	1231	49½	\$126.45
F0A6SD0	410	1382	54	141.35
F0A7SD0	475	1529	58½	156.25
F0A8SD0	540	1685	62½	171.25
F0A9SD0	605	1827	66½	184.75
F0A10SD0	670	1972	71	200.85


WATER BOILER

No.	Net Load, Sq. Ft.	W't, Lbs.	Overall Length, In.	Each
F0A5WD0	550	1226	49½	\$121.25
F0A6WD0	655	1376	54	133.95
F0A7WD0	760	1524	58½	146.65
F0A8WD0	865	1680	62½	159.50
F0A9WD0	970	1822	66½	172.25
F0A10WD0	1075	1967	71	184.95

ENTIRE PAGE FACTORY SHIPMENT ONLY

Net F.O.B. Chicago, Add Freight to _____

FREEPORT OIL BURNERS



Approved by hundreds of users and have proven their worth through years of faithful service.

A Quality Product, built to please the most discriminating buyer. Quiet, Efficient, and built of Standard parts.

Compactness and beauty of design has been worked into assembly, and each burner is most attractive.

Aluminum Castings used throughout, highly polished, and with other parts finished in black baked japan, the whole unit will attract attention.

Volume production and the use of Standard parts and castings made in manufacturer's own foundry, machined and polished in their own machine shop and polishing plant, make it possible for us to offer these wonderful burners at these low prices.

High-Pressure Type Most Favorable—Of the large number of burners sold the past five years, the great majority were High Pressure Gun Type; this type unit was accepted because they are quiet, clean, efficient, and free from service demands.

Standard Parts—Are added assurance to your customers and will instill confidence in the product. Freeport parts can be purchased if need be in years to come from a number of well established reliable makers, a satisfaction more desirable than could be expected if the burner were made of special parts.

The Freeport uses Standard parts, mounted on heavy, highly polished aluminum castings.

Motor—Wagner.

Pump—Tuthill or Webster mechanical seal.

Transformer—Webster or Jefferson, 100-10,000 volt 60C.
mid-point ground, non radio interference.

Circuit Breaker—Allen Bradley or Square D.

Valve—Detroit or Webster.

Strainer—Detroit or Webster.

Fan—American Blower.

Nozzle—Apthorp, Nitroil, or Monarch.

Controls—Minneapolis Honeywell or Penn Electric.

Approved by the National Board of Underwriters' Laboratories

SPECIFICATIONS

Including Minneapolis-Honeywell R117 Relay and T11 Acratherm

Fuel cap., gal. per hour.....	1¼ to 2	1¾ to 4
Radiation cap., steam, sq. ft.....	200 to 500	500 to 1200
Radiation cap., hot water, sq. ft.....	350 to 800	800 to 1800
Warm air grate size, in.....	14 to 24	24 to 30
Motor, h.p.	1/10	1/6
Watt consumption	80 to 100	150 to 170
Shipping w't, lbs.....	100	110
Nos.	FD5H0	FD10H0
Each	\$129.50	\$139.50


Installation and Tank Extra

Entire Page for Factory Shipment Only

Prices Net F.O.B. Chicago, Add Freight to _____

The New

Hibbard Automatic



\$175⁰⁰
30 LB. SIZE

The UNDER-FEED PRINCIPLE OF FIRING—The Most Efficient and Economical Method of Firing Warm Air, Hot Water or Steam Boiler Heating Plants.

Automatic heating now comes within the reach of every home owner. **Hibbard** Stokers are even more economical to operate than hand firing for they efficiently burn the cheaper coal screenings. It is half the cost of oil and a quarter the cost of gas heat.

OUR GUARANTEE

To efficiently burn all free burning coal screenings. This means that it will return to you, in the form of useful heat and power, every available ounce of energy contained in your coal.

Abate smoke in conformity with the city smoke ordinance. Complete combustion is attained—no smoke, no soot, no ashes. Automatically maintain the stipulated boiler pressure under present load conditions. It will automatically maintain even temperature where desired, and control boiler pressure under present conditions, with less coal, no trouble, and no waste.


This is our guarantee of service, performance, and economy.

10 DISTINCT OUTSTANDING FEATURES

- 1. HOPPER BASE.** A one piece hopper base of heavy cast iron construction means long life and freedom from rust and corrosion. This hopper base is made long and narrow to eliminate any caking of the coal; therefore eliminating an agitator.
- 2. FEED SCREW.** The feed screw is made of a chrome-nickel alloy steel and is made in one piece to eliminate any differential in the flights.
- 3. AIR DUCT.** The air duct is made of heavy sheet metal.
- 4. CLEANOUT DOOR.** The cleanout door is easily accessible for removing the foreign matter in the fuel. Material which may be forced into the feed tube can easily be removed through this cleanout door.
- 5. WORM TUBE AND WIND BOX.** The worm tube and wind box are made of heavy cast iron. The wind box of this design makes the installation of a stoker very easy.
- 6. RETORT.** The retort is made rectangular and being made this way it reduces the air pressure that is needed to burn the coal (retorts on all stokers of larger size are made this way so if it is essential to have a rectangular retort on a larger job for proper combustion, it surely is essential on a domestic stoker). Bypass in the retort and the wind box eliminates any smoking back.
- 7. TUYERES.** Tuyeres are made in sections (4 corner tuyeres and 16 open tuyeres). This tuyere design is quite different from most stokers. On some domestic stokers, the tuyere or ring are made in one solid piece; the others are made in four pieces; with a setup as this you have plenty of space for expansion and contraction, therefore giving longer life to the tuyere.
- 8. TRANSMISSION.** The transmission is of the agitated type creating a breathing fuel bed.
- 9. MOTOR.** The motor is top mounted and driven with a "V" belt. It has two speeds beside neural.
- 10. FAN HOUSING AND FAN DAMPER.** The fan housing and fan damper are made of heavy cast iron.



THERMOSTAT CONTROL




FEATURES 8-9-10

Thermostatically controlled. Keeps even heat at any desired temperature. Equipped with "Hold Fire" control. Keeps fire from going out in mild weather and eliminates frequent refiring.



Illustration showing construction on sizes over 40 lb. cap. 90 lb. size and larger.

COAL BURNER




Home Model


Nos. F925 and F1025

Low streamlined hoppers. Only 24 in. from the floor. Easily filled. Enable stoker to fit closer to boiler or furnace. Finished in blue with chrome hinge and handle.


Illustration showing construction of 30 and 40 lb. capacity sizes.



FEATURES 5-6-7



FEATURE 2 - FEED SCREW



FEATURE 4 - CLEAN OUT DOOR

Blower housing is of cast iron. Air duct is of 16 gauge stock. Hopper constructed of 16 gauge copper bearing sheet metal and is spot welded.

All stokers equipped with Wagner, 110 volt, A.C. 60 cycle single phase motor, and Mercoid thermostatic controls.

NOTE—If in doubt about the size of stoker required, write us giving make and number of boiler, also size of grate.

Specify Whether Wanted for Hot Water or Steam Boiler or Warm Air Furnace

No.	Coal Feed Per Hour, Lbs.	Hopper Capacity, Lbs.	No. of Speeds	Motor, H.P.	Cap. Steam Radiation, Sq. Ft.	Cap. Water Radiation, Sq. Ft.	Min. Dist. from Tuyeres (Grates) to Heating Surface, in.	Distance from Floor to Tuyeres (Grates), in.	Overall Length, in.	Ship. W't, Lbs.	Each
F925D0	30	300	2	$\frac{3}{4}$	600	1000	16	11	77	478	\$175.00★
F1025D0	40	300	2	$\frac{3}{4}$	875	1400	16	11	77	478	195.00★
F1125D0	50	450	3	$\frac{3}{4}$	875	1400	18	12	78	600	250.00★
F1225D0	60	450	3	$\frac{3}{4}$	1320	2100	20	12	78	600	263.50★
F1275D0	75	450	3	$\frac{3}{4}$	1650	2600	20	12	88	625	285.00★
F1325D0	90	450	3	$\frac{3}{4}$	2000	3200	22	12½	91	825	341.75★
F1425D0	100	650	3	$\frac{3}{4}$	2200	3500	22	15	100	1200	375.00★
F1525D0	125	650	3	$\frac{3}{4}$	2800	4400	22	15	100	1300	491.75★
F1625D0	150	650	3	$\frac{3}{4}$	3300	5250	24	15½	102	1500	566.75★
F1725D0	200	650	3	1	4400	7040	24	15½	102	1700	608.35★
F1825D0	250	650	3	1	5500	8800	26	15½	102	1750	670.00★
F1925D0	350	650	3	1½	7700	12320	36	18	118	2100	746.75★

Prices on Larger Sizes on Application

★Items Marked Thus ★ Are Shipped From Factory Only

Prices Net F.O.B. Chicago, Add Freight to

RADIANT ROUND BOILER



Steam



Water

Thousands of Radiant Round Boilers are rendering satisfactory service to owners throughout the country. Grate dimensions are full size as shown in specifications. Smoke Consumer on all models. Upright lever shaking grates burn all grades of fuel successfully.


Radiant Round Boiler firepots are several inches deeper than many others carrying the same ratings. This insures at least 15% greater heat output. This extra heating surface and the long staggered fire travel makes the Radiant Round Boiler ideal for oil burners. Recommended radiation loads shown below include piping.

Diam. grate, in.....	18	18	20	20	22
Grate area, sq. ft.....	1.77	1.77	2.18	2.18	2.64
Radiation steam, guaranteed load sq. ft.....	275	325	375	425	450
Radiation water, guaranteed load sq. ft.....	450	525	610	690	730
Steam tappings, in.....	2½	2½	3	3	3½
Water tappings, in.....	2½	2½	2½	2½	3
Height to outlet steam, in.....	46	51	52½	57½	53½
Height water line steam, in.....	39½	44½	45½	50½	46½
Height to outlet water, in.....	41½	46½	47½	52½	47½
Smoke pipe, in.....	7	7	8	8	9
Approx. shipping w't, steam, lbs.....	774	872	1010	1135	1135
Approx. shipping w't, water, lbs.....	697	795	883	1008	1012
For Hot Water, Nos.....	F1184WD0	F1185WD0	F1204WD0	F1205WD0	F1224WD0
Each	\$80.00★	87.50★	97.50★	105.00★	105.00★
For Steam, Nos.....	F1184SD0	F1185SD0	F1204SD0	F1205SD0	F1224SD0
Each	\$88.75★	96.75★	108.50★	115.00★	115.00★
Diam. grate, in.....	22	25	25	28	28
Grate area, sq. ft.....	2.64	3.41	3.41	4.27	4.27
Radiation steam, guaranteed load sq. ft.....	500	600	650	750	800
Radiation water, guaranteed load sq. ft.....	810	965	1035	1200	1290
Steam tappings, in.....	3½	3½	3½	4	4
Water tappings, in.....	3	3	3	4	4
Height to outlet steam, in.....	58½	53½	58½	55½	60½
Height water line steam, in.....	51½	47½	52½	48½	53½
Height to outlet water, in.....	52½	47½	42½	50½	55½
Smoke pipe, in.....	9	9	9	10	10
Approx. shipping w't, steam, lbs.....	1303	1329	1517	1757	2019
Approx. shipping w't, water, lbs.....	1180	1206	1390	1560	1822
For Hot Water, Nos.....	F1225WD0	F1254WD0	F1255WD0	F1284WD0	F1285WD0
Each	\$108.50★	126.25★	132.50★	147.75★	154.00★
For Steam, Nos.....	F1225SD0	F1254SD0	F1255SD0	F1284SD0	F1285SD0
Each	\$124.50★	138.75★	146.25★	161.25★	170.00★

*Items Marked Thus ★ Are Shipped from Factory Only

et F.O.B. Chicago, Add Freight to _____

OIL AND STORAGE TANKS




Round Underground Tanks

Welded construction, flanged heads, tested with heavy air pressure and coated with rust resisting paint. Guaranteed oil tight. Threaded openings, one 3½ in. and two 2 in.—or four 2 in. as desired. Graduated gauge stick furnished to measure approximate contents. Built to comply with Underwriters' standard.

No. F21D0

Cap., Gals.	Dim., In.	Thick- ness	Type	W't, Lbs.	Each
110	26×48	16 ga.	Galv.	105	\$24.00★
280	34×72	14 ga.	Galv.	250	37.50★
315	36×72	14 in.	Black	600	39.50★
550	41×95	14 ga.	Galv.	375	46.00★
550	41×95	12 ga.	Galv.	515	53.00★
550	47×74	14 in.	Black	800	52.00★
1000	64×74	14 in.	Black	1200	75.00★
1000	48×132	14 in.	Black	1300	84.50★
1000	46×144	12 ga.	Galv.	780	83.00★
1500	64×108	14 in.	Black	1600	98.00★
1500	47×166	14 in.	Black	2000	116.00★
2000	64×144	14 in.	Black	2110	124.00★
2500	64×180	14 in.	Black	2618	147.00★
3000	64×192	14 in.	Black	3038	171.00★
4000	64×288	14 in.	Black	3882	229.00★
5000	72×288	14 in.	Black	5700	320.00★



Oval Basement Tanks

Welded construction, flanged heads, tested with heavy air pressure and coated with rust resisting paint. Guaranteed oil tight. Built to comply with Underwriters' standard. Cap. 275 gal. size 42×27×66 in., gauge No. 14, w't 220 lbs.

F4D0each \$30.00

If the tank is to be used in connection with a suction pump system it will be necessary to have an extra suction stub bushing and foot valve.

F275D0—Suction stub bushing & foot valve.....each \$12.50

If used in connection with gravity feed system it will be necessary to use a filler cap and a vent fitting.

F276D0—Filler cap and vent fitting.....each \$3.00

Fuel Oil Storage Tank Gauges

EASIEST TO READ—White indicating hand, large 2¼ in. airplane type dial.

SIMPLE TO INSTALL—With an ordinary pipe wrench, when tank is full, partially full or empty. Just insert float mechanism into tank then tighten bushing (which is free of float mechanism) into tank opening. Head mechanism is then placed on top, turned to the desired position and all is locked in place by the hex holddown nut leaving the entire installation permanent and absolutely leakproof.

ACCURATE BECAUSE IT CANNOT STICK—All direct contacts between moving parts. Extra large varnished float, contracted by a phosphor bronze spring that keeps the float constantly at the level of the oil, eliminating the need of ever pounding the tank to drop float.


SIMPLE AND RUGGED IN CONSTRUCTION—Made of heavy steel stamping cannot crack or break. The holddown nut and inner bushing are diecast and assembled into a standard iron bushing. Float arm and rod are of heavy gauge spring stock that will not lose its shape in use or handling. Heavy plated and rustproof. Height above tank only 3½ in.

SIZES—Made to fit all depths of standard around basement tanks, set vertically or horizontally, 2 in. opening.

1521D0each \$1.90


★Items Marked Thus ★ Are Shipped from Factory

Prices Net F.O.B. Chicago, Add Freight to —



Storage Tanks

Guaranteed
r water
working pres-
sure of 65 lbs.,
tested to 100
lbs. hydro-
static pres-
sure. Every
size listed car-
ried in stock.
Tapped for
horizontal or
vertical installation.



A tank with coils should be provided with manhole. If special
enings are required, send sketch showing size and relative
ations.

No. F10D0—Standard

Cap., Gal.	Diam., In.	Length, Ft.	W't, Lbs.	Each
66	20	4	235	\$ 24.68★
85	20	5	280	27.30★
100	24	4	290	28.61★
120	24	5	340	32.03★
140	24	6	390	35.44★
150	30	4	390	37.54★
180	30	5	455	42.00★
200	30	6	520	46.46★
250	30	7	585	50.96★
295	30	8	650	55.39★
365	36	6	650	54.08★
420	36	7	725	59.85★
525	36	8	800	65.63★
630	36	10	950	77.18★
735	42	6	820	72.45★
775	42	7	910	79.80★
825	42	8	1000	87.15★
940	42	10	1180	101.85★
1000	42	12	1360	116.55★
1300	48	14	1540	131.25★
1500	48			
1880	48			
2260	48			

No. F11D0—Extra Heavy

Guaranteed for waterworking pressure of 100 lbs.; tested to
100 lbs. hydrostatic pressure. Every size listed, without exception,
carried in stock. Tapped for horizontal or vertical installation.

A tank with coils should be provided with manhole. If special
enings are required, send sketch showing size and relative
ation.

Cap., Lbs.	Diam., In.	Length, Ft.	W't, Lbs.	Each
20	24	5	350	\$ 35.96★
30	24	6	400	39.38★
40	30	5	470	47.78★
50	30	6	535	52.24★
60	30	7	600	56.70★
75	30	8	665	61.16★
90	36	6	785	69.30★
105	36	7	880	77.18★
120	36	8	975	85.05★
140	36	10	1165	100.80★
160	42	6	990	90.56★
180	42	7	1100	100.01★
200	42	8	1210	109.46★
220	42	10	1430	128.36★
240	42	12	1650	147.28★
260	42	14	1870	166.15★
280	48	8	1435	133.88★
300	48	10	1690	156.45★
320	48	12	1945	179.03★
340	48	14	2200	201.60★
360	48	16	2455	224.18★
380	48	18	2710	246.75★

Pneumatic Pressure Tanks



For home,
farm or fac-
tory water
supply sys-
tems. Guar-
anteed for water
working pres-
sure not ex-
ceeding 75 lbs.,
tested to 125
lbs. hydro-
static pres-
sure.

Prices do not include water gauges and other fittings.
Specify whether for horizontal or vertical installation.

No. F120D0

Cap., Gal.	Diam., In.	Length, Ft.	W't, Lbs.	Each
120	24	5	340	\$ 32.03★
140	24	6	390	35.44★
245	24	10	590	49.09★
220	30	6	535	52.24★
295	30	8	665	61.16★
365	30	10	795	70.09★
315	36	6	675	61.69★
420	36	8	825	73.24★
525	36	10	975	84.79★
630	36	12	1125	96.34★
735	36	14	1275	107.89★
575	42	8	1210	109.46★
720	42	10	1430	128.36★
865	42	12	1650	147.36★
1000	42	14	1870	166.16★
940	48	10	1690	156.45★
1300	48	14	2200	201.60★
1500	48	16	2455	224.21★
1880	48	20	2965	269.33★
2260	48	24	3475	314.48★

Pneumatic Tanks Tapped for Water Gauge

24 in. horizontal tanks, tapped for 12 in. water gauge
30 in. horizontal tanks, tapped for 14 in. water gauge
36 in. horizontal tanks, tapped for 16 in. water gauge
42 in. horizontal tanks, tapped for 20 in. water gauge
48 in. horizontal tanks, tapped for 24 in. water gauge
6 ft. vertical tanks, tapped for 16 in. water gauge

Coils, Manholes, Handholes for All Tanks

Shown on This Page

Regular four-pipe return bend steam coil. Tested to 150 lbs.
hydrostatic pressure for working pressure not exceeding 100 lbs.
For vertical tanks we recommend spiral coils. Prices on appli-
cation.

No. F121D1—Coils

Size of Tank	Size of Coil	Plain Coil Each	Galv. Coil Each
20 in. x 4 ft.	4 pipes 1 in.		
20 in. x 5 ft.	4 pipes 1 in.		
24 in. x 4 ft.	4 pipes 1½ in.		
24 in. x 5 ft.	4 pipes 1½ in.		
24 in. x 6 ft.	4 pipes 1½ in.		
30 in. x 4 ft.	4 pipes 1½ in.		
30 in. x 5 ft.	4 pipes 1½ in.		
30 in. x 6 ft.	4 pipes 1½ in.		
30 in. x 7 ft.	4 pipes 1½ in.		
30 in. x 8 ft.	4 pipes 1½ in.		
36 in. x 6 ft.	4 pipes 1½ in.		
36 in. x 7 ft.	4 pipes 1½ in.		
36 in. x 8 ft.	4 pipes 1½ in.		
36 in. x 10 ft.	4 pipes 1½ in.		
42 in. x 6 ft.	4 pipes 1½ in.		
42 in. x 7 ft.	4 pipes 1½ in.		
42 in. x 8 ft.	4 pipes 1½ in.		
42 in. x 10 ft.	4 pipes 1½ in.		
42 in. x 12 ft.	4 pipes 1½ in.		
42 in. x 14 ft.	4 pipes 1½ in.		

Prices

on

Application

F122D1—Manholes

In Headeach
In Shelleach

F123D1—Handholes

In Headeach
In Shelleach

Entire Page for Factory Shipment Only

Get F.C. Chicago, Add Freight to _____

Hibbard


Steam or Hot Water Radiation

Thoroughly tested to one hundred and twenty pounds hydraulic pressure before shipping and all sections will be replaced by us that are found defective in manufacture or mechanical construction, and customers given credit for said sections when same are returned to us, but no claims for consequential expenses will be allowed. Add 1/2 in. to length for each bushing.

Tappings—1 1/2 in. top and bottom. Bottom bushed for steam or water as per specifications.

Connections—Both steam and water—extra heavy 1 1/2 in. right* and left threaded nipples at top and bottom.


Length—2 1/2 in. per section. W't per sq. ft. 5 1/2 lbs.



Wall Radiation
For Steam and Water


The new and lighter tube style, particularly desirable because it combines push nipple flexibility with the tubular design, making it possible to buy Wall Radiation in exact footage requirements instead of units of 7 feet and 9 feet.

Height, in.	22	29
Length section, in.	2 1/2	2 1/2
No. sq. ft. in section.	1 1/2	1 1/2
Nos.	F22D0	F29D0
Square foot	\$0.42	.40



Three Tube Width 4 3/8 in.				
Height, in.	20	26	32	38
Square feet to section.	1 1/2	2 1/4	3	3 1/2
F3D0square foot	\$0.40	.37	.35	.32
Four Tube Width 6 1/4 in.				
Height, in.	20	26	32	38
Square feet to section.	2 1/4	3 1/4	4 1/4	5
F4D0square foot	\$0.40	.37	.35	.32
Five Tube Width 8 in.				
Height, in.	20	26	32	38
Square feet to section.	2 3/4	3 3/4	4 3/4	5 1/2
F5D0square foot	\$0.40	.38	.37	.35
Six Tube Width 9 1/2 in.				
Height, in.	20	26	32	38
Square feet to section.	3	4	5	6
F6D0square foot	\$0.40	.37	.35	.32
Seven Tube Width 11 1/2 in.				
Height, in.	15	17	20	23
Square feet to section.	2 1/2	3	3 1/2	4 1/2
F7D0square foot	\$0.40	.37	.35	.32

Richvar Convactor Radiation



A Modern Convactor Radiator ... Made of Durable Cast Iron ... For Steam ... Hot Water ... Vapor ... Vacuum ... Or Orifice Vapor Systems. For Recessed or Exposed Installation. Made in 5 in. and 7 1/2 in. widths ... 20 in. high.

Modern in appearance, space saving and efficient—can be used for recessed or free standing installations.

Delivers convected and radiated heat. There are no enclosures to retard circulation of convected heat or hold back radiated heat.

Quick to heat up—slow to cool when the pressure is off the supply line—has the bulk to form a reservoir of heat which prevents the room from chilling.

Throws heat out into the room at an efficient height, away from walls—prevents soiled, streaked walls, curtains and draperies.

Requires no front panel or special enclosure to make it presentable—easy to keep clean and redecorate.

Simple and easy to install—for any type of heating system requiring radiators.

Richvar is particularly adaptable on jobs involving the replacement of recessed radiation which has failed to give satisfactory service. Invariably the same recess opening can be used at considerable saving.

Length per section 2 in., w't per square foot 4 1/2 lbs. The capacity of the 5 in. width is 2.15 square feet per section and of the 7 1/2 in. width 3 square feet per section.

Regular Radiation Without Bottom Grille

F55D0—5 in. width.....	square foot	\$0.50★
F75D0—7 1/2 in. width.....	square foot	\$0.50★

Bottom Grille Only

F85D0	lineal foot	\$0.50★
-------------	-------------	---------

Entire Page for Factory Shipment Only

Streamline Radiator Covers

Combined, practicability with beauty—keeps walls, ceilings and curtains free from dust.




Width 9 3/4 In.

Length closed, in.	14	22 3/4	28
Extended, in.	27	44	54
W't doz., lbs.	36	60	72
Walnut Finish			
Nos.	H927WD0	H944WD0	H954WD0
Each	\$1.00	1.25	1.50

Ivory Finish			
Nos.	H927ID0	H944ID0	H954ID0
Each	\$1.00	1.25	1.50

ONE IN A CARTON



7 3/4 In. Wide Air-Flo Radiator Covers

Length closed 22 3/4 in., length extended 44 in., w't doz. 66 lbs.

N1744WD0—Walnut finish	each \$1.35
N1744ID0—Ivory finish	each 1.35

Extensions for Above

Width 7 3/4 in., length closed 22 in., length extended 44 in., w't doz. 57 lbs.

N1844WD0—Walnut finish	each \$1.25
N1844ID0—Ivory finish	each 1.25

ONE IN A CARTON

9 3/4 In. Wide Air-Flo Radiator Covers

Length closed, in.	14 1/2	22 3/4	28
Extended, in.	27	44	54
W't doz., lbs.	48	72	84

Walnut Finish			
Nos.	H1927WD0	H1944WD0	H1954WD0
Each	\$1.25	1.50	1.75
Ivory Finish			
Nos.	H1927ID0	H1944ID0	H1954ID0
Each	\$1.25	1.50	1.75

Extensions for Above

Width 9 3/4 in., length closed 22 in., length extended 44 in., w't doz. 63 lbs.

N1964WD0—Walnut finish	each \$1.35
N1964ID0—Ivory finish	each 1.35

ONE IN A CARTON

12 3/4 In. Wide Air-Flo Radiator Covers


Length closed 22 3/4 in., length extended 44 in., w't doz. 34 lbs.	
N1244WD0—Walnut finish	each \$1.75
N1244ID0—Ivory finish	each 1.75

Extensions for Above

Width 12 3/4 in., length closed 22 in., length extended 44 in., w't doz. 75 lbs.

N1344WD0—Walnut finish	each \$1.65
N1344ID0—Ivory finish	each 1.65

ONE IN A CARTON




Radiator Cover Brackets

Three brackets required for each cover adds rigidity and security to cover, also supports humidifying pan.

H90D0—Pkg. of 1/2 dz,	
each	\$0.35

* Marked Thus ★ Are Shipped from Factory Only

Art Metal Radiator Covers



Very fine construction being made of heavy furniture steel, finished in five coats of baked enamel in any wood-grain or solid color desired, has a built-in humidifier, is of welded construction throughout, has special designed grille-work which has 65% free opening, and also has grille-work in the top panel to prevent any heat pockets being formed. Specify finish and size, in measuring length include valve.


F400D0—Height 14 to 27 in. inclusive.

Length, in.	Each
12 to 26.....	\$12.75★
26 to 36.....	15.00★
36 to 48.....	17.25★
48 to 60.....	19.25★
60 to 72.....	20.50★
72 to 84.....	22.00★
84 to 96.....	24.25★
96 to 108.....	27.00★

F500D0—Height 27 to 38 in. inclusive.

Length, in.	Each
12 to 26.....	\$14.00★
26 to 36.....	17.25★
36 to 48.....	19.25★
48 to 60.....	20.50★
60 to 72.....	24.75★
72 to 84.....	27.00★
84 to 96.....	33.25★
96 to 108.....	37.25★

Humidifying Pans




Affords healthful moist heat. One quart capacity, easy to fill without removing radiator cover. For use with Nos. 927, 1927 and 1244 series only.

H91WD0—Walnut finish.	
Pkg. of 1/2 dz *	each \$0.50
H91ID0—Ivory finish.	
Pkg. of 1/2 dz *	each .50

Increase Fireplace Efficiency 500% with the Smokeless MAJESTIC "SPECIAL" CIRCULATOR FIREPLACE



 A match furnishes heat but you wouldn't try to keep warm with a match. Yet most fireplaces operate on the same inefficient principle of heat distribution. A bonfire is another example of gross heating inefficiency . . . just like the fireplaces that depend entirely upon the direct radiation of heat from burning fuel as a method of heat distribution. A frozen back and roasted face are the results of such heating methods.




An entirely prefabricated steel fireplace. Unit is adaptable to any mantle design. For use with basket grate or andirons. For burning coal or wood or gas logs. Damper is built in . . . Cannot smoke. Circulates heat like a modern furnace. Can be installed in old fireplaces by removing present face, setting unit in place and rebuilding face.

Easily installed by any mason. Saves from \$15.00 to \$25.00 in materials and labor.

Furnishes all heat necessary in cottages, cabins or small homes. Provides a means of utilizing the heat that went up the flue in the old fashioned fireplace by pulling the cool air in through the bottom openings, over the back and sides of the fire chamber and then discharging it through the openings on the top of the unit, just like a modern furnace.

The Majestic circulator fireplace both circulates and radiates heat. Grille openings can be placed anywhere. Operating economies make it a profitable investment.

Will give a lifetime of service and satisfaction. Firebox constructed of heavy steel, $\frac{3}{16}$ in. thick. Being electrically welded, welds are even stronger than the grates themselves.



No.	Finished Opening Wide, In.	High, In.	Flue Connection, In.	Room Cap., Cu. Ft.	Grilles Needed for Warm and Cold Air	Ship. Wt Lbs.	Each
H280D0	28	26	8½×13	3200	4—8×5	250	\$27.90
H340D0	34	28	8½×13	3800	4—8×8	270	32.85
H400D0	40	30	13×13	4500	4—8×10	310	41.70
H460D0	46	32	13×13	5200	4—10×10	440	70.50
H520D0	52	34	13×18	6000	4—10×12	510	79.50

Majestic special circulator fireplaces are shipped complete with mineral wool and full installation directions.

More Detailed Information About Construction or Installation Will Be Furnished On Request

GRILLES FOR MAJESTIC "SPECIAL" AND "MASTER" FIREPLACES



No. F1D0
Fish Scale



No. F2D0
Colonial



No. F3D0
Sanitary

Bronze Finish

Specify Sizes and No. when Ordering


Size	Ship. Wt, Lbs.	Each
8×5	4	\$1.35★
8×8	6	1.50★
8×10	8	1.60★
10×10	9	65+
10×12		

★Items Marked Thus ★ Are Shipped From To

MAJESTIC "MASTER" CIRCULATOR FIREPLACE

W
I
T
H


Radiant
BLADES



**HAS 91% MORE HEATING
SURFACE AND 30% MORE
EFFICIENCY THAN THE
SPECIAL**

To get the maximum area of heated surface, thus generating the maximum amount of heated air, Majestic engineers have used "Radiant Blades" which are solidly welded to the firebox. These radiant blades give approximately 91% more heat generating surface, and, naturally, a proportionate increase of warm air to be distributed to your rooms.

More Detailed Information About Construction or
Installation Will Be Furnished on Request.



No.
H028D0
H034D0
H040D0
H046D0
H052D0

Room
Cap. in
Cu. Ft.
4060
5040
6025
7000
7990

Flue
Conne-
ction,
In.
8½×13
8½×13
13×13
13×13
13×18

Ship.
W't
370
420
510
590
656

Each
with
Cas-
ing
\$36.85
46.20
63.00
86.00
102.00

See Page 882C for Prices on Grilles.

To figure room capacity multiply the length of the room in feet by the width, then multiply this amount by the height of the ceiling.


Details of Dimensions of Majestic Circulator Fireplace

NOTE

Dimensions shown in this table are actual measurements of the fireplace circulator. Be sure and allow ¾ in. all around for insulating pad.

Full directions for installation are attached to each circulator at the factory.

THE CASING IS COVERED WITH MINERAL WOOL WHICH FILLS IN BETWEEN THE CASING AND THE SURROUNDING MASONRY. THE OUTSIDE COLD AIR DUCT IS OPTIONAL-IF IT IS USED, OUR 16"×8" ADJUSTABLE FOUNDATION GRATE WITH BRONZE SCREEN SHOULD BE INSTALLED AS SHOWN




DIMENSIONS, IN INCHES:

NOTE: SPACE **MUST** BE LEFT BETWEEN THE CIRCULATOR CASING AND SURROUNDING MASONRY, AT LEAST ¾" ALL AROUND THE SIDES AND 1" AT THE TOP.

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	N	O	P
28	28	20	26	8	12	8	16	50	15	19	4	36	34	15	46
34	34	25	28	8	12	8	19	55	16	20	4	42	36	16	51
40	40	31	30	8	12	12	22	60	17	21	4	48	38	17	56
46	46	36	36	8	12	12	25	65	18	22	4	54	40	18	61
52	52	42	42	8	12	12	27	69	19	24	4	60	42	19	65

Grilles Needed
for Warm and
Cold Air


4—8×5
4—8×8
4—8×10
4—10×10
4—10×12



Mark "O" Inclusive Are Common to Both "Master" and "Special" Units

et F.C. C. Chicago, Add Freight to

Register Shields

Floor
Register
ShieldWall
Register
Shield

Adjustable

For Warm Air Furnace Registers

Made adjustable to fit all sizes of Floor and Wall Registers from 10 to 19 in.

Will deflect warm air out into room along floor instead of allowing heat to go directly to ceiling.

Of neat appearance. Not easily marred or scratched. Made of heavy gauge steel and constructed without the solder, screws or bolts.

Floor Register Shield, wt per doz. 38 lbs.

D325D0—Walnut grained finish,
each\$1.45

D125D0—Gloss black finish,
each\$1.00

Wall Register Shield, w't per doz. 10 lbs.

D315D0—Walnut grained finish,
each\$0.75

D126D0—Gloss black finish,
each\$0.60

PACKED HALF DOZEN

Round Stove Pipe Registers
and Faces

Cast iron, to fit 6 in. stove pipe, w't each 9 lbs.

Black Registers, Less Faces

D6D0each \$2.50


White Faces

D66D0each \$2.25

Register Shields with
Humidifying Pan

For use in homes with hot air furnaces. Gives the same protection to the interior of the home that the radiator cabinet gives the steam or hot water heated homes. Installed in thirty seconds by simply loosening two screws on register face. It humidifies, catches dirt, saves cleaning and causes wider heat circulation. It is attractive, inexpensive and does not wear out.


Made of heavy steel. Galvanized water container. Length overall 15 in. W't doz. 15 lbs.



Wall Type

D155D0—Black japanned finish,
each\$0.45

D0155D0—Oxidized copper finish,
each\$0.50



Floor Type

D255D0—Black japanned finish,
each\$0.50

D0255D0—Oxidized copper finish,
each\$0.55

Wood Register Faces




For cold air ducts,
4x1 1/2 in. oak strips,
1/2 in. cross strips, glued
in. grooves, meshes 3/4x1 1/2
in.

No. D123D0

Size, in.	Each	Size, in.	Each
12x20	\$1.66	16x30	\$3.34
12x30	2.50	20x24	3.33
14x20	1.94	20x30	4.15
16x20	2.22	24x30	5.00
16x24	2.67		

Adjustable Registers or
Ventilators

Auer—Style "X"
H & C—Style 2250



Telescoping Boxes. All steel black floor register with valves, white ceiling plate. Two sheet metal boxes which telescope within each other, taking but little more than half the space for stock.


Installation is made quickly by one man from the floor of the room above.

Both the black japanned floor register and the white japanned ceiling face are of wrought steel.

Size table telescoped approximately 4 in. high, adjustable to fit ceilings from 5 to 11 in. in depth.

Size, in.	8x10	8x12	9x12
W't, lbs.	7	8	8 1/2
Pkg. of 3 *	H810D0	H812D0	H912D0
Each	\$2.25	2.75	2.85
Size, in.	10x12	10x14	12x14
W't, lbs.	8 1/2	10	12
Pkg. of 3 *	H1012D0	H1014D0	H1214D0
Each	\$3.50	4.75	5.00

ONE IN A CARTON

Adjustable Smoke Pipe
Registers or Ventilators


Can be used either as a smoke pipe register or an adjustable ventilator. Consists of a black floor register with valves and a white ceiling plate, both of which have opening in center for a 6 in. smoke pipe. Supplied with removable center pieces to close smoke pipe openings, which make this an adjustable ventilator performing the same service as the regular pattern, viz., allowing the surplus heat to pass from a lower room to an upper one.

Combination Pattern


Size, in.	8x10	10x12
W't, lbs.	9	9
	H12	

AIR CONDITIONING REGISTERS AND REGISTER FACES

Wall Registers and Faces




No. P2030D




No. P2043D

Baseboard Registers and Faces



No. P2056D



No. P2075D

Furnished in Grey Prime Coat

Refined and inconspicuous, vertical bars avert dust lodging, arrow mesh diffuses air, installed after plastering, face extends over plaster, detachable frame fastens into stack head, register screwed to frame.

Size, In.	For Warm Air Register, with Valve and Band Frame		For Cold Air Face, with Band Frame (No Valve)		For Forced Air Face only, With- out Valve or Frame	
	No.	Each	No.	Each	No.	Each
3x6.....	P2030D0	\$1.45	P2043D0	\$0.90	P2005D0	\$0.70
4x4.....	P2031D0	1.35	P2044D0	.85	P2006D0	.65
4x5.....	P2032D0	1.45	P2045D0	.90	P2007D0	.70
4x6.....	P2033D0	1.45	P2046D0	.90	P2008D0	.70
4x8.....	P2034D0	1.65	P2047D0	1.05	P2009D0	.80
6x4.....	P2035D0	1.45	P2048D0	.90	P2010D0	.70
6x6.....	P2036D0	1.60	P2049D0	1.00	P2011D0	.75
6x8.....	P2037D0	1.65	P2050D0	1.05	P2012D0	.80
8x8.....	P2038D0	1.75	P2051D0	1.10	P2013D0	.85
10x4.....	P2039D0	1.75	P2052D0	.90	P2014D0	.70
10x5.....	P2040D0	1.75	P2053D0	1.05	P2015D0	.80
10x6.....	P2041D0	1.75			P2016D0	.85
10x8.....	P2042D0	1.75			P2017D0	.90

Furnished in Grey Prime Coat

Finish flush with baseboard. Have $\frac{3}{8}$ in. flange turned back on top and two ends. Fit into baseboard and make a snug fit across the top. 14 and 30 in. lengths fit the standard space between two studdings.

Size, In.	For Warm Air Register, with Valve and Frame		For Cold Air Face, with Frame (No Valve)	
	No.	Each	No.	Each
8x6.....	P2056D0	\$1.60	P2075D0	\$1.05
10x4.....	P2057D0	1.50	P2076D0	1.00
10x5.....	P2058D0	1.60	P2077D0	1.05
10x6.....	P2059D0	1.65	P2078D0	1.10
10x8.....	P2060D0	1.80	P2079D0	1.20
12x4.....	P2061D0	1.60	P2080D0	1.05
12x5.....	P2062D0	1.75	P2081D0	1.15
12x6.....	P2063D0	1.80	P2082D0	1.20
12x8.....	P2064D0	1.95	P2083D0	1.30
14x4.....	P2065D0	1.65	P2084D0	1.10
14x5.....	P2066D0	1.80	P2085D0	1.20
14x6.....	P2067D0	1.95	P2086D0	1.30
14x8.....	P2068D0	2.10	P2087D0	1.40
24x5.....	P2069D0	2.40	P2088D0	1.60
24x6.....	P2070D0	2.85	P2089D0	1.90
30x4.....	P2071D0	2.80	P2090D0	1.85
30x5.....	P2072D0	3.00	P2091D0	2.00
30x6.....	P2073D0	3.45	P2092D0	2.30
30x8.....	P2074D0	3.90	P2093D0	2.60

All Steel Floor Registers and Faces

Auer Registers—Style "O"

H & C Registers, Style 200

Auer Faces, Style "H"

H & C Faces, Style 250

All Steel Registers for floor, wall or ceiling use. For floor use these registers are reinforced with heavy steel supporting bars. Faces are embossed and "crimped" downward to provide strength and have 80% air opening.

BLACK JAPANNED

Registers			Faces			WHITE JAPANNED			GOLDEN OAK		
Opening, In.	Nos.	Each	Nos.	Each		Nos.	Each		Nos.	Each	
6x8	D500D1	\$1.55	D550D1	\$0.90		P650D1	\$1.00		P700D1	\$1.65	
8x8	D501D1	1.60	D551D1	1.00		P651D1	1.10		P701D1	1.70	
8x10	D502D1	1.70	D552D1	1.10		D652D1	1.25		D702D1	1.85	
8x12	D503D1	1.90	P553D1	1.30		P653D1	1.45		P703D1	2.05	
9x12	D504D1	2.15	D554D1	1.50		D654D1	1.70		D704D1	2.35	
10x12	D506D1	2.40	D556D1	1.70		D656D1	1.90		D706D1	2.60	
10x14	D507D1	3.40	D557D1	2.00		D657D1	2.25		P707D1	3.65	
12x14	D508D1	4.25	D558D1	2.50		D658D1	2.80		D708D1	4.55	


Any of above registers can be used as ventilators by adding a pulley and when placed in wall or ceiling above easy reach they can be operated by means of chain or cord. Registers so equipped must be picked up from Chicago factory.

Pulleys for Ventilators 75 cents extra.

Indicator Handles, one "open," one "closed," and 10 feet of cord.


P10D1

Steel Cold Air Faces



Back View

Front View



Auer—Style "R"

H & C—Style 255

Made of high quality plating steel, durable and non-breakable. To provide maximum air opening fretwork is oblong mesh.


Grille work formed semi-tubular which engages and holds reinforcing bars in a fixed position, these bars providing ample strength for floor use.

A sturdy frame is welded around four sides to under side of face, which extends into floor opening, holding it in a positive position without being fastened down and causes it to lie perfectly straight and hides edges of flooring.

Oak finish has two coats of Oak enamel and a preserving coat of special Varnish, each baked on separately and is nearest standard for various floors.

Opening, For Pipe, BLACK JAPANNED				OAK FINISH			
In.	In.	Nos.	Each	Nos.	Each		
12x14	12	D302D1	\$2.50	D402D1	\$2.80		
10x24	14	P306D1	3.40	D406D1	3.80		
12x24	16	D308D1	3.75	D408D1	4.20		
14x24	18	P310D1	4.10	D410D1	4.60		
6x30	13	P312D1	3.40	D412D1	3.80		
8x30	14	D314D1	3.60	D414D1	4.05		
10x30	16	D316D1	3.75	D416D1	4.20		
12x30	18	D318D1	4.00	D418D1	4.50		
14x30	20	D320D1	4.60	D420D1	5.15		
16x30	21	D321D1	5.50	D422D1	6.15		
18x30	22	P324D1	6.10	D424D1	6.85		

Steel Base Board Registers



Where air opening is the main factor this register affords all the air opening or full area attainable in a register face, namely 80%.

Bars are formed semi-tubular making the face sturdy. Positive valve adjustment which holds the valve at any required angle, is incorporated.

Opening, Base Ext., For Pipe,			BLACK JAPANNED		WHITE JAPANNED	
In.	In.	In.	Nos.	Each	Nos.	Each
8x10	2 1/2	8	D906D1	\$2.00	P1006D1	\$2.35
8x12	2 1/2	9	D907D1	2.40	P1007D1	2.90
9x12	2 1/2	10	D908D1	3.00	P1008D1	3.50
11x13	4	12	D910D1	4.50	P1010D1	5.25

CONSULT US ANY TIME.

YOU'RE ALWAYS WELCOME . . . NEVER

UNDER OBLIGATION


Majestic Built-In Milk and Package Receiver



Consists of two cast steel frames and doors. Connected by steel body. Opening 12 in. high and 14 in. wide is required for installation. Automatic theft proof compartment on which both doors may be locked and unlocked from the inside only.

For wall thickness,			
in.	5 to 8	8 to 14	14 to 22
W't each, lbs.	36	40	45
Nos.	F1D0	F2D0	F3D0
Each	\$9.50★	9.75★	10.75★

Majestic Access Units




For easy access to plumbing, steam pipes, wiring, etc. Above illustration shows a Majestic Access Unit installed. Note substantial locking device which holds door flush with frame when closed. Frames are made of 18 gauge and doors of 1/2 inch Stretcher Levelled Steel. Corners are strongly reinforced, and door locks firmly in place.

No.	Panel Size, In.	Wall Opening, In.	W't Lbs.	Each
F100D0	7 1/2 x 11	8 x 11 1/2	6	\$4.50★
F105D0	12 1/2 x 16 1/2	H 7	10	6.20★
F200D0	14 1/2 x 18 1/2	H 14	14	7.00★
F300D0	19 1/2 x 24 1/2	H 22	22	9.00★

Majestic Coal Chutes

Bodies Have Certified Malleable Iron Frames, Doors and Hinges and Copper Steel Bodies Reinforced with Angle Iron.



Open

Closed

Residence Size

Wall Opening 23 In. Wide, 18 In. High, 12 In. Deep

H10MAD0—With 1/2 in. wire glass pannel—copper steel hopper, w't each 63 lbs., each\$13.60

H101MBD0—Copper steel door and hopper, w't each 52 lbs.each \$10.70

F10MCD0—With 1/2 in. wire glass panel—no hopper, w't each 52 lbs., each\$12.30★

F101MDD0—Copper steel door, no hopper, w't each 41 lbs.each \$9.35★

For 8-inch basement walls. Have 9 in. straight bottom bodies. No hoppers. No chains to the gravity latch 23 in. wide, 17 in. high, 9 in. deep.

F500MD0—Malleable iron frame and hinges, pressed copper steel door, w't each 35 lbs.each \$8.00★

F600MD0—Glass panel door, w't each 47 lbs.each \$11.10★

School House Size

Wall Opening 32 In. Wide, 22 In. High, 17 In. Deep

F20MAD0—With 1/2 in. wire glass panel, steel hopper, chain on gravity latch, w't each 129 lbs.each \$24.00★

F20MCD0—With 1/2 in. wire glass panel, no hopper, w't each 108 lbs., each\$21.60★

F203MBD0—Copper steel door, with hopper, w't each 105 lbs., each\$21.35★

F203MDD0—Copper steel door, no hopper, w't each 84 lbs., each\$19.00★


For 12 In. Walls—No Chains to Gravity Latch Type

F520MD0—Copper steel door, no hopper, w't each 70 lbs.each \$16.00★

F620MD0—Glass panel no hoppr, w't each 94 lbs.each \$20.30★

★ Are Shipped from Factory Only


Majestic Grade Line Chutes



Hopper and body are of Keystone Copper Steel, and the body is reinforced with heavy angle iron. The Majestic is equipped with a springless, positive, automatic latch, operated by inside chain. Construction is absolutely watertight. The frame is provided with water drainage groove under edge of door.

Door opening, in.	23 1/2 x 18 1/2	29 x 24
Rough wall opening, in.	25 x 25	31 x 31
Shipping w't, lbs.	135	218
Nos.	F16D0	F18D0
Each	\$34.65★	50.30★

Hibbard Coal Door



Wall opening 24x17x9 in. Solid steel door, malleable hinges, automatic lock, no hopper, w't 43 lbs.

H50D0each \$6.45


Ash Pit Doors



The doors are made of the best iron for this purpose, strong, smooth, well fitted and japanned. They are used for ash pits in dwellings, stores, etc., where necessary to keep pits securely closed.

Size, in.	8x8	8x10	10x12
W't doz., lbs.	113	122	157
Nos.	M10D9	M11D9	M12D0
Each	\$0.95	1.00	1.50

Ash Dumps




Door fastened in frame, cannot drop out. Dumped with a poker.

Cast iron. Outside measurements 7x10, door 5x8, w't doz. 36 lbs.

D8D0each \$0.75

Furnace Check Dampers



Cast iron, black lacquer finish. Reversible for Vertical or Horizontal Smoke Pipe.


For pipe, in. 5 and 6 7 and 8 9 and 10

W't each, lbs. 23 3 3½

Nos. **D153D9 D3D9 D13D9**

Each \$1.00 1.00 1.00

**Cast
Iron
Black
Lacquered
Finish**




For pipe, in. . 6 7 8 9
W't each, lbs. 5 7 8 10

D1D0...each \$1.35 1.80 2.15 2.35

End Check Only

For pipe, in. . 6 7 8 9
W't each, lbs. 3 4 5 5½


D2D9...each \$1.10 1.35 1.80 2.00



**Cast
Iron
Black
Lacquered
Finish**

For pipe, in. 8 9
Size of opening, in. 9x3½ 10x4
W't each, lbs. 3 3½
D4D9 \$1.10 1.10

Adams 2-in-1 Dome Dampers




Worm gear operation

Underslung operation

Size, Front, in.	Size, Back, in.	Depth, in.	Throat Opening, in.	W't Each, lbs.
24	15½	11½	18x8	21
30	21½	11½	24x8	27
36	27	11½	30x8	30
42	33	11½	36x8	39
48	39	11½	41x8	41

Foundation Grates



Cast iron, japanned.

For any place where ventilation is necessary.

Size, in.	6x8	8x8	6x12
W't, doz. lbs.	15	26	28
Nos. H680D0 H880D0 H6120D0			
Each \$0.25	.30	.35	

Size, in.	8x10	8x12
W't per doz., lbs.	30	31
Nos. H8100D0 H8120D9		
Each \$0.35	.45	

Size, in.	8x16	10x12
W't per doz., lbs.	42	40
Nos. H8160D9 H10120D9		
Each \$0.60	.70	

PACKED ONE DOZEN

Steel Coal Chutes

Made of 18 gauge, galvanized steel, reinforced by a framework of angle iron. 18 in. wide at head end, 17 in. wide at bottom end. 4 in. high at head end, 3½ in. high at bottom end.

Length, ft. . .	8	10	12
W't, lbs.	52	65	76
Nos. F508D0 F510D0 F512D0			
Each \$9.30	12.50	14.70	

Made to serve either worm gear or underslung installations. Equipped with both geared mechanism and ratchet mechanism. Dampers set up for worm mechanism installations. To change to ratchet operation remove rod with worm and attach ratchet bracket.


An outstanding feature is the segment gear which controls opening and closing of lid. Movement of segment gear controlled by worm which is self locking and makes possible opening and closing of damper lid to any desired point.

Lid hinged in back and fastened to body with cotter pins which eliminates possibility of lid slipping out of place.


Majestic Built-In Garbage Receivers

Removes unsightly garbage can from rear porch and puts it in the wall, out of sight, odorless, at hand in a convenient place.

Adapts itself to a wide range of installations. May be installed to open inside the kitchen, to open on an outside porch. Consists of a heavy cast iron frame and air tight door, a copper steel body that recesses in the wall, and a garbage can. The garbage pail rests on a cast iron shelf which is fastened to the door. When the door is opened, the can swings out in position to receive garbage.



Can capacity, gal.	4	5
Wall opening, in.	14½x12	14½x16
W't each, lbs.	36	50
Nos. F4D0 F5D0		
Each \$7.00★	11.20★	
Can capacity, gal.	7	9
Wall opening, in.	14½x16½	19x29
W't each, lbs.	50	115
Nos. F7D0 F9D0		
Each \$11.20★	25.55★	



★Items Marked Thus ★ Are Shipped free


Prices Net F.O.B. Chicago, Add Freight

How to select WATER SYSTEMS

Small Home Requirements


225 - - 250
Gal. Pump

8-15-20-42
Gallon Tanks



Filling Stations
Barbecue Stands
Restaurants
Stores
Trailers
Summer Resort Cabins

SMALL HOMES • 1 BATHROOM



Medium Sized Home Requirements

MEDIUM SIZED HOMES • 2 BATHROOMS

350 Gal. Pump

42-82-120
Gallon Tanks



Taverns
Farm Residences
Railroad and Bus
Stations
Small Camps
Small Schools
Dairies
Churches



Large Home Requirements

LARGE HOMES • 4 BATHROOMS

Large Farms and Barnyards
Small Hotels
Medium Sized Schools
Airports
Tourist Camps
Small Factories
Small Air Conditioning Jobs

500 Gal. Pump

42-120-220-315
Gallon Tanks



Mar. 1909

F.C. & F.

Red Jacket SHALLOW WELL WATER SYSTEMS

Select from these three outstanding Lines

RED JACKET offers a wide selection of models and sizes in three distinctive priced lines. Each of these three lines is well-known for its many exclusive Red Jacket design features which make it an outstanding pump value and assure maximum operating economy with minimum attention.


Select from these three Red Jacket lines with confidence. Designs of all Red Jacket Pumps, Units and Water Systems have been originated and developed by engineers with a lifetime of experience.

Rigid material standards, skillful manufacturing and severe testing all combine to produce what you most desire—dependable, economical automatic water supply.

"SCOUT" LINE

LOW COMPETITIVE PRICE GROUP


The "Scout" Line of 225 gallon, oil lubricated Red Jacket Water Systems is a small, economical unit with all the ruggedness and endurance of larger capacity Red Jacket Pumping Units. It is unequalled for simplicity of construction. Employing a one-piece piston rod that is rigidly mounted and permanently aligned, they are world famous for their economical and trouble-free performance.



"WARRIOR" LINE

COMPETITIVE PRICE GROUP


The "Warrior" Line of 250 gallon Red Jacket Water Systems has the exclusive feature of being water lubricated. They do not require oiling at any time. These units employ the same principle used on propeller shafts of largest ocean liners. Requires only absolute minimum of attention. Highly favored for dependable operation and attractive low cost.



"CHIEF" LINE

STANDARD PRICE GROUP


The "Chief" Line includes 250, 350 and 500 gallon capacity Red Jacket Water Systems. They are all oil lubricated and employ the most advanced principles of power pumping. Castings are extra heavy, as are power frame, shafting and bush bearings. Best quality materials used throughout. The pumping unit is fitted with the finest accessory equipment obtainable for extremely hard service at the




RED JACKET "SCOUT" WATER SYSTEMS

FOR SMALL HOMES

225 Gallons per Hour—Oil Lubricated—22 Ft. Suction



No. T48D



No. F48GD

Pumping Unit with Gasoline Engine Less Tank

Includes $\frac{1}{2}$ H. P., 4 Cycle, Single Cylinder, Air Cooled, High Speed Gasoline Engine, V-Belt Self Aligning Drive, Combination Cast Iron Sub-base for Pump and Engine, and Relief Valve. Arranged for hand start and automatic cut-off.

Pumping Unit with Electric Motor Less Tank

Recommended for the small home, summer cottage, filling station and refreshment stand. They provide a small capacity water supply at extremely low cost. The "Little Scout" has an outstanding and unique power end with fewer operating parts than any other reciprocating pump. Ruggedly built, it insures trouble-free, quiet performance throughout its unusually long service life. Maximum working pressure up to 35 lbs.

Complete Electric Water Systems With Tank

Includes Pumping Unit, Relief Valve, Pressure Switch, Pressure Gauge, Air Control, Galvanized Steel Pneumatic Storage Tank, and fittings between tank and pump.

How to Select the Right Size Tank

These Water Systems can be furnished with an 8, 15, 42, or 120-gallon storage tank. Any of these combinations will take care of one bathroom home or equivalent. The larger the storage tank, the less often the pumping unit starts and stops, which results in lower operating cost. Larger tanks provide more reserve storage for large sudden withdrawals.

Repair Kit

Contains cup leathers, valve rubbers, valve springs, cotter keys, air snifter core and complete set of gaskets.



622Deach \$1.65


SPECIFICATIONS

H. P. Capacitor—110 Volt, 60 Cycle, A. C. Motor—Cylinder Bore $1\frac{1}{8}$ in.—Stroke $1\frac{1}{8}$ in. Suction $\frac{3}{4}$ in.—Discharge $\frac{1}{2}$ in.

No.	Description	Size Tank, Gal.	Overall Size, In.	Ship. Wt., Lbs.	Each
48D0	Pumping Unit with Motor	...	18×10×17	79	\$47.00
488D0	Complete Water System	8	18×30×30	100	53.15
481D0	Complete Water System	15	18×33×33	127	57.70
484D0	Complete Water System	42	18×33×51	181	66.00
412D0	Complete Water System	120	25×41×65	289	89.10
412D0	Complete Water System	120	25×21×18	116	78.45★

★ Are Shipped from Factory Only

et F.C. Chicago, Add Freight to



No. T484D

8-gallon storage tank system for limited service, furnished less pressure gauge.

15-gallon storage tank system for small homes with minimum water requirements.



42-gallon storage tank. Most practical size for average family home with one bathroom.

120-gallon galvanized storage tank handles unusual water demands and decreases operating costs.

RED JACKET "WARRIOR" WATER SYSTEM

FOR SMALL HOMES

250 Gallons per Hour—Water Lubricated—22-Foot Suction Lift



Pumping Unit with Electric Motor, Less Tank

The most popular unit in the entire Red Jacket line. The only water lubricated pumping unit of its kind made.

Its dependability and endurance have been thoroughly tested and proven. Thousands are in use throughout the country.

SPECIFICATIONS

1/4 H. P. Capacitor; 110 Volt, 60 Cycle A. C. Motor. Cylinder bore 1 1/2 in. stroke 1 1/2 in. suction and discharge 3/4 in., maximum working pressure 40 lbs. per square inch. Shipping w't 100 lbs.

T500D0each \$49.50

Complete Horizontal Tank Water Systems

This completely assembled "Warrior" water system with pneumatic storage tank includes pumping unit, relief valve, pressure switch, pressure gauge, automatic air control, galvanized steel storage tank. These units are the most popular in the Red Jacket line. They are designed to meet the needs of the average home, roadside filling station and rural store. Its dependability and endurance have been thoroughly tested and proven through thousands of installations.

SPECIFICATIONS

1/4 H. P. Capacitor; 110 Volt, 60 Cycle A. C. Motor. Cylinder bore 1 1/2 in., stroke 1 1/2 in., suction and discharge, 3/4 in. maximum working pressure 40 lbs. per square inch.

Nos.	Capacity, Gal.	Overall Size, In.	Shipping W't Lbs.	Each
T508D0	8	26x12x24	138	\$56.75
T502D0	20	34x14x28	171	61.30




Prices Net F.O.B. Chicago, Add Freight

RED JACKET "WARRIOR" WATER SYSTEM

FOR SMALL HOMES


250 Gallons per Hour—Water Lubricated—22-Foot Suction Lift



No. T501D

Fresh Water System

Fresh Water System with 1½ gallon cushion tank for continuous service, irrigation, construction work, etc.



No. F500GD

Pumping Unit with Gasoline Engine

Includes ½ H.P., 4-cycle, single cylinder, air-cooled, high speed gasoline engine, V-belt, self aligning drive, combination cast iron sub-base for pump and engine, and relief valve.



No. T504D

Complete Electric Water Systems

Includes pumping unit, relief valve, pressure switch, pressure gauge, air control, galvanized steel pneumatic storage tank, and fittings between tank and pump.

How to Select Right Size Tank

This water system can be furnished with an 8, 15, 20, 42 or 120 gallon storage tank. Any of these combinations will take care of a one bathroom home or equivalent. The larger the storage tank the less often the pumping unit starts and stops which results in lower operating cost. Larger tanks provide more reserve storage for large sudden withdrawals.

SPECIFICATIONS

½ H.P. Capacitor 110 V. 60 Cycle A.C. Motor. Cylinder bore 1½ in. Stroke 1½ in.
Suction ¾ in. Discharge ¾ in.

No.		Size Tank, Gal.	Overall Size, In.	Ship. W't, Lbs.	Each
501D0	Complete Water System	1½	24×15×22	113	\$51.75
505D0	Complete Water System	15	26×26×33	148	60.20
504D0	Complete Water System	42	26×30×51	202	68.50
5012D0	Complete Water System	120	26×38×65	310	91.60

½ H.P. Gasoline Engine—4 Cycle—Air Cooled—Foot Starter

No.		Size Tank, Gal. Less Tank	Overall Size, In.	Ship. W't, Lbs.	Each
500GD0	Pumping Unit with Engine		22×25×22	145	\$80.60★
501GD0	Complete Water System		26×46×51	247	107.10★
			26×46×65	355	130.20★

Thus ★ Are Shipped from Factory Only



Repair Kit


Contains cup leathers, valve rubbers, valve springs, cotter keys, air snifter core and complete set of gaskets.

622D0each \$1.65

RED JACKET "CHIEF" WATER SYSTEMS

FOR SMALL HOMES

250 Gallons per Hour—Oil Lubricated—22-Foot Suction Lift




No. F510GD

Vertical Tank Gasoline Water Systems

Includes Pumping Unit, $\frac{1}{2}$ H. P. Gasoline Engine, Combination Pump and Engine Base, Storage Tank, Air Control, Pressure Gauge, and fittings between pump and tank.

Pumping Unit with Gasoline Engine Less Tank

Complete Pumping Unit includes Pump with Self-Aligning V-Belt Drive, $\frac{1}{2}$ H. P., Air Cooled 4-Cycle, Single Cylinder Gasoline Engine with Foot Pedal Starter, Combination Cast Iron Pump and Engine Base and Relief Valve. Automatic Circuit Breaker to stop pump at desired pressure furnished as optional equipment.



No. T518D

Complete Horizontal Tank Water Systems

Shipped completely assembled, ready to connect.

T518D0—Pumping Unit, mounted on 8-gal. horizontal pneumatic storage tank. Requires space only 15 in. wide by 30 in. long. Supplies ample water under pressure for a small size family.

T512D0—Compact, efficient assembly of Pumping Unit with a 20-gal. horizontal pneumatic storage tank. Requires space only 16x34 in. Adequately meets requirements of average size family.



Repair Kit

Contains cup leathers, valve rubbers, valve springs, cotter keys, air snifter core and complete set of gaskets.

622D0 each \$1.65

$\frac{1}{2}$ H.P. Capacitor Type Heavy Duty Motor. No Radio Interference.

Adjustable Motor Base.

Special Built-in Relief Valve.

Large Discharge and Vacuum Chamber.

Easily Accessible Valves Specially Designed for Balanced Pump Action.


Self Aligning V Belt Drive.

Two Pole Switch with Overload Protection.

Combined Splash and Gravity Feed Oil Lubrication.

Stainless Steel Piston Rod Reduces Wear.

Easily Removed Plunger.



No. T510D

Pumping Unit with Electric Motor Less Tank


This DeLuxe Pumping Unit is built for heavy duty service. It is recommended for average size homes with one bathroom, filling stations, resort homes, etc. Castings are extra heavy, as are power frame, shafting and bearing bushings. Best quality materials used throughout. Maximum working pressure up to 40 lbs.

Complete Vertical Tank Electric Water Systems

Includes Pumping Unit, Relief Valve, Pressure Switch, Pressure Gauge, Air Control, Galvanized Steel Pneumatic Storage Tank, and fittings between tank and pump.

How to Select the Right Size Tank

This Water System can be furnished with an 8, 15, 20, 42 or 120-gallon storage tank. Any of these combinations will take care of a one bathroom home or equivalent. The larger the storage tank, the less often the pumping unit starts and stops, which results in lower operating cost. Larger tanks provide more reserve storage for large sudden withdrawals.



No. T514D

SPECIFICATIONS

$\frac{1}{2}$ H. P. Capacitor; 110 Volt, 60 Cycle, A. C. Motor; Cylinder Bore $1\frac{1}{8}$ in.; Stroke $1\frac{1}{8}$ in.; Suction $\frac{3}{4}$ in.; Discharge $\frac{3}{4}$ in.

No.	Description	Size Tank, Gal.	Overall Size, In.	Shipping Wt, Lbs.	Each
T510D0	Pumping Unit with Motor	Less Tank	30x11x23	114	\$55.90
T518D0	Complete Water System	8	30x15x28	145	63.15
T515D0	Complete Water System	15	30x31x33	162	66.60
T512D0	Complete Water System	20	34x16x33	178	67.70
T514D0	Complete Water System	42	30x35x61	216	74.90
T5112D0	Complete Water System	120	30x35x65	324	98.00

$\frac{1}{2}$ H. P. Gasoline Engine—4 Cycle—Air Cooled—Foot Starter

No.	Description	Size Tank, Gal.	Overall Size, In.	Shipping Wt, Lbs.	Each
F510GD0	Pumping Unit with Engine	Less Tank		152	\$ 87.00
F514GD0	Complete Water System				113.00
F5112GD0	Complete Water System				113.00

★Items Marked Thus ★ Are Shipped from

Prices Net F.O.B. Chicago, Add Freight

RED JACKET "CHIEF" WATER SYSTEMS

FOR MEDIUM SIZED HOMES

350 G.P.H. Oil Lubricated—22 Ft. Suction Lift

$\frac{1}{2}$ H. P. Capacitor Type
Heavy Duty Motor. No
radio interference.

Self Aligning V-Belt
Drive.

Adjustable Motor Base.

Two-pole Switch with
Overload Protection.

Highest Quality Cup
Leathers.


Combined Splash and
Gravity Feed Oil Lub-
rication.

Easily Removed Plunger.

Stainless Steel Piston
Rod reduces wear.

Large Discharge and
Vacuum Chamber.

Double Stuffing Box in-
sures tight seal.




No. F530GD

Pumping Unit with Gasoline Engine Less Tank

Includes Pumping Unit, $\frac{1}{2}$ H. P. Gasoline
Engine, Combination Pump and Engine
Base, Relief Valve and Automatic Aligning
V-Belt Drive. Automatic Circuit Breaker
furnished as optional equipment.

Complete Gasoline Water Systems

Include Pumping Unit, Gasoline Engine,
Combination Base, Storage Tank, Air Con-
trol, Relief Valve, Circuit Breaker, and fit-
tings between pump and tank.



Easily Accessible Valves
Specially Designed for
Balanced Pump Action.


No. T530D

Pumping Unit with Electric Motor Less Tank

A DeLuxe Red Jacket Pumping Unit built
for heavy duty service with extra heavy
castings, power frame, shafting and bear-
ing bushings. Recommended for use in
homes with two bathrooms, summer homes,
filling stations and small schools. Maxi-
mum working pressure up to 40 lbs.

How to Select the Right Size Tank

This Water System can be furnished with
42, 122 or 220 gallon storage tank. Any of
these combinations will take care of a two
bathroom home or equivalent. The larger
the storage tank, the less often the pump-
ing unit starts and stops which results in
lower operating cost. Larger tanks pro-
vide more reserve storage for large sudden
withdrawals.



No. T534D

Complete Electric Water Systems

Includes Pumping Unit,
Relief Valve, Pressure
Switch, Pressure Gauge,
Air Control, Galvanized
Steel Pneumatic Storage
Tank, and fittings be-
tween tank and pump.

SPECIFICATIONS


$\frac{1}{2}$ H. P. Capacitor—110 Volt, 60 Cycle A. C. Motor—Cylinder Bore $1\frac{1}{8}$ In.—Stroke $1\frac{3}{4}$ In.
Suction 1 In.—Discharge $\frac{3}{4}$ In.

No.	Description	Size Tank, Gals.	Overall, Size, In.	Shipping W't, Lbs.	Each
530D0	Pumping Unit with Motor	Less Tank	30x11x21	115	\$ 58.85
534D0	Complete Water System	42	30x35x51	217	77.85
5312D0	Complete Water System	120	30x35x65	325	100.95
5322D0	Complete Water System	220	30x35x77	508	132.60★

$\frac{1}{2}$ H. P. Gasoline Engine—4 Cycle—Air Cooled—Foot Starter

No.	Description	Size Tank, Gals.	Overall, Size, In.	Shipping W't, Lbs.	Each
530GD0	Pumping Unit with Motor	Less Tank	32x22x20	152	\$ 85.80★
534GD0	Complete Water System	42	32x46x51	254	112.30★
5312GD0	Complete Water System	120	32x46x77	548	167.05★

Thus ★ Are Shipped from Factory Only



Repair Kit

Contains cup leathers,
valve rubbers, valve
springs, cotter keys, air
snifter core and complete
set of gaskets.

622D0.....each \$1.65

At F.O. Chicago, Add Freight to _____

RED JACKET "CHIEF" WATER SYSTEMS

FOR LARGE HOMES

500 Gallons per Hour—Oil Lubricated—22-Foot Suction Lift

Adjustable Motor Base.

Large Discharge and Vacuum Chamber.

Two Highest Grade Cup Leathers Removable Through Cylinder Cap.

Flexible Valves and Large Seats, Easily Accessible.

$\frac{1}{2}$ H.P. Capacitor Heavy Duty Motor. No Radio Interference.

Two Pole Switch with Overload Protection.

Self Aligning Double V Belt Drive.

Combined Splash and Gravity Feed Lubrication.

Stainless Steel Piston Rod, Less Wear. Perfect Alignment.

Double Stuffing Box Makes Tight Seal.


No. F550D

Pumping Unit with Electric Motor Less Tank

Large capacity, De Luxe Red Jacket Pumping Unit. Finest quality materials and workmanship. Extra heavy castings, power frame shafting and bearing bushings for heavy duty service. Recommended for large homes with 2 to 4 bathrooms, rural schools, average size dairies, etc. Maximum working pressure up to 40 lbs.

How to Select the Right Size Tank

This Water System can be furnished with a 42, 120 or 220-gallon storage tank. Any of these combinations will take care of a home with 4 bathrooms or more, or its equivalent. The larger the storage tank, the less often the pumping unit starts and stops, which results in lower operating cost. Larger tanks provide more reserve storage for large sudden withdrawals.



No. F550GD

Pumping Unit with Gasoline Engine Less Tank

Includes pump, V-Belt, self-aligning drive $\frac{1}{2}$ H.P. gasoline engine, combination pump and engine base and relief valve. Circuit breaker supplied at slight additional cost.

Complete Gasoline Water Systems

Equipped with gasoline pumping unit, air cooled gasoline engine and storage tank pump and engine base, relief valve, air control, pressure gauge, circuit breaker and fittings between pump and tank.

SPECIFICATIONS

$\frac{1}{2}$ H.P. Capacitor 110 V. 60 Cycle AC Motor—Double V-Belt Drive—Cylinder Bore $1\frac{1}{4}$ in. Stroke 2 in., Suction $1\frac{1}{4}$ in. Discharge 1 in.


No.		Size Tank, in.	Overall Size, in.	Ship. W't, Lbs.	Each
F550D0	Pumping Unit with Motor	Less Tank	31x12x22	155	\$89.60★
F554D0	Complete Water System	42	31x35x51	259	110.10★
F5512D0	Complete Water System	120	31x35x65	367	133.20★
F5522D0	Complete Water System	220	31x35x77	550	164.85★

$\frac{1}{2}$ H.P. Gasoline Engine—4 Cycle—Air Cooled—Foot Starter

No.		Size Tank, in.	Overall Size, in.	Ship. W't, Lbs.	Each
F550GD0	Pumping Unit with Engine	Less Tank	33x12x22	155	\$103.55★
F5512GD0	Complete Water System	120	33x35x51	259	154.85★
F5522GD0	Complete Water System	220	33x35x65	367	186.40★

★Items Marked Thus ★ Are Shipped from

Prices Net F.O.B. Chicago, Add Freight



No. F554D

Complete Electric Water Systems

Include pumping unit, relief valve, pressure switch, pressure gauge, air control, galvanized steel pneumatic storage tank, and fittings between tank and pump.




Repair Kit

Contains cup leathers, valve rubbers, valve springs, cotter keys, air snifter core and complete set of gaskets.


622D0.....each \$1.65

RED JACKET Automatic Demonstrators

*Deliver Running Water
anywhere you place them!*



No. T4064D



No. T508 1/2 D

**LET IT WORK FOR YOU ON THE SIDEWALK OUTSIDE YOUR
STORE, AT THE CHURCH BAZAAR OR SCHOOL PICNIC**

Selling Helps Furnished with Demonstrator Units

1. Consumer Price Cards.
2. Wall Posters.
3. Dealer Identification Sign.
4. Consumer Broadsides.
5. Industry Booklets, "RUNNING WATER."
6. Water System Circulars.
7. Water Softener and Filter Circulars.
8. Hand and Windmill Circulars.
9. Well Accessory Circulars.
10. Demonstrator Instruction Card.

Deep Well Water System Demonstrator

Complete with Knotty Pine Display Base, Reservoir and piping. 42 gal. Tank, w't each 360 lbs.

T4064D0each \$134.55

Shallow Well Water System Demonstrator

Complete with Knotty Pine Display Base, Reservoir and piping. Shipped completely assembled ready to operate.

With 8 Gallon Tank, w't each 175 lbs.

T508 1/2 D0each \$62.75

With 20 Gallon Tank, w't each 220 lbs.


T502 1/2 D0each \$67.30

RED JACKET DEEP WELL WATER SYSTEMS

Red Jacket Deep Well Water Systems are dependable, economical, complete, and include many exclusive patented Red Jacket features which insure quiet, economical service over a long period of years. Red Jacket Deep Well Pumping Heads occupy considerably less floor space and head room because of their extremely compact design.

These dependable pumping heads and deep well water systems all feature Rolling Power. This eliminates crossheads, walking beams, lever arms, connecting rods and wrist pins. Consequently, there is no sliding friction and the usual resulting wear of parts.

The motors used on Red Jacket Deep Well Pumping Heads are always smaller than those used on other pumps of similar capacity. This is made possible by the greater efficiency of Red Jacket's **Rolling Power**. Naturally, this results in substantial savings in the operating cost.




Operation of Red Jacket-Dorward "Rolling Power" Deep Well Pumping Head

1. Pump pulley mounted on hardened steel drive shaft turns pinion gear. Pinion gear meshes with main rotor gear and transmits power to rotor.

2. Sturdy rotor revolves on dual set of hardened steel roller bearings reducing friction to a minimum.



3. Crankshaft, mounted in rotor, has pinion gear on opposite end from crank. Pinion gear meshes with stationary internal gear which causes crankshaft to revolve in opposite direction to rotor and moves plunger rod up and down in a fixed vertical line without the use of cumbersome power wasting cross heads, lever arms, connecting rods or walking beams.

4. All moving parts revolve in pool of oil for perfect lubrication.



Sliding Head

Grooved tracks in pumping head base permit the easy sliding of the head into pumping position where it is firmly held by heavy machine bolts. Whenever it is necessary to remove plunger rod or drop pipe from well, it is an easy matter to loosen machine bolts and slide head back out of position. No lifting required. This provides access to well for pulling plunger rod or drop pipe.



REVERSIBLE ROTOR FEATURE Doubles Service Life


The "Rolling Power" unit used in the Red Jacket Deep Well pumping head may be rotated in either direction. After a number of years of service, the direction of the "Rolling Power" unit may be reversed, with practically the same results as installing a new unit. Only Red Jacket has this extra feature which practically doubles the life of the Pumping Head.

ORDERING INFORMATION

The Selection Chart on the following page makes it possible to select the proper deep well water system and order it as a complete packaged unit. Order by system number and specify the number of feet of drop pipe and rod required. Electric current is other than 110 volts, 60 cycles.

True Value "DE LUXE" ELECTRIC WASHERS

The finest washer in America. You can pay more but you cannot get finer washing quality. DeLuxe in truth as well as name. Check over the outstanding features. Turns out lovely, fresh, spotless clothes without wear or tear. Your clothes will last longer. Largest size tub, largest agitator and most massive safety wringer enables you to turn out the largest washings in shortest time. Order today and save your time, money, health and clothes.



- **Massive Chamberlain De Luxe Wringer**, top of heavy stamped steel, cadmium plated, aluminum finish; Drain Board heavy die cast aluminum. Hand rest gives protection to your hands. Touch on large safety bar releases all pressure. Big 2 1/4 in. balloon rubber rolls. Massive pressure reset lever. Pressure regulating wheel on underside of top bar. Reversible automatically controlled water shed. Locks in 8 positions.
- **Oversize Agitator**, twenty per cent greater in washing area than standard size. Triple vane design creates surging, swishing water action. No injury to clothes because dirt is washed out, not scrubbed out. Washes clothes quicker and faster without injury than other machines. Made of cast aluminum, wire brushed, satin finish. Diameter 13 in.
- **Oversize Tub**, holds 18 gallons to washing line, clothes capacity 8 dry pounds, usually called 8 sheet size. Made from one piece of heavy special enameling steel, fired with two coats of vitreous porcelain enamel. Dome type cover made of heavy steel, rust-proofed.
- **Streamlined Chassis-Column Type Legs**. Massive, streamlined "Kettle Type" base built like a bridge entirely of heavy steel.

W837H0—110 A.C., 60 cycle, shipping w't about 190 lbs.....

Motor and mechanism suspended from steel base plate without strain on tub. Rubber pads on top of base plate provide cushion for tub. Inset, extra deep, column type legs reduce vibration and add life to washer. Reinforced with steel cross members; 2 1/2 in. oversize rubber casters, free rolling.

● **Quick Release Drain**, touch of finger opens or closes. Chromium plated control. Live rubber ball valve. Strainer over outlet. Female fitting for hose.

● **Oiled for life Motor**. General Electric 1/4 H. P. Never requires oiling. Heavy overload capacity.

● **Precision Transmission**. Machine cut gears of steel and grey iron. Has steel connecting rod instead of usual cast iron type. See full description on preceding page. The best transmission made. Millions in use to day. This is the heart of the washer and means long life.

● **Finish**. Tub finished in beautiful vitreous porcelain. All other surfaces extra heavy enamel finish. New Synthetic. Note the high quality of the finish to ordinary

True Value "SUPER" ELECTRIC WASHER

Washes everything from finest silks to overalls. Oversize Agitator; Fine Lovell wringer, full bar release; full family size tub and other features give you a machine which is hard to beat at any price. Turns out clothes snowy white and exquisitely clean. You will get a new thrill out of wearing clothes washed in the Super *True Value* Washer. The price is so reasonable, be sure to order today.



• **Lovell Wringer.** Heavy stamped steel frame, cadmium plated and rust-proofed, aluminum finish. Big self adjusting balloon rolls. Touch the bar to release the rolls. Pressure regulator and pressure reset lever. Automatically controlled, reversible water shed. High side wall drain board. Hand rest and clothes guide to rolls. Locks in eight positions.

• **Oversize Agitator.** Twenty per cent greater in washing area than standard size. Triple van design creates 18 surging water currents forcing soapy suds through every particle of your clothes and bringing them out spotlessly clean. Made of cast aluminum, wire brushed, satin finish. Diameter 13 in.

• **Full Family Size Tub.** Holds 16 gallons to washing line. Clothes capacity 6 dry pounds, usually called 6 sheet size. Porcelain enameled, double coated inside and outside. Extra deep, non-plash rim. Water, extra strong of heavy steel, rust-proofed. Hand rest, chrome plated cover handle.

• **Vertical Agitator Control.** Chrome plated. Operated by hand or foot. Modernistic, column type legs. From base plate to top of agitator seat for

• **Precision Transmission.** The same wonderful transmission, described on a preceding page, comes in all *True Value* Washers. If you are mechanically minded read this description. If you are not, just know that it is the finest transmission engineers can produce and will give you years of service. That is all you really have to know about the transmission. It has given service in over a million homes. **A Million American Women Can't Be Wrong.**

• **Quick Release Drain.** Labor saving, rust proof, non-corroding. Strainer over outlet. Female thread for hose connection. Chrome plated handle.

• **Oiled-for-life Motor.** General Electric, 1/4 H.P. Never requires oiling. Every component part of this washing machine is the best for the purpose intended.

• **Finish.** Tub finish in "Beige," gleaming vitreous porcelain enamel. All other surfaces, except wringer, finished in blending shade of Beige, by new process synthetic enamel, baked on and giving beautiful, glossy sheen.


Weight 170 lbs.

et F.C. t, p, Chicago, Add Freight to

each \$59.95

True Value "SPECIAL" ELECTRIC WASHER

We have told you on a preceding page about the wonderful power plant in all *True Value* Washers. The *True Value* Special Washer has a full family size tub, a full standard size agitator, efficient Lovell wringer with pressure release. Think of the price and then remember the years of service in store for you with this machine. You cannot afford to turn down this great buy if you are in the market for a washing machine at all and feel you must economize on price. Order it today.



● **Lovell Wringer.** "Target type" pressure release, positive and easy to reset. Exclusive "hand fitting" pressure regulator. Rugged steel frame, rust-proofed, aluminum finish. Manually controlled reversible water shed. High side wall drainboard—2 in. rubber rolls.

● **Agitator.** Famous *True Value*, triple vane, double wing design which creates a surging, turbulent water action. Rapid turnover of clothes without wear on fabric. Made of cast aluminum wire brushed, satin finish. 11 in. diameter. Automobile lever type agitator control, located on side of machine. Not necessary to dip hands in water to start or stop like some machines at this low price.

● **Standard, family size tub.** Holds 16 gal. to washing line. Clothes capacity 6 dry pounds, usually called 6 sheet size. Porcelain enameled, double coated, inside and outside. Heavy steel, rust-proofed cover. Convenient cover handle.

● **All Steel Chassis.** Motor and transmission suspended from base plate without strain on porcelain. Four rubber pads afford

cushion seat for tub. Legs reinforced with steel cross members. Free rolling rubber casters, 2 in. diam.

● **Standard faucet type drain.** Strainer over outlet. Will not corrode or clog. Male fitting for hose.

● **Precision Transmission.** Machine cut gears of steel and grey iron. Steel connecting rod instead of cast iron as in some washers. This transmission makes the *True Value* Special Washer the best buy in the low priced field. In fact, the same transmission is used in our highest price machine.

● **Oiled-for-life Motor.** General Electric $\frac{1}{4}$ H.P. Motor. Never requires oiling. Heavy overload motor. With such a motor, transmission, tub and wringer as you have in the *True Value* Special Washer, you can't go wrong.

● **Finish.** Tub finished in "vitreous enamel" with a blending shade on and giving

W637H
\$44.95
RETAIL

W637H0—100 A. C., 60 cycle. Shipping w't about 160 lbs.

Prices Net F.O.B. Chicago, Add Freight

True Value "SUPER" GASOLINE WASHERS

Exactly like the *True Value* Super Electric Washer shown on page 1167 except powered by the new type Briggs-Stratton four-cycle gasoline engine, instead of the G. E. $\frac{1}{4}$ H. P. Electric Motor. Costs no more to run than an electric motor and gives wonderful service for farm or city homes without electricity. Any woman can run it. Ample power to operate both washer and wringer. No woman anywhere has an excuse to be without a *True Value* Washer. Order yours today.

Washes everything from finest silks to overalls. Oversize Agitator; Fine Lovell wringer, full bar release; full family size tub and other features give you a machine which is hard to beat at any price. Turns out clothes snowy white and exquisitely clean. You will get a new thrill out of wearing clothes washed in the Super *True Value* Washer. The price is so reasonable, be sure to order today.

Quick Release Drain. Labor saving, rust proof, non-corroding. Strainer over outlet. Female thread for hose connection. Chrome plated handle.

Full Bar Type Pressure Release. Touch of safety bar releases all pressure instantly. Simple to reset.

Finish. Tub finish in "Beige," gleaming vitreous porcelain enamel. All other surfaces, except wringer, finished in blending shade of Beige, by new process synthetic enamel, baked on and giving beautiful, glossy finish.

Lovell Wringer. Heavy stamped steel frame, cadmium plated and rust-proofed, aluminum finish. Big self adjusting balloon rolls. Touch the bar to release the rolls. Pressure regulator and pressure reset lever. Automatically controlled reversible water shed. High side wall drain board and clothes guide to rolls. Locks eight positions. Lovell wringer does a large part of the work in wringing clothes. The kind you



W937H
\$89.95
RETAIL

• **Oversize Agitator.** Twenty per cent greater in washing area than standard size. Triple vane design creates 18 surging water currents forcing soapy suds through every particle of your clothes and bringing them out spotlessly clean. Made of cast aluminum wire brushed satin finish. Diameter 13 in.

• **Full Family Size Tub.** Holds 16 gallons to washing line. Clothes capacity 6 dry pounds, usually called 6 sheet size. Porcelain enameled, double coated inside and outside. Extra deep, non-splash rim. Dome cover, extra strong of heavy steel, rust-proofed. Hand fitting chrome plated cover handle.

• **Extra Deep Steel Chassis Column Type Legs.** Modernistic, streamlined. Motor and transmission suspended from base plate without strain on tub. Four rubber pads afford cushion seat for tub. Oversize rubber casters.

• **Precision Transmission.** The same wonderful transmission, described on a preceding page, comes in all *True Value* Washers. If you are mechanically minded read this description. If you are not, just know that it is the finest transmission engineers can produce and will give you years of service. That is all you really have to know about the transmission. It has given service in over a million homes. **A Million American Women Can't Be Wrong.**

• **Gas Engine**—New type Briggs-Stratton four cycle gasoline engine, $\frac{1}{2}$ H.P. Gas Carburetor, mixing gas and oil not necessary. Belt drive, three-to-one safety factor. Simply step on foot pedal to start. Compact, smooth running. Mounted through rubber cushions on heavy steel base. Finest engine made for washing machines. Complete with six foot flexible metal exhaust and muffler.

Accessories included with machine.

Gasoline Engine, shipping w't about 180 lbs..... each \$89.95

et F.C. & F. Chicago, Add Freight to _____

**MODERNIZE
AND BEAUTIFY
YOUR HOME WITH
Hillbald
PLUMBING GOODS**

*Highest in Quality
Finish and Design*